

Pre-Cx Inspections/Site Visits				8	8	8		1	\$2,960		3	1					1			
Attend Start-ups				24	16	16		1	\$6,880		7	5					1			
	2008	\$42	\$100	\$120	\$130	\$120	\$140					0	0	0	0		1,280	4,560	3,900	\$9,740
Task 4 - FPT - Div 16 - Electrical/Fire/Lighting									\$22,080	7%		0	0	0	0	0	1	3	2	
General development - detailed FPTs and test plans						16		1	\$1,920											
General Electrical System Commissioning						24		1	\$2,880		3									
Review test agency work plan						8		1	\$960		1								1	
Coordinate/Witness FPT power system testing on power distribution system						24		1	\$2,880		3							1		
Commission Lighting Control System						16		1	\$1,920		2							1		
Coordinate/Witness FPT ATS Equipment						24		1	\$2,880		3							1		
Coordinate/Witness FPT Emergency Generators						32		1	\$3,840		4								1	
Coordinate/Witness Fire Alarm System						24		1	\$2,880		3									
Retesting allowance						16		1	\$1,920		2						1			
	2008	\$42	\$100	\$120	\$130	\$120	\$140					3,539	0	0	0		5,120	7,600	13,650	\$29,909
Task 5 - FPT HVAC/Controls/Mechanical Systems									\$128,540	42%		64	0	0	0	0	4	5	7	
General development - detailed FPTs and testing plans	x								\$5,040											
Review TAB reports, select 10% sample, witness	x								\$6,000		6	3						1		
HVAC Equipment/Systems FPTs																				
Unitary/Hydronic																				
FPT of hydronic components (strainers), 20% sample, review TAB & pressure tests	x							1	\$2,000		2	1								
FPT Exhaust Fans/Lab Fans (100% sample of 8)	x							8	\$2,000		2	1								
FPT Supply/Return Fans (100% sample of 5)	x							5	\$1,250		1.25	1								
FPT HVAC Pumps (100% sample of 11)	x							11	\$2,750		2.75	1								
FPT DHW System (100% sample)	x							1	\$1,000		1	1							1	
FPT DHW Pumps (100% sample of 3)								3	\$750		0.75	1								
FPT Miscellaneous Terminal Units	x							1	\$1,000		1							1		
AHU/Packaged Units																				
FPT Main AHUs (100% sample of 4)	x							4	\$10,000		10	5							1	
FPT Clean RoomAC Unit (100% sample 26)								26	\$19,500		19.5	10							2	
FPT Packaged Rooftop AC Unit (100% sample 2)	x							2	\$2,000		2	2					1			
FPT Computer Room AC Unit (100% sample of 1)	x							1	\$750		0.75									
Chillers/Central Plant																				
FPT Cooling Towers (100% sample of 2)	x							2	\$2,000		2	1								
FPT Electric Centrifugal Chiller (100% sample of 1)	x							1	\$3,000		3	1								
FPT Steam Absorption Chiller (100% sample 1)	x							1	\$3,000		3	1								
FPT Process Cooling Heat Exchanger (100% sample of 1)								1	\$1,000		1	1								
FPT Tower Water Treatment System	x							1	\$1,000		1	1								
FPT CHW Primary/Secondary System	x							1	\$3,000		3	1								
FPT HW Secondary System	x							1	\$2,000		2	1								
FPT Process CHW Distribution								1	\$3,000		3	1								
FPT Process CHW Pumps								2	\$500		0.5	1								
FPT Heat Exchangers (100% sample of 2)	x							2	\$2,000		2	1							1	
FPT ATC Compressed Air/Dryer Systems	x							1	\$500		0.5	1								
Terminal Units FPTs																				
FPT VAV Boxes (20% sample of 119)	x							24	\$6,000		6	3						1		

[illegible]