



HRV-1 Point List																
Point	System and Service		Sensor		Features						Notes					
Name	Number [BACnet Object ID], Note 7		Type	Accuracy	Alarms				Trending							
					Limit		Warning		Samples1	Commissioning5			Operating5			
					Hi	Lo	Hi	Lo		Time2	Local3		Archive4	Time2	Local3	Archive4
<b>Analog Inputs</b>																
Outdoor air temperature		Outdoor air temperature	Vaisala HMT 330						60	1 min	✓	✓	1 min	✓	✓	Note 18, 21
Outdoor air humidity		OA humidity for reference/performance assessment	Vaisala HMT 330						60	1 min	✓	✓	1 min	✓	✓	
Supply filter differential pressure		Supply filter differential pressure	0-2 in.w.c. input,, 4-20 ma output transmitter	+/-1% full scale					24	1 hour	✓	✓	1 day	✓	✓	Note 6
Enthalpy wheel supply side leaving air temperature		Heat wheel discharge temperature	Flexible averaging 1,000 Ω Pt RTD with close coupled transmitter	Note 8, 9					60	1 min	✓	✓	1 min	✓	✓	Note 18
Supply air temperature		Electric heating coil leaving air temperature	Flexible averaging 1,000 Ω Pt RTD with close coupled transmitter	Note 8, 9					60	1 min	✓	✓	1 min	✓	✓	Note 18
Entering exhaust air temperature		Exhaust air temperature entering the heat wheel	Flexible averaging 1,000 Ω Pt RTD with close coupled transmitter	Note 8, 9					60	1 min	✓	✓	1 min	✓	✓	Note 22
Exhaust filter differential pressure		Exhaust filter differential pressure	0-2 in.w.c. input,, 4-20 ma output transmitter	+/-1% full scale					24	1 hour	✓	✓	1 day	✓	✓	Note 6
Leaving exhaust air temperature		Exhaust air temperature leaving the heat wheel	Flexible averaging 1,000 Ω Pt RTD with close coupled transmitter	Note 8, 9					60	1 min	✓	✓	1 min	✓	✓	Note 22
Supply fan amps		Supply fan amps for proof of operation and energy	Current transformer						60	1 min	✓	✓	1 min	✓	✓	Note 7
Exhaust fan amps		Exhaust fan amps for proof of operation and energy	Current transformer						60	1 min	✓	✓	1 min	✓	✓	Note 7
Heat wheel amps		Heat wheel amps for proof of operation and energy	Current transformer						60	1 min	✓	✓	1 min	✓	✓	Note 7
Enthalpy wheel pressure drop - Supply side		Enthalpy wheel supply side pressure drop	0-2 in.w.c. input,, 4-20 ma output transmitter	+/-1% full scale					24	1 hour	✓	✓	1 day	✓	✓	
Enthalpy wheel pressure drop - Exhaust side		Enthalpy wheel exhaust side pressure drop	0-2 in.w.c. input,, 4-20 ma output transmitter	+/-1% full scale					24	1 hour	✓	✓	1 day	✓	✓	
EF-1 inlet static pressure		Static on building side of back draft damper	0-0.25 in.w.c. input,, 4-20 ma output transmitter, Dwyer MS-121	+/-1% full scale					60	1 min	✓	✓	1 min	✓	✓	Note 19
EF-2 inlet static pressure		Static on building side of back draft damper	0-0.25 in.w.c. input,, 4-20 ma output transmitter, Dwyer MS-121	+/-1% full scale					60	1 min	✓	✓	1 min	✓	✓	Note 19
EF-3 inlet static pressure		Static on building side of back draft damper	0-0.25 in.w.c. input,, 4-20 ma output transmitter, Dwyer MS-121	+/-1% full scale					60	1 min	✓	✓	1 min	✓	✓	Note 19
EF-6 inlet static pressure		Static on building side of back draft damper	0-0.25 in.w.c. input,, 4-20 ma output transmitter, Dwyer MS-121	+/-1% full scale					60	1 min	✓	✓	1 min	✓	✓	Note 19
EF-7 inlet static pressure		Static on building side of back draft damper	0-0.25 in.w.c. input,, 4-20 ma output transmitter, Dwyer MS-121	+/-1% full scale					60	1 min	✓	✓	1 min	✓	✓	Note 19
EF-8 inlet static pressure		Static on building side of back draft damper	0-0.25 in.w.c. input,, 4-20 ma output transmitter, Dwyer MS-121	+/-1% full scale					60	1 min	✓	✓	1 min	✓	✓	Note 19
<b>Analog Outputs</b>																
Electric heat stage 1 SCR		Modulates 1st stage of electric heat	4-20 ma output	N/A					60	1 min	✓	✓	1 min	✓	✓	Note 13
<b>Digital Inputs</b>																
HRV-11 safety trip		Annunciates a safety shut down of the AHU	Note 10	N/A					10	COV	✓	✓	COV	✓	✓	
Frost control indication		Annunciates when a frost control cycle is in progress	Note 11	N/A					10	COV	✓	✓	COV	✓	✓	
<b>Digital Outputs (All digital outputs to include local override capability and indication)</b>																
HRV-1 Enable		AHU-1 supply fan start/stop command	Relay output	N/A					10	COV	✓	✓	COV	✓	✓	Note 12
Electric heat enable		Enables electric heat	Relay output	N/A					10	COV	✓	✓	COV	✓	✓	Note 13
Outdoor air damper		HRV-1 Outdoor air damper	Factory mounted and wired	N/A					0	N/A	N/A	N/A	N/A	N/A	N/A	Note 12
Exhaust air damper		HRV-1 Exhaust air damper	Factory mounted and wired	N/A					0	N/A	N/A	N/A	N/A	N/A	N/A	Note 13
EF-1 start/stop		Starts and stops EF-1	Relay output	N/A					10	COV	ü	ü	COV	ü	ü	Note 20
EF-2 start/stop		Starts and stops EF-1	Relay output	N/A					10	COV	ü	ü	COV	ü	ü	Note 20
EF-3 start/stop		Starts and stops EF-1	Relay output	N/A					10	COV	ü	ü	COV	ü	ü	Note 20
EF-7 start/stop		Starts and stops EF-1	Relay output	N/A					10	COV	ü	ü	COV	ü	ü	Note 20
EF-8 start/stop		Starts and stops EF-1	Relay output	N/A					10	COV	ü	ü	COV	ü	ü	Note 20
<b>Hardwired and Safety Interlocks (Hardwired to shut down the system. Safeties shall function no matter what position the equipment's Hand-Off-Auto, Inverter-Bypass, or other selector switches are in)</b>																
Freezestat		Low discharge temperature safety	Hardwired	N/A					0	N/A	N/A	N/A	N/A	N/A	N/A	Note 15
Electric heat high limit		High limit lock-out	Hardwired	N/A					0	N/A	N/A	N/A	N/A	N/A	N/A	
Hoistway Vent Damper Interlock		Hoistway Vent	Hardwired	N/A					0	N/A	N/A	N/A	N/A	N/A	N/A	Note 16
EF-6 start/stop		Starts and stops EF-1	Hardwired interlock from switch at the hood.	N/A					0	N/A	N/A	N/A	N/A	N/A	N/A	Note 17
<b>Virtual Points</b>																
Supply air temperature set point		Heat wheel leaving air temperature set point	Logic generated	N/A					5	COV	✓	✓	COV	✓	✓	
Fire alarm shut down		Fire alarm system interlock	Logic generated	N/A					0	N/A	N/A	N/A	N/A	N/A	N/A	Note 14
<b>Notes:</b>																
1.	Samples indicates the minimum number of data samples that must be held in the local controller if it is trending the point.															
2.	Time indicates the required sampling time for the trending function.															
3.	A check in the local column indicates that the trending only needs to be running in the local controller and the most recent value can write over the last value when the trend buffer fills up.															
4.	A check in the archive column indicates that the trend data must be archived to the system hard disc when trend buffer fills up so that a continuous trend record is maintained.															
5.	Commissioning trending requirements only need to be implemented during the start-up and warranty year. After the start-up and warranty process, the control contractor should set the trending parameters to the operating requirements listed if they differ from the commissioning requirements.															
6.	Use flow and pressure drop to trend filter life cycle cost and trigger filter changes based on life cycle cost. See control logic and narrative for additional information.															
7.	Monitor amps to provide a proof of operation in put and create a virtual meter to track energy use using voltage and power factor constants determined during commissioning. Accumulate and display current demand level, kWh for the day, and kWh for the previous day, calendar month, and calendar year. Archive data to the data to the dedicated archival data storage drive in the City's Data Center. See Network Diagram.															
8.	0.75% of span for sensor plus transmitter combined.															
9.	2 feet of element for every 4 sq.ft. of duct area, 6 ft. minimum length.															
10.	Wire safety devices to pilot a relay and keep it energized in normal operation so that a safety trip de-energizes the relay. Use relay contacts to interlock the supply fan VFD, the exhaust fan VFD, and to provide a digital status input to the DDC system. Safeties shall function no matter what the position of the starter Hand-Off-Auto selector switch is.															
11.	Provide interface relay (one per point) wired per vendor wiring diagrams. Verify the interface relay current draw with both relays energized will not overload the vendor's control power transformer.															
12.	Enable point allows factory control circuit to start and stop the various motors, drives and actuators associated with the AHU.															
13.	Multistage electric resistance heater shall have an SCR for the first stage. Logic shall be arranged to provide modulated capacity through the entire operating range by coordinating the operation of the SCR controlled stage with the remaining across the line stages.															
14.	A common signal from a dry contact on the fire alarm control panel shall be used by the DDC system to trigger a fire alarm shut down of all HVAC systems on alarm. Systems to go through a normal restart when the fire alarm is cleared.															
15.	Respond to the coldest temperature over 12 continuous inches of the element.															
16.	Wired to the fire alarm system and arranged to open the vent damper on alarm. Coordinate with the fire alarm contractor and City of Seattle Code requirements.															
17.	Hard wire the hood switch to interlock it with the exhaust fan, the intake damper and the MUAU.															
18.	Perform a relative calibration of this point relative to the other temperature points in the same air stream using the outdoor air temperature sensor as a reference. Adjust the zero of the other sensors so all sensors agree when immersed in a well stirred bucket of ice water. Adjust the span of the other sensors so the all agree when subject to an air stream at the same temperature (heat wheel off, electric heat off).															
19.	Monitor pressure to provide a proof of operation in put and create a virtual meter to track energy use using amperage, voltage and power factor constants determined during commissioning.. Accumulate and display current demand level, kWh for the day, and kWh for the previous day, calendar month, and calendar year. Archive data to the data to the dedicated archival data storage drive in the City's Data Center. See Network Diagram.															
20.	Provide horsepower rated relay at the exhaust fan location, functional devices RIBM24ZL or equal. See detail on M5.11.															
21.	Coordinate with the Architect, mechanical designer, commissioning provider, control designer, and operating team to select a location for the outdoor air conditions sensor in the field during construction. Anticipate a wiring run with-in 25 feet of the sensor location shown on the drawings.															
22.	Perform a relative calibration of this point relative to the other temperature points in the same air stream using the heat wheel entering air temperature sensor as a reference. Adjust the zero of the other sensors so all sensors agree when immersed in a well stirred bucket of ice water. Adjust the span of the other sensors so the all agree when subject to an air stream at the same temperature (heat wheel off, electric heat off).															
23.	Create a virtual proof of operation point based on this analog input. Coordinate with the balancer and commissioning provider during start-up to determine the appropriate set point.															

**Weinstein A+U**  
Architects + Urban Designers LLC  
2200 Western Avenue Suite 301  
Seattle, WA 98121  
T 206 443 8806  
F 206 443 1218  
Weinsteinau.com

© 2013 Weinstein AU - These documents have been prepared specifically for the above named project. They are not suitable for use on other projects or in other locations without the approval and participation of the Architect.



NW Satellite Office  
8560 North Buchanan Avenue  
Portland, Oregon, 97203  
Phone: (503) 286-1494  
DSellers@FacilityDynamics.com

Corporate Office  
6760 Alexander Bell Drive, Suite 200  
Columbia, MD 21046  
Phone: (410) 290-0900  
www.FacilityDynamics.com



**CITY OF SEATTLE**

**Fire Station 22**  
901 E. Roanoke St.  
Seattle WA 98102

**100% CD SET**



**100% CONSTRUCTION DOCUMENTS**

PROJECT-NO	13004
DRAWN	DA5
CHECKED BY	CBM
DATE	1/11/16
REVISIONS	DATE
△	
△	
△	
△	
△	
△	
△	
SHEET TITLE	<b>HRV-1 Point List</b>
SHEET NUMBER	<b>TC 0.10</b>

HRV-2 Point List																
Point		System and Service		Sensor		Features						Notes				
Name	Number [BACnet Object ID], Note 7	Type	Accuracy	Alarms				Trending								
				Limit		Warning		Samples1	Commissioning5			Operating5				
				Hi	Lo	Hi	Lo		Time2	Local3	Archive4	Time2	Local3	Archive4		
<b>Analog Inputs</b>																
	Supply filter differential pressure	Supply filter differential pressure	0-2 in.w.c. input., 4-20 ma output transmitter	+/-1% full scale					24	1 hour	✓	✓	1 day	✓	✓	Note 6
	Heat exchanger supply side leaving air temperature	Heat exchanger discharge temperature	Flexible averaging 1,000 Ω Pt RTD with close coupled transmitter	Note 8, 9					60	1 min	✓	✓	1 min	✓	✓	Note 18
	Entering exhaust air temperature	Exhaust air temperature entering the heat wheel	Flexible averaging 1,000 Ω Pt RTD with close coupled transmitter	Note 8, 9					60	1 min	✓	✓	1 min	✓	✓	Note 19
	Exhaust filter differential pressure	Exhaust filter differential pressure	0-2 in.w.c. input., 4-20 ma output transmitter	+/-1% full scale					24	1 hour	✓	✓	1 day	✓	✓	Note 6
	Leaving exhaust air temperature	Exhaust air temperature leaving the heat wheel	Flexible averaging 1,000 Ω Pt RTD with close coupled transmitter	Note 8, 9					60	1 min	✓	✓	1 min	✓	✓	Note 19
	Supply fan amps	Supply fan amps for proof of operation and energy	Current transformer						60	1 min	✓	✓	1 min	✓	✓	Note 7
	Exhaust fan amps	Exhaust fan amps for proof of operation and energy	Current transformer						60	1 min	✓	✓	1 min	✓	✓	Note 7
	Supply fan speed command	Commands fan speed for different operating modes	4-20 ma output						60	1 min	✓	✓	1 min	✓	✓	Note 7
	Exhaust fan speed command	Commands fan speed for different operating modes	4-20 ma output						60	1 min	✓	✓	1 min	✓	✓	Note 7
	Heat exchanger pressure drop - Supply side	Enthalpy wheel supply side pressure drop	0-2 in.w.c. input., 4-20 ma output transmitter	+/-1% full scale					24	1 hour	✓	✓	1 day	✓	✓	
	Heat exchanger pressure drop - Exhaust side	Enthalpy wheel exhaust side pressure drop	0-2 in.w.c. input., 4-20 ma output transmitter	+/-1% full scale					24	1 hour	✓	✓	1 day	✓	✓	
	Space temperature	Bunker area space temperature	1,000 Ω Pt RTD space with close coupled transmitter	+/-1% full scale					24	1 hour	✓	✓	1 day	✓	✓	
	Space temperature set point adjustment	Set point adjustment on space temperature sensor	Integral with space temperature sensor						60	1 min	✓	✓	1 min	✓	✓	
	Unit Heater 1 Flue Temperature	Thermocouple with 4-20 ma transmitter	+/- 3°F						60	1 min	✓	✓	5 min	✓	✓	Note 7
	Destratification fan amps	Fan amps for proof of operation and energy	Current transformer						60	1 min	✓	✓	1 min	✓	✓	Note 7
<b>Digital Inputs</b>																
	Spring wound interval timer	AHU-2 high speed operating mode control	12 hour, No hold, DPDT Spring Wound Timer	N/A					10	COV	✓	✓	COV	✓	✓	
	HRV-2 safety trip	Annunciates a safety shut down of the AHU	Note 10	N/A					10	COV	✓	✓	COV	✓	✓	
<b>Digital Outputs (All digital outputs to include local override capability and indication)</b>																
	HRV-2 Enable	Enables HRV-2 fans and internal interlocks	Relay output	N/A					10	COV	✓	✓	COV	✓	✓	Note 12
	UH-1 Fan Start/Stop	Starts and stops the unit heater fan	Relay output	N/A					10	COV	✓	✓	COV	✓	✓	
	UH-1 Stage 1 Heat	Turns the gas valve on and off	Relay output	N/A					10	COV	✓	✓	COV	✓	✓	
	DF-1 Enable	Enables destratification fan SF-1	Relay output	N/A					10	COV	✓	✓	COV	✓	✓	Note 12
<b>Safety Interlocks (Hardwired to shut down the system. Safeties shall function no matter what position the equipment's Hand-Off-Auto, Inverter-Bypass, or other selector switches are in)</b>																
	Fire alarm shut down	Fire alarm system interlock	Software programmed based on fire alarm system input	N/A					0	N/A	N/A	N/A	N/A	N/A	N/A	Note 14
	Freezestat	Low discharge temperature safety	Hardwired	N/A					0	N/A	N/A	N/A	N/A	N/A	N/A	Note 15
<b>Network Points</b>																
	Supply fan VFD network card	Provides access to onboard VFD data and diagnostics	BACnet or Siemens P2 Network Card	N/A					0	N/A	N/A	N/A	N/A	N/A	N/A	Note 17
	Exhaust fan VFD network card	Provides access to onboard VFD data and diagnostics	BACnet or Siemens P2 Network Card	N/A					0	N/A	N/A	N/A	N/A	N/A	N/A	Note 17
<b>Virtual Points</b>																
	High speed cycle temperature set point	Controls UH-2 during the high speed cycle	Logic generated, Note 18	N/A					5	COV	✓	✓	COV	✓	✓	
	Normal cycle temperature set point	Controls UH-2 during the normal cycle	Logic generated, Note 18	N/A					5	COV	✓	✓	COV	✓	✓	
	UH-2 temperature control differential	Supply flow set point	Logic generated	N/A					5	COV	✓	✓	COV	✓	✓	
	Low speed supply fan set point	Heat wheel leaving air temperature set point	Logic generated	N/A					5	COV	✓	✓	COV	✓	✓	
	High speed supply fan set point	Frost control set point for leaving exhaust air	Logic generated	N/A					5	COV	✓	✓	COV	✓	✓	
	Low speed exhaust fan set point	Supply flow set point	Logic generated	N/A					5	COV	✓	✓	COV	✓	✓	
	High speed exhaust fan set point	Exhaust flow set point	Logic generated	N/A					5	COV	✓	✓	COV	✓	✓	
	Power failure recovery	Internal point monitoring controller power	Used to trigger a power failure recovery sequence	N/A					5	COV	✓	✓	COV	✓	✓	
<b>Notes:</b>																
1.	Samples indicates the minimum number of data samples that must be held in the local controller if it is trending the point.															
2.	Time indicates the required sampling time for the trending function.															
3.	A check in the local column indicates that the trending only needs to be running in the local controller and the most recent value can write over the last value when the trend buffer fills up.															
4.	A check in the archive column indicates that the trend data must be archived to the system hard disc when trend buffer fills up so that a continuous trend record is maintained.															
5.	Commissioning trending requirements only need to be implemented during the start-up and warranty year. After the start-up and warranty process, the control contractor should set the trending parameters to the operating requirements listed if they differ from the commissioning requirements.															
6.	Use flow and pressure drop to trend filter life cycle cost and trigger filter changes based on life cycle cost. See control logic and narrative for additional information.															
7.	Monitor amps to provide a proof of operation in put and create a virtual meter to track energy use. Monitor amps to provide a proof of operation in put and create a virtual meter to track energy use. Accumulate and display current demand level, kWh for the day, and kWh for the previous day, calendar month, and calendar year. Archive data to the data to the dedicated archival data storage drive in the City's Data Center. See Network Diagram.															
8.	0.75% of span for sensor plus transmitter combined.															
9.	2 feet of element for every 4 sq.ft. of duct area, 6 ft. minimum length.															
10.	Wire safety devices to pilot a relay and keep it energized in normal operation so that a safety trip de-energizes the relay. Use relay contacts to interlock the supply fan VFD, the exhaust fan VFD, and to provide a digital status input to the DDC system. Safeties shall function no matter what the position of the starter Hand-Off-Auto selector switch is.															
11.	Provide interface relay (one per point) wired per vendor wiring diagrams. Verify the interface relay current draw with both relays energized will not overload the vendor's control power transformer.															
12.	Enable point allows factory control circuit to start and stop the various motors, drives and actuators associated with the AHU.															
13.	Multistage electric resistance heater shall have an SCR for the first stage. Logic shall be arranged to provide modulated capacity through the entire operating range by coordinating the operation of the SCR controlled stage with the remaining across the line stages.															
14.	Wire to contacts in a device furnished and installed by fire alarm contractor in the supply duct per the requirements of NFPA 90A, NFPA 72 and the City of Seattle Fire Code.															
15.	Respond to the coldest temperature over 12 continuous inches of the element.															
16.	Wired to the fire alarm system and arranged to open the vent damper on alarm. Coordinate with the fire alarm contractor and City of Seattle Code requirements.															
17.	Provide BACnet or Siemens P2 network card. Coordinate communication protocol/networking requirements with City of Seattle DOIT. Map all internally available points across the interface so they are visible at the Facility Operations OWS. Coordinate presentation details during submittals.															
18.	Perform a relative calibration of this point relative to the other temperature points in the same air stream using the outdoor air temperature sensor as a reference. Adjust the zero of the other sensors so all sensors agree when immersed in a well stirred bucket of ice water. Adjust the span of the other sensors so they all agree when subject to an air stream at the same temperature (heat wheel off, electric heat off).															
19.	Perform a relative calibration of this point relative to the other temperature points in the same air stream using the heat exchanger entering air temperature sensor as a reference. Adjust the zero of the other sensors so all sensors agree when immersed in a well stirred bucket of ice water. Adjust the span of the other sensors so they all agree when subject to an air stream at the same temperature (heat wheel off, electric heat off).															
20.	Used as a proof of operation input and also as a loss of efficiency alarm. Also use the proof of operation input to create a virtual meter to track energy use. Accumulate and display current demand level, kWh for the day, and kWh for the previous day, calendar month, and calendar year. Archive data to the data to the dedicated archival data storage drive in the City's Data Center. See Network Diagram.															

**Weinstein A+U**  
Architects + Urban Designers LLC  
2200 Western Avenue Suite 301  
Seattle, WA 98121  
T 206 443 8806  
F 206 443 1218  
Weinsteinau.com

© 2013 Weinstein AU - These documents have been prepared specifically for the above named project. They are not suitable for use on other projects or in other locations without the approval and participation of the Architect.



NW Satellite Office  
8560 North Buchanan Avenue  
Portland, Oregon, 97203  
Phone: (503) 286-1494  
DSellers@FacilityDynamics.com

Corporate Office  
6760 Alexander Bell Drive, Suite 200  
Columbia, MD 21046  
Phone: (410) 290-0900  
www.FacilityDynamics.com



**CITY OF SEATTLE**

**Fire Station 22**  
901 E. Roanoke St.  
Seattle WA 98102

**100% CD SET**



**100% CONSTRUCTION DOCUMENTS**

PROJECT-NO	13004
DRAWN	DA5
CHECKED BY	CBM
DATE	1/11/16
REVISIONS	DATE

- △
- △
- △
- △
- △
- △

SHEET TITLE  
**HRV-2 Point List**

SHEET NUMBER  
**TC 0.11**













Misc. Point List																	
Point Name	Number [BACnet Object ID], Note 7	System and Service	Sensor		Features									Notes			
			Type	Accuracy	Alarms				Trending								
					Limit		Warning		Samples1	Commissioning5			Operating5				
					Hi	Lo	Hi	Lo		Time2	Local3	Archive4	Time2		Local3	Archive4	
<b>Analog Inputs</b>																	
Electric heater EH-1 space temperature		Restroom 112 space temperature sensor	1,000 Ω Pt RTD with close coupled transmitter	Note 6						30	2 min	✓	✓	5 min	✓	✓	Note 10
Electric heater EH-1 set point adjustment		EH-1 set point adjustment	Set point adjustment							30	2 min	✓	✓	1 min	✓	✓	
Electric heater EH-3 space temperature		Lobby space temperature sensor	1,000 Ω Pt RTD with close coupled transmitter	Note 6						30	2 min	✓	✓	5 min	✓	✓	
Electric heater EH-3 set point adjustment		EH-3 set point adjustment	Set point adjustment							30	2 min	✓	✓	1 min	✓	✓	Note 10
Electric heater EH-4 space temperature		Maintenance 108 space temperature sensor	1,000 Ω Pt RTD with close coupled transmitter	Note 6						30	2 min	✓	✓	5 min	✓	✓	
Electric heater EH-4 set point adjustment		EH-4 set point adjustment	Set point adjustment							30	2 min	✓	✓	1 min	✓	✓	Note 10
Electric heater EH-7 space temperature		MDS Storage space temperature sensor	1,000 Ω Pt RTD with close coupled transmitter	Note 6						30	2 min	✓	✓	5 min	✓	✓	
Electric heater EH-7 set point adjustment		EH-7 set point adjustment	Set point adjustment							30	2 min	✓	✓	1 min	✓	✓	Note 10
Domestic hot water supply temperature		Domestic water temperature to the loads	Insertion 1,000 Ω Pt RTD with close coupled transmitter	Note 6						60	1 sec	✓	✓	1 min	✓	✓	
Domestic hot water return temperature		Domestic water temperature at the return pump	Insertion 1,000 Ω Pt RTD with close coupled transmitter	Note 6						60	1 sec	✓	✓	1 min	✓	✓	
Domestic hot water pump amps		Pump amps	Set point adjustment							60	1 min	✓	✓	1 min	✓	✓	
Battery Charger Proof		Generator Battery Charger Proof of Operation	DC voltage transmitter	+/- 0.5% Full Scale						60	1 min	✓	✓	1 min	✓	✓	
Heater Proof of Operation		Generator Block Heater Proof of Operation	Surface temperature transmitter	+/- 0.5% Full Scale						60	1 min	✓	✓	1 min	✓	✓	
Whole Building Electric Meter		Whole building electrical consumption	Pick up retransmitted signal from the utility							60	1 min	✓	✓	1 min	✓	✓	Note 13, 14
Whole Building Gas Meter		Whole building gas consumption	Pick up retransmitted signal from the utility							60	1 min	✓	✓	1 min	✓	✓	Note 13, 15
UH-1 Gas Meter		UH-1 gas consumption	Sensus M-1002 with RIOtronics pulser							60	1 min	✓	✓	1 min	✓	✓	Note 14, 15, 17
UH-2 through 5 and DHW Gas Meter		UH-2 through 5 and DHW gas consumption	Sensus M-1002 with RIOtronics pulser							60	1 min	✓	✓	1 min	✓	✓	Note 14 - 17
MUAU Gas Meter		MUAU gas consumption	Sensus M-1002 with RIOtronics pulser							60	1 min	✓	✓	1 min	✓	✓	Note 14, 15, 17
Domestic Hot Water Gas Meter		Domestic hot water heater gas consumption	Sensus M-1002 with RIOtronics pulser							60	1 min	✓	✓	1 min	✓	✓	Note 14, - 17
Whole Building Water Meter WM-1		Whole building water consumption	Line size Neptune Tru/Flo Compound Meter	1%/1-1/2%						60	1 min	✓	✓	1 min	✓	✓	Note 12, 14
Rain Water Prefilter Differential Pressure		Rainwater Harvesting System	Differential Pressure Transmitter	+/- 2% Full Scale						10	COV	✓	✓	COV	✓	✓	Note 25
Rain Water Final Filter Differential Pressure		Rainwater Harvesting System	Differential Pressure Transmitter	+/- 2% Full Scale						10	COV	✓	✓	COV	✓	✓	Note 25
Rain Water System Supply Pressure		Rainwater Harvesting System	Pressure Transmitter	+/- 2% Full Scale						10	COV	✓	✓	COV	✓	✓	Note 25
<b>Digital Inputs</b>																	
Transfer Switch Proof of Operation		Automatic transfer switch status	Isolated contact	N/A						10	COV	✓	✓	COV	✓	✓	Note 18
Fitness Center occupancy sensor		North Fitness Center occupancy detection	Occupancy switch	N/A						10	COV	✓	✓	COV	✓	✓	
Beanery occupancy sensor		North Fitness Center occupancy detection	Occupancy switch	N/A						10	COV	✓	✓	COV	✓	✓	
Day Room occupancy sensor		North Fitness Center occupancy detection	Occupancy switch	N/A						10	COV	✓	✓	COV	✓	✓	
Fire alarm indication		Fire alarm status	Isolated contact	N/A						10	COV	✓	✓	COV	✓	✓	Note 21
Rain Water System Tank Level Alarm		Rainwater Harvesting System	Isolated contact	N/A						10	COV	✓	✓	COV	✓	✓	Note 24
Rain Water System General Alarm		Rainwater Harvesting System	Isolated contact	N/A						10	COV	✓	✓	COV	✓	✓	Note 24
<b>Digital Outputs (All digital outputs to include local override capability and indication)</b>																	
EH-1 On/Off		EH-1 space temperature control	Relay output, Note 9	N/A						10	COV	✓	✓	COV	✓	✓	
EH-3 On/Off		EH-3 space temperature control	Relay output, Note 9	N/A						10	COV	✓	✓	COV	✓	✓	
EH-4 On/Off		EH-4 space temperature control	Relay output, Note 9	N/A						10	COV	✓	✓	COV	✓	✓	
EH-6 On/Off		EH6 space temperature control	Relay output, Note 9, 10	N/A						10	COV	✓	✓	COV	✓	✓	
EH-7 On/Off		EH-7 space temperature control	Relay output, Note 9	N/A						10	COV	✓	✓	COV	✓	✓	
Domestic hot water pump start/stop		Domestic hot water recirculation pump command	Relay output	N/A						10	COV	✓	✓	COV	✓	✓	
<b>Hard Wired Points</b>																	
Rainwater tank 1 level sensor		Interlock wiring for the rain water system	By Rainwater Harvesting System Vendor	N/A						N/A	N/A	N/A	N/A	N/A	N/A	N/A	Note 22
Rainwater harvesting flush water make up meter		Interlock wiring for the rain water system	By Rainwater Harvesting System Vendor	N/A						N/A	N/A	N/A	N/A	N/A	N/A	N/A	Note 22
Rainwater harvesting irrigation make up meter		Interlock wiring for the rain water system	By Rainwater Harvesting System Vendor	N/A						N/A	N/A	N/A	N/A	N/A	N/A	N/A	Note 22
Rainwater harvesting flush water make up alarm		Interlock wiring for the rain water system	By Rainwater Harvesting System Vendor	N/A						N/A	N/A	N/A	N/A	N/A	N/A	N/A	Note 22
Rainwater harvesting irrigation make up alarm		Interlock wiring for the rain water system	By Rainwater Harvesting System Vendor	N/A						N/A	N/A	N/A	N/A	N/A	N/A	N/A	Note 22
<b>Safety Interlocks (Hardwired to shut down the system. Safeties shall function no matter what position the equipment's Hand-Off-Auto, Inverter-Bypass, or other selector switches are in)</b>																	
Air compressor emergency stop		Hardwired emergency stop switch at door	Mushroom switch as required by code	N/A						10	COV	✓	✓	COV	✓	✓	
<b>Virtual Points</b>																	
Domestic hot water set point		Set point for cycling domestic water pump	N/A	N/A						5	COV	✓	✓	COV	✓	✓	
<b>Network Points</b>																	
Emergency Generator Energy		LEED Monitoring and Verification	Modbus Interface to the Electrical Power Monitoring System	N/A						60	1 min	✓	✓	1 min	✓	✓	Note 14, 19
Panel M2 Energy		LEED Monitoring and Verification	Modbus Interface to the Electrical Power Monitoring System	N/A						60	1 min	✓	✓	1 min	✓	✓	Note 14, 19
Panel G2 Energy		LEED Monitoring and Verification	Modbus Interface to the Electrical Power Monitoring System	N/A						60	1 min	✓	✓	1 min	✓	✓	Note 14, 19
Panel G1 Energy		LEED Monitoring and Verification	Modbus Interface to the Electrical Power Monitoring System	N/A						60	1 min	✓	✓	1 min	✓	✓	Note 14, 19
Vehicle Charging Station Energy		LEED Monitoring and Verification	Modbus Interface to the Electrical Power Monitoring System	N/A						60	1 min	✓	✓	1 min	✓	✓	Note 14, 19
Panel ELB Energy		LEED Monitoring and Verification	Modbus Interface to the Electrical Power Monitoring System	N/A						60	1 min	✓	✓	1 min	✓	✓	Note 14, 19
Panel MB Energy		LEED Monitoring and Verification	Modbus Interface to the Electrical Power Monitoring System	N/A						60	1 min	✓	✓	1 min	✓	✓	Note 14, 19
Panel LB Energy		LEED Monitoring and Verification	Modbus Interface to the Electrical Power Monitoring System	N/A						60	1 min	✓	✓	1 min	✓	✓	Note 14, 19
Panel GB Energy		LEED Monitoring and Verification	Modbus Interface to the Electrical Power Monitoring System	N/A						60	1 min	✓	✓	1 min	✓	✓	Note 14, 19
Photovoltaic Energy		LEED Monitoring and Verification	Modbus Interface to the Electrical Power Monitoring System	N/A						60	1 min	✓	✓	1 min	✓	✓	Note 14, 19
Rainwater Harvesting System Energy		LEED Monitoring and Verification	Modbus Interface to the Electrical Power Monitoring System	N/A						60	1 min	✓	✓	1 min	✓	✓	Note 14, 19
Power Monitoring Points 1 - 20		LEED Monitoring and Verification	Modbus Interface to the Electrical Power Monitoring System	N/A						60	1 min	✓	✓	1 min	✓	✓	Note 14, 19, 20
Tank 1 level		Rainwater Harvesting System	BACnet Point	N/A						60	1 min	✓	✓	1 min	✓	✓	Note 23
Tank 2 level		Rainwater Harvesting System	BACnet Point	N/A						60	1 min	✓	✓	1 min	✓	✓	Note 23
Rainwater Flow		Rainwater Harvesting System	BACnet Point	N/A						60	1 min	✓	✓	1 min	✓	✓	Note 23
Irrigation Make Up Flow		Rainwater Harvesting System	BACnet Point	N/A						60	1 min	✓	✓	1 min	✓	✓	Note 23
Flush Water Make Up Flow		Rainwater Harvesting System	BACnet Point	N/A						60	1 min	✓	✓	1 min	✓	✓	Note 23
UV Fault		Rainwater Harvesting System	BACnet Point	N/A						60	1 min	✓	✓	1 min	✓	✓	Note 23
Rainwater pump speed		Rainwater Harvesting System	BACnet Point	N/A						60	1 min	✓	✓	1 min	✓	✓	Note 23
Rainwater pump differential pressure		Rainwater Harvesting System	BACnet Point	N/A						60	1 min	✓	✓	1 min	✓	✓	Note 23

See sheet TC 042 for Notes

100% CONSTRUCTION DOCUMENTS

**Weinstein A+U**  
Architects + Urban Designers LLC  
2200 Western Avenue Suite 301  
Seattle, WA 98121  
T 206 443 8806  
F 206 443 1218  
Weinsteinau.com

© 2013 Weinstein A+U - These documents have been prepared specifically for the above named project. They are not suitable for use on other projects or in other locations without the approval and participation of the Architect.



NW Satellite Office  
8560 North Buchanan Avenue  
Portland, Oregon, 97203  
Phone: (503) 286-1494  
DSellers@FacilityDynamics.com

Corporate Office  
6760 Alexander Bell Drive, Suite 200  
Columbia, MD 21046  
Phone: (410) 290-0900  
www.FacilityDynamics.com



**CITY OF SEATTLE**

**Fire Station 22**  
901 E. Roanoke St.  
Seattle WA 98102

100% CD SET



PROJECT-NO	13004
DRAWN	DA5
CHECKED BY	CBM
DATE	1/11/16
REVISIONS	DATE
△	Revision 1 - Addendum 5 - 2016-02-19
△	
△	
△	
△	
△	

SHEET TITLE  
**Miscellaneous Point List**

SHEET NUMBER  
**TC0.41**

Notes:
1. Samples indicates the minimum number of data samples that must be held in the local controller if it is trending the point.
2. Time indicates the required sampling time for the trending function.
3. A check in the local column indicates that the trending only needs to be running in the local controller and the most recent value can write over the last value when the trend buffer fills up.
4. A check in the archive column indicates that the trend data must be archived to the system hard disc when trend buffer fills up so that a continuous trend record is maintained.
5. Commissioning trending requirements only need to be implemented during the start-up and warranty year. After the start-up and warranty process, the control contractor should set the trending parameters to the operating requirements listed if they differ from the commissioning requirements.
6. 0.75% of span for sensor plus transmitter combined; provide a 2nd calibration well along with the well for the sensor for pipe mounted sensors.
7. Point numbers will be determined once the Owner's point naming standard is finalized. And this list will be updated at that time. For BACnet points, "xx" refers to the equipment's "group number". For the purposes of this project, each indoor unit will be considered to be a group.
8. Coordinate with the utility to pick up an isolated retransmitted signal from their meter
9. Coordinate relay contact rating with heater requirements
10. Sequence the unit heater with the operation of HRV-3 controls serving the area in software. Cycle the heater on if the space temperature drops 2°F (adjustable) below the current HRV heating set point.
11. Coordinate with the plumbing contractor to install the meter in the gas service to the water heaters. Use the total gas consumption and the submetered values to create a virtual meter for the cooking gas consumption.
12. Coordinate with the plumbing contractor to install the meter in the incoming water service ahead of the back flow preventers.
13. Coordinate with the utility to pick up an isolated retransmitted signal from their meter.
14. In addition to indicating current flow integrate the flow reading to provide consumption for the past hour, the past day, the current calendar month, and the current calendar year. Archive data to the data to the dedicated archival data storage drive in the City's Data Center. See Network Diagram.
15. Coordinate with the plumber to install the meter in the gas service to the existing device or devices.
16. Use data from this submeter along with the data from the domestic hot water sub-meter to create a virtual meter monitoring the gas consumption of Unit Heaters 2 - through 5.
17. Use the whole building meter data along with data from the Unit Heater 1 submeter, the Unit Heater 2-5 and Domestic Hot Water submeter, and the MUAU Submeter to create a virtual meter monitoring gas consumption of the cooking equipment.
18. Coordinate with Division 16 to pick up transfer switch status to be used to initiate power failure and power failure recovery sequences.
19. Coordinate with Division 16 define these objects in their power monitoring system network and pass them to the Siemens network via a Modbus link.
20. These points are placeholders for points to be specified during submittal review and commissioning to provide data for the LEED Monitoring and Verification process and the building energy model. Some points may be totalizations of multiple circuits. For instance, the LEED energy model may need to know the total electrical consumption of the VRF indoor units, which are served by multiple power circuits.
21. Coordinate with Division 16 to pick up a dry contact that closes if there is a fire alarm.
22. Furnish interlock wiring as required by the Rainwater Harvesting system; assume 4-#14 conductors per point in conduit.
23. Coordinate with the Rainwater Harvesting System vendor to define these objects in their control system network and pass them to the Siemens network via a BACnet link.
24. Coordinate with the Rainwater Harvesting System vendor for isolated dry contacts to monitor for these parameters.
25. Coordinate with the Rainwater Harvesting System vendor to install these independent sensors on their pump skid for independent monitoring and alarm generation

**Weinstein A+U**  
Architects + Urban Designers LLC  
2200 Western Avenue Suite 301  
Seattle, WA 98121  
T 206 443 8806  
F 206 443 1218  
Weinsteinau.com

© 2013 Weinstein AU - These documents have been prepared specifically for the above named project. They are not suitable for use on other projects or in other locations without the approval and participation of the Architect.



**Facility Dynamics**  
ENGINEERING

NW Satellite Office  
8560 North Buchanan Avenue  
Portland, Oregon, 97203  
Phone: (503) 286-1494  
DSellers@FacilityDynamics.com

Corporate Office  
6760 Alexander Bell Drive, Suite 200  
Columbia, MD 21046  
Phone: (410) 290-0900  
www.FacilityDynamics.com



**CITY OF SEATTLE**

**Fire Station 22**  
901 E. Roanoke St.  
Seattle WA 98102

**100% CD SET**



**100% CONSTRUCTION DOCUMENTS**

PROJECT-NO	13004
DRAWN	DAS
CHECKED BY	CBM
DATE	1/11/16
REVISIONS	DATE
△	Revision 1 - Addendum 5 - 2016-02-19
△	
△	
△	
△	
△	
SHEET TITLE	<b>Miscellaneous Point List</b>
SHEET NUMBER	<b>TC0.42</b>

1  
Add. 05






CITY OF SEATTLE

Fire Station 22  
 901 E. Roanoke St.  
 Seattle WA 98102

100% CD SET




100% CONSTRUCTION DOCUMENTS



- SHEET NOTES**
- 1 MNet down to Branch Controller 2, 1 MNet Down to the Mitsubishi EB50-GUA, 1 Siemens P2 and 1 Modbus down to the DOIT furnished router and ??#18 TSP down to Siemens BC-1.
  - 1 MNet up to Branch Controller 1, 1 MNet Up to the VRF Outdoor Unit, 1 MNet up to VRF, 1 Siemens P2 up to Siemens BC-2, and 1 Modbus up to the Distribution System Data Engine.
  - 30 #18 TSP up from Siemens BC-1 to field devices located in the Apparatus Bay ceiling area.
  - 1 #18 TSP up; route conduit along structural elements to minimize visibility through the glass panels.
  - 4 conductors (1 spares) plus 1 green ground in conduit up to the Apparatus Bay Destratification Fans.
  - Route conduit and cables to the field devices in the Apparatus Bay in the ceiling cavity over Stair 1 to access the wall cavity. Coordinate with the ceiling installation and Architect to provide sufficient clearance between the beam at the head of the stairs for the conduit and cable route.
  - Fan speed control switches for the destratification fans; 1 wireless switch controls all fans. 100 foot range maximum from the switch to the 1st fan and between fans.
  - Space temperature and set point adjustment for UH-2 through 5, EF-5 high speed request push button, EF-5, and vehicle exhaust fan **proof of operation pilot lights. Pilot lights shall be push to test type. Include the words "Push to Test" in the engraved label provided for the device. Provide 2 #18 TSP for each of these field devices.**
  - Combination Nitrous Oxide and Carbon Monoxide detector, alarm, and ventilation control. Provide 5 #18 TSP to Siemens BC-1 for:
    - 9.1. 4-20 ma NO<sub>2</sub> level indication
    - 9.2. 4-20 ma CO level indication
    - 9.3. Alarm indication
    - 9.4. High speed request signal from the Siemens logic
    - 9.5. 24 vac power
  - Provide 2 #18 TSP to the EF-5 variable speed motor controller to command low and high speed operation.
  - Coordinate with Division 26 to wire the manual speed control switch into the fan circuit. Furnish and install a 1/2 inch conduit from the electrical contractors disconnect to the manual speed switch location with 4 #12 THHN conductors plus ground and wire per the manufacturer's written instructions.
  - 27 #18 TSP up to Siemens BC-2 (1 spare).
  - Combination Nitrous Oxide and Carbon Monoxide detector and alarm, and alarm. Provide 4 #18 TSP to Siemens BC-1 for:
    - 12.1. 4-20 ma NO<sub>2</sub> level indication
    - 12.2. 4-20 ma CO level indication
    - 12.3. Alarm indication
    - 12.4. 24 vac power

- SHEET NOTES (Continued)**
13. Space temperature sensor with set point adjustment requires 2-#18 TSP cables.
  14. Coordinate with Division 23 to install a gas submeters in the line serving Unit Heater 1 in Bunker Gear Storage.

- GENERAL NOTES**
1. Due to the scale of the drawings, the routes occupied by wiring runs are larger on plan than they will be in the field. The routing on the drawing is intended to convey the general route to be follow. In general, the following guidelines apply:
    - 1.1. Hold wiring clear of equipment access panels and access routes.
    - 1.2. Follow existing pipe and duct routes when they are in the vicinity of the wiring run shown.
  2. Similarly, due to the scale of the drawings, the symbols used for the various field devices are generally larger than the actual device. The location shown on plan is intended to show the general location for the purposes of determining wire/cable route and quantity. The final location of all devices shall be coordinated in the field.
    - 2.1. Devices locations in visible areas will be coordinated and verified in the field with a representative from the Architect, the Control Designer, and the Mechanical Designer at a minimum.
    - 2.2. Device locations in concealed areas will be coordinated and verified in the field with a representative from the Control Designer and the Mechanical Designer at a minimum.
  3. Where conduit is required, furnish and install a separate raceway system for each of the following cable system types.
    - 3.1. MNet, Siemens P2, and Modbus cables
    - 3.2. Input/output cables (#18 Twisted Shielded Pairs)
    - 3.3. VRF Controller cables
  4. All Mitsubishi equipment shall be furnished by Mitsubishi under Division 23 of the specifications.
  5. Mitsubishi network cabling shall be roughed in by the temperature control contractor along with the cabling required by the temperature control system. But final terminations to the Mitsubishi equipment shall be by Mitsubishi.
  6. Coordinate with Mitsubishi as required to provide the necessary rough-in and to mount Mitsubishi equipment. See the TC6.00 and TC 6.01 for additional information regarding the control power and network wiring requirements for the Mitsubishi equipment.



PROJECT-NO	13004
DRAWN	DA5
CHECKED BY	CBM
DATE	1/11/16
REVISIONS	DATE
▲	Revision 1 - Addendum 5 - 2016-02-19
▲	
▲	
▲	
▲	
SHEET TITLE	First Floor Plan
SHEET NUMBER	TC 2.21



**CITY OF SEATTLE**

**Fire Station 22**  
 901 E. Roanoke St.  
 Seattle WA 98102

100% CD SET




100% CONSTRUCTION DOCUMENTS

PROJECT-NO	13004
DRAWN	DA5
CHECKED BY	CBM
DATE	1/11/16
REVISIONS	DATE
△	Revision 1 - Addendum 5 - 2016-02-19
△	
△	
△	
△	
SHEET TITLE	

Second Floor Plan

SHEET NUMBER  
**TC 2.31**



**SHEET NOTES**


- Siemens Building Controller BC-2 in recessed panel. Coordinate with the general contractor and the architect for paint color for the exposed surfaces. Coordinate with Division 26 to focus wall washers to highlight the panel.
- 1 MNet down to Branch Controller 2, 1 MNet Down to the Mitsubishi EB-50GU-A in the basement level, 1 MNet down to VRF10, 1 Siemens P2 and one Modbus down to the DOIT router.
- 2 MNet and 16 #18 TSP (2 spare) up to the VRF Outdoor Unit.
- 1 MNet and 8 #18TSP (1 spare) up to ODU-1.
- From this point on, in the direction of the arrows, all control cables shall be in conduit because of the open ceiling. Conduits shall be routed to follow the VRF piping runs and duct runs where possible and shall run parallel and/or perpendicular to those distribution networks.
- Coordinate with Division 26 to install the wireless fan speed controllers. See the first floor plan notes associated with the wall switch for additional information.
- Down to door switch.
- 2 #18 TSP up to EF-5 from the Apparatus Bay ventilation controller.
- 1-#18TSP up to the vehicle exhaust system.
- 30-#18TSP (spares) down to Siemens BC-1.
- 5 conductors (1 spare) plus ground in conduit down to the first floor fan control switches. 2 #18 TSP down to the Apparatus Bay Ventilation Controller.
- Conduit with exhaust fan back-draft damper interlock wiring down from disconnect and up into the roof curb. See detail on TC5.11.
- 1 #18 TSP up to RV-2. Coordinate with Division 23 to provide a factory roof curve with hinged access and motorized back draft damper and damper tray with low voltage actuator, voltage specified by the temperature control contractor. Installation to be similar to the detail shown on TC 5.11 for motorized back draft dampers serving roof mounted exhaust fans.
- Wire manual hood switch to start EF-6 and open its back draft damper via across the line interlocks to the back draft damper actuator. Coordinate with Division 23 to have EF-6 provided with hinged access and damper tray with motorized back draft damper. Coordinate with Division 23 and 26 to ensure the voltage of the actuator matches the EF-6 line voltage. Interlock RV-1's back draft damper with the EF-6 back draft damper. Coordinate with Division 23 and 26 to ensure the voltage of the actuator matches the EF-6 line voltage. Interlock the MUAU with the hood switch via a hard wired relay piloted interlock. Installation to be similar to what is shown in the detail on TC-5.11.
- 1 #18 TSP up to the exhaust fan enable relay.
- 17 #18 TSP up to HRV-1 from Siemens BC-2.
- 15 #18 TSP up to HRV-2 from Siemens BC-2.
- 13 #18 TSP up to HRV-3 from Siemens BC-2.
- 8 #18 TSP up to MUAU from Siemens BC-2.
- 10 #18 TSP up from the Bunker Storage Room to Siemens BC-2.

**SHEET NOTES (Continued)**

- Coordinate with Division 23 to install wells, calibration wells, and temperature sensors in the domestic hot water supply and return lines.
- Electrical panels LCP2, M2, and G2. Coordinate with Division 26 to install the domestic hot water pump and hot water heater current sensors and the domestic hot water pump enable point.
- Coordinate with the utility to pick up a retransmitted signal from their meter to monitor electrical kW and gas therms.
- Coordinate with Division 23 to install gas meters in the piping to UH2 - 5 and the domestic hot water heater, the piping to the domestic hot water heater, and the piping to MUAU 1.
- Coordinate with Division 26 to install the wired speed control switch.
- Coordinate with the Architect to install this sensor at or above the level of the outdoor light to avoid any shadows.

**GENERAL NOTES**

- Due to the scale of the drawings, the routes occupied by wiring runs are larger on plan than they will be in the field. The routing on the drawing is intended to convey the general route to be follow. In general, the following guidelines apply:
  - Hold wiring clear of equipment access panels and access routes.
  - Follow existing pipe and duct routes when they are in the vicinity of the wiring run shown.
- Similarly, due to the scale of the drawings, the symbols used for the various field devices are generally larger than the actual device. The location shown on plan is intended to show the general location for the purposes of determining wire/cable route and quantity. The final location of all devices shall be coordinated in the field.
  - Devices locations in visible areas will be coordinated and verified in the field with a representative from the Architect, the Control Designer, and the Mechanical Designer at a minimum.
  - Device locations in concealed areas will be coordinated and verified in the field with a representative from the Control Designer and the Mechanical Designer at a minimum.
- Where conduit is required, furnish and install a separate raceway system for each of the following cable system types.
  - MNet, Siemens P2, and Modbus cables
  - Input/output cables (#18 Twisted Shielded Pairs)
  - VRF Controller cables
- All Mitsubishi equipment shall be furnished by Mitsubishi under Division 23 of the specifications.
- Mitsubishi network cabling shall be roughed in by the temperature control contractor along with the cabling required by the temperature control system. But final terminations to the Mitsubishi equipment shall be by Mitsubishi.
- Coordinate with Mitsubishi as required to provide the necessary rough-in and go mount Mitsubishi equipment. See the TC6.00 and TC 6.01 for additional information regarding the control power and network wiring requirements for the Mitsubishi equipment.



D:\2016\13004\Fire Station 22\2016-02-19\13004-TC 2.31.dwg



**CITY OF SEATTLE**

**Fire Station 22**  
 901 E. Roanoke St.  
 Seattle WA 98102

100% CD SET




100% CONSTRUCTION DOCUMENTS

PROJECT-NO	13004
DRAWN	DA5
CHECKED BY	CBM
DATE	1/11/16
REVISIONS	DATE

△	
△	
△	
△	
△	

SHEET TITLE  
**Roof Plan**

SHEET NUMBER  
**TC 2.41**




**SHEET NOTES**

- 1 MNet up from the Mitsubishi EB-50GU-A, 1 MNet down to ODU-1, and 16 #18 TSP (2 spare) to Siemens panel BC-1. Provide Pate roof penetration curve or equal. Coordinate with the roofing contractor to ensure the roofing warranty requirements are complied with.
- MNet up from the VRF Outdoor Unit and 8 #18TSP (1 spare) up from Siemens panel BC-1.
- Provide Pate roof penetration curve or equal. Coordinate with the roofing contractor to ensure the roofing warranty requirements are complied with.
- VRF Outdoor Unit and related data points; See point list and system diagram for details and sensor locations.
- Furnish and install a stainless steel, hinged cover NEMA 4 enclosure to house the refrigeration unit temperature and pressure transmitters. Keep the enclosure clear of the equipment service and air flow paths. Coordinate with the mechanical contractor to support the enclosure from the roof mounted equipment support for the refrigeration unit (see M801) using stainless steel unistrut or similar framing system. Coordinate with Mitsubishi to connect the pressure transmitters with tees and service valves to the refrigeration circuit high and low pressure test connections. Coordinate with Mitsubishi to install the surface temperature sensors as required on the refrigeration piping.
- Outdoor unit ODU-1 and related data points; See point list and system diagram for details and sensor locations.
- 2 #18 up from the Apparatus Bay ventilation controller. Coordinate with Division 23 to have the EF-5 ECM motor furnished with the 2 speed option and back draft interlock option. Coordinate with Division 26 for wiring power and control to the two speed option.
- Back draft damper interlock wiring conduit down from disconnect and back up inside the roof curb. See detail on M5.11.
- 1 #18 TSP up from Siemens BC-1, back draft damper interlock wiring conduit down from disconnect and back up inside the roof curb. See detail on M5.11.
- 5 #18 TSP up from Siemens BC-1. Coordinate with Division 23 to provide a factory roof curve with hinged access and motorized back draft damper and damper tray with low voltage actuator, voltage specified by the temperature control contractor. Installation to be similar to the detail shown on TC 5.11 for motorized back draft dampers serving roof mounted exhaust fans.
- 17 #18 TSP (2 spares) up from Siemens BC-2 inside the roof curb and into the control compartment to serve HRV-1 points
- 15 #18 TSP (2 spares) up from Siemens BC-2 inside the roof curb and into the control compartment to serve HRV-2 points.
- 13 #18 TSP (2 spares) up from Siemens BC-2 inside the roof curb and into the control compartment to serve HRV-3 points.
- #8 TSP (2 spares) up from Siemens BC-2 inside the roof curb and into the control compartment to serve MUAU points.

**GENERAL NOTES**


- Due to the scale of the drawings, the routes occupied by wiring runs are larger on plan than they will be in the field. The routing on the drawing is intended to convey the general route to be follow. In general, the following guidelines apply:
  - Hold wiring clear of equipment access panels and access routes.
  - Follow existing pipe and duct routes when they are in the vicinity of the wiring run shown.
- Similarly, due to the scale of the drawings, the symbols used for the various field devices are generally larger than the actual device. The location shown on plan is intended to show the general location for the purposes of determining wire/cable route and quantity. The final location of all devices shall be coordinated in the field.
  - Devices locations in visible areas will be coordinated and verified in the field with a representative from the Architect, the Control Designer, and the Mechanical Designer at a minimum.
  - Device locations in concealed areas will be coordinated and verified in the field with a representative from the Control Designer and the Mechanical Designer at a minimum.
- Where conduit is required, furnish and install a separate raceway system for each of the following cable system types.
  - MNet, Siemens P2, and Modbus cables
  - Input/output cables (#18 Twisted Shielded Pairs)
  - VRF Controller cables
- All Mitsubishi equipment shall be furnished by Mitsubishi under Division 23 of the specifications.
- Mitsubishi network cabling shall be roughed in by the temperature control contractor along with the cabling required by the temperature control system. But final terminations to the Mitsubishi equipment shall be by Mitsubishi.
- Coordinate with Mitsubishi as required to provide the necessary rough-in and go mount Mitsubishi equipment. See the TC6.00 and TC 6.01 for additional information regarding the control power and network wiring requirements for the Mitsubishi equipment.




D:\2017\13004\Fire Station 22\13004-TC 2.41-16000-Rev.dwg, TC 2.41, 1/11/16, 14:08:04



# ERCH-20-15L WIRING DIAGRAM



# PVe-20-SC WIRING DIAGRAM



**Weinstein A+U**  
Architects + Urban Designers LLC  
2200 Western Avenue Suite 301  
Seattle, WA 98121  
T 206 443 8806  
F 206 443 1218  
Weinsteinau.com

© 2013 Weinstein A+U - These documents have been prepared specifically for the above named project. They are not suitable for use on other projects or in other locations without the approval and participation of the Architect.



**Facility Dynamics**  
ENGINEERING  
NW Satellite Office  
8560 North Buchanan Avenue  
Portland, Oregon, 97203  
Phone: (503) 286-1494  
DSellers@FacilityDynamics.com

Corporate Office  
6760 Alexander Bell Drive, Suite 200  
Columbia, MD 21046  
Phone: (410) 290-0900  
www.FacilityDynamics.com



**CITY OF SEATTLE**

**Fire Station 22**  
901 E. Roanoke St.  
Seattle WA 98102

100% CD SET



100% CONSTRUCTION DOCUMENTS

PROJECT-NO	13004
DRAWN	DAS
CHECKED BY	CBM
DATE	2/19/16
REVISIONS	DATE

Revision 1 - Addendum 5 - 2016-02-19

SHEET TITLE  
**Wiring Details**

SHEET NUMBER  
**TC 5.21**

## HRV-1 Interlock Wiring


No Scale

- The wiring diagram for the basis of design unit is shown for bidding purposes to illustrate the points of interface between the DDC system and the unit's factory installed wiring. A project specific wiring diagram will be furnished by the control system designer subsequent to submittal approval. See the narrative sequence and point list for additional information and requirements.
- HRV enable contact from the DDC system.
- Electric heat enable contact from the DDC system.
- 4-20 ma SCR modulation command from the DDC system.
- Isolated contact indicating the frost cycle is active, monitored by the DDC System

## HRV-2 Interlock Wiring

No Scale

- HRV-3 to be similar.
- The wiring diagram for the basis of design unit is shown for bidding purposes to illustrate the points of interface between the DDC system and the unit's factory installed wiring. A project specific wiring diagram will be furnished by the control system designer subsequent to submittal approval. See the narrative sequence and point list for additional information and requirements.
- HRV enable contact from the DDC system.
- Isolated contact indicating the frost cycle is active, monitored by the DDC System
- HRV-2 will be equipped with a VFD on the supply fan and an ECM on the exhaust fan, both arranged to provide a two speed operating cycle. See the narrative sequence for the details of the two speed operation and the point list for the details of what will be required to integrate the VFD and the ECM with the DDC system



**GREENHECK**  
Building Value In Air.

Wiring Diagram Code:  
**G113C421A010N11DU05**

**CAUTION**  
UNIT SHALL BE GROUNDED IN ACCORDANCE WITH N.E.C. POWER MUST BE OFF WHILE SERVICING.

**NOTES**  
USE COPPER CONDUCTORS ONLY  
60° C FOR TERMINALS RATED LESS THAN 100 AMPS  
75° C FOR TERMINALS RATED 100 AMPS OR MORE  
FIELD CONTROL WIRING RESISTANCE SHOULD NOT EXCEED 0.75 OHM.  
FIELD WIRED - - - - -  
FACTORY SUPPLIED AND WIRED \_\_\_\_\_

**WIRE COLOR CODE**


BK	BLACK	BL	BLUE	BR	BROWN
GY	GRAY	LT BL	LIGHT BLUE	O	ORANGE
PK	PINK	PR	PURPLE	R	RED
W	WHITE	Y	YELLOW		

**LEGEND**

D1 INLET DAMPER  
DS1 MAIN DISCONNECT SWITCH  
FSC FIRE SYSTEM CONTACT  
MF MOTOR  
OLR MOTOR OVERLOAD  
PS1 DIRTY FILTER SWITCH  
RF SUPPLY FAN RELAY  
RH HEAT RELAY  
S1 EXHAUST FAN SWITCH  
S2 FAN SWITCH  
S4 HEAT AND COOL SWITCH  
SS ROOM OVERRIDE  
ST1 MOTOR STARTER  
TR# TRANSFORMER

USER INDIRECT GAS FURNACE INTERFACE CONNECTIONS:  
FACTORY WIRED TO TERMINAL "S2" IN IG FURNACE COMPARTMENT

Template Drawing: U05



**GREENHECK**  
Building Value In Air.

Wiring Diagram Code:  
**G4F11X1MX0000S05**

**CAUTION**  
UNIT SHALL BE GROUNDED IN ACCORDANCE WITH N.E.C. POWER MUST BE OFF WHILE SERVICING.

**NOTES**  
USE COPPER CONDUCTORS ONLY  
60° C FOR TERMINALS RATED LESS THAN 100 AMPS  
75° C FOR TERMINALS RATED 100 AMPS OR MORE  
FIELD CONTROL WIRING RESISTANCE SHOULD NOT EXCEED 0.75 OHM.  
FIELD WIRED - - - - -  
FACTORY SUPPLIED AND WIRED \_\_\_\_\_

**WIRE COLOR CODE**

BK	BLACK	BL	BLUE	BR	BROWN
GY	GRAY	LT BL	LIGHT BLUE	O	ORANGE
PK	PINK	PR	PURPLE	R	RED
W	WHITE	Y	YELLOW		

**LEGEND**

CM COMBUSTION BLOWER MOTOR  
HLC HIGH TEMPERATURE LIMIT CONTROL  
IC1 IGNITION CONTROL - SMALL MANIFOLD  
IC2 IGNITION CONTROL - LARGE MANIFOLD  
MV1 MAIN GAS VALVE - SMALL MANIFOLD  
MV2 MAIN GAS VALVE - LARGE MANIFOLD  
PS2 COMBUSTION AIR PROVING SWITCH  
R1 MAIN GAS VALVE 1 MONITORING  
R2 MAIN GAS VALVE 2 MONITORING  
R9 AIR PROVING SWITCH RELAY  
SC1 STAGE CONTROLLER  
TR# TRANSFORMER(S)  
TS1 OUTDOOR AIR TEMP SENSOR  
TS2 DISCHARGE AIR TEMP SENSOR

## MUAU Interlock Wiring

No Scale

- The wiring diagram for the basis of design unit is shown for bidding purposes to illustrate the points of interface between the DDC system and the unit's factory installed wiring. A project specific wiring diagram will be furnished by the control system designer subsequent to submittal approval. See the narrative sequence and point list for additional information and requirements.
- HRV enable contact from the DDC system.
- Gas furnace enable contact from the DDC system.
- Jumper H to G. The fire alarm shutdown is provided in software via the DDC system.
- Unused on this project.

1  
Add. 05

**Weinstein A+U**  
Architects + Urban Designers LLC  
2200 Western Avenue Suite 301  
Seattle, WA 98121  
T 206 443 8806  
F 206 443 1218  
Weinsteinau.com

© 2013 Weinstein A+U - These documents have been prepared specifically for the above named project. They are not suitable for use on other projects or in other locations without the approval and participation of the Architect.



NW Satellite Office  
8560 North Buchanan Avenue  
Portland, Oregon, 97203  
Phone: (503) 286-1494  
DSellers@FacilityDynamics.com

Corporate Office  
6760 Alexander Bell Drive, Suite 200  
Columbia, MD 21046  
Phone: (410) 290-0900  
www.FacilityDynamics.com



**CITY OF SEATTLE**

**Fire Station 22**  
901 E. Roanoke St.  
Seattle WA 98102

100% CD SET



100% CONSTRUCTION DOCUMENTS

PROJECT-NO	13004
DRAWN	DA5
CHECKED BY	CBM
DATE	2/19/16
REVISIONS	DATE

Revision 1 - Addendum 5 - 2016-02-19

SHEET TITLE

Wiring Details

SHEET NUMBER

**TC 5.22**



NW Satellite Office  
 8560 North Buchanan Avenue  
 Portland, Oregon, 97203  
 Phone: (503) 286-1494  
 DSellers@FacilityDynamics.com

Corporate Office  
 6760 Alexander Bell Drive, Suite 200  
 Columbia, MD 21046  
 Phone: (410) 290-0900  
 www.FacilityDynamics.com



**CITY OF SEATTLE**

**Fire Station 22**  
 901 E. Roanoke St.  
 Seattle WA 98102

**100% CD SET**

© 2013 Facility Dynamics, Inc. All Rights Reserved. Facility Dynamics is a registered trademark of Facility Dynamics, Inc.




**100% CONSTRUCTION DOCUMENTS**

PROJECT-NO	13004
DRAWN	DAS
CHECKED BY	CBM
DATE	1/11/16
REVISIONS	DATE

Revision 1 - Addendum 5 - 2016-02-18

SHEET TITLE  
**Network Diagram - Overview**

SHEET NUMBER  
**TC 6.00**












# Heat Recovery Ventilator HRV-1 and Make Up Air Unit MUAU System Diagram - Enlarged View - North and South East Portion

NO SCALE

In general terms, this section is drawn as if the occupied part of the building was split down the corridor and then unfolded, pivoting around a vertical line at the East end of the corridor.

The complete diagram can be seen on TC6.10. This enlarged section includes the North and South East portion of the system. Note that the enlarged sections overlap in some cases to allow different spaces to be viewed in their entirety.

For Continuation, See TC6.12



C

**Weinstein A+U**  
Architects + Urban Designers LLC  
2200 Western Avenue Suite 301  
Seattle, WA 98121  
T 206 443 8806  
F 206 443 1218  
Weinsteinau.com

© 2013 Weinstein A+U - These documents have been prepared specifically for the above named project. They are not suitable for use on other projects or in other locations without the approval and participation of the Architect.

**Facility Dynamics**  
ENGINEERING

NW Satellite Office  
8560 North Buchanan Avenue  
Portland, Oregon, 97203  
Phone: (503) 286-1494  
DSellers@FacilityDynamics.com


Corporate Office  
6760 Alexander Bell Drive, Suite 200  
Columbia, MD 21046  
Phone: (410) 290-0900  
www.FacilityDynamics.com



**CITY OF SEATTLE**

**Fire Station 22**  
901 E. Roanoke St.  
Seattle WA 98102

100% CD SET



100% CONSTRUCTION DOCUMENTS

PROJECT-NO	13004
DRAWN	DAS
CHECKED BY	CBM
DATE	1/11/16
REVISIONS	DATE
△	
△	
△	
△	
△	

SHEET TITLE  
**HRV1 and MUAU System Diagram NE and SE Detail**

SHEET NUMBER  
**TC 6.13**

B

C


For Continuation, See TC6.13

# Heat Recovery Ventilator HRV-1 and Make Up Air Unit MUAU System Diagram - Enlarged View - South East Portion

NO SCALE

In general terms, this section is drawn as if the occupied part of the building was split down the corridor and then unfolded, pivoting around a vertical line at the East end of the corridor.

The complete diagram can be seen on TC6.10. This enlarged section includes the South East portion of the system. Note that the enlarged sections overlap in some cases to allow different spaces to be viewed in their entirety.



**Weinstein A+U**  
Architects + Urban Designers LLC  
2200 Western Avenue Suite 301  
Seattle, WA 98121  
T 206 443 8806  
F 206 443 1218  
Weinsteinau.com

© 2013 Weinstein A+U - These documents have been prepared specifically for the above named project. They are not suitable for use on other projects or in other locations without the approval and participation of the Architect.



**Facility Dynamics**  
ENGINEERING

NW Satellite Office  
8560 North Buchanan Avenue  
Portland, Oregon, 97203  
Phone: (503) 286-1494  
DSellers@FacilityDynamics.com

Corporate Office  
6780 Alexander Bell Drive, Suite 200  
Columbia, MD 21046  
Phone: (410) 290-0900  
www.FacilityDynamics.com



**CITY OF SEATTLE**

**Fire Station 22**  
901 E. Roanoke St.  
Seattle WA 98102

100% CD SET



100% CONSTRUCTION DOCUMENTS

PROJECT-NO	13004
DRAWN	DAS
CHECKED BY	CBM
DATE	1/11/16
REVISIONS	DATE
△	
△	
△	
△	
△	
△	

SHEET TITLE  
**HRV1 and MUAU System Diagram SE Detail**

SHEET NUMBER  
**TC 6.14**

D:\Projects\13004\Fire Station 22\13004-TC6.14.dwg, 1/11/16, 10:00 AM, David A. Sellers, P.E., License No. 52574, State of Washington

D


# Heat Recovery Ventilator HRV-1 and Make Up Air Unit MUAU System Diagram - Enlarged View - South West Portion

NO SCALE

In general terms, this section is drawn as if the occupied part of the building was split down the corridor and then unfolded, pivoting around a vertical line at the East end of the corridor.

The complete diagram can be seen on TC6.10. The enlarged section includes the South West portion of the system, including the to air handling units associated with it.

For Continuation, See TC6.14



**Weinstein A+U**  
 Architects + Urban Designers LLC  
 2200 Western Avenue Suite 301  
 Seattle, WA 98121  
 T 206 443 8806  
 F 206 443 1218  
 weinsteinau.com

© 2013 Weinstein A+U - These documents have been prepared specifically for the above named project. They are not suitable for use on other projects or in other locations without the approval and participation of the Architect.



NW Satellite Office  
 8560 North Buchanan Avenue  
 Portland, Oregon, 97203  
 Phone: (503) 286-1494  
 DSellers@FacilityDynamics.com

Corporate Office  
 6760 Alexander Bell Drive, Suite 200  
 Columbia, MD 21046  
 Phone: (410) 290-0900  
 www.FacilityDynamics.com



**CITY OF SEATTLE**

**Fire Station 22**  
 901 E. Roanoke St.  
 Seattle WA 98102

100% CD SET



100% CONSTRUCTION DOCUMENTS

PROJECT-NO	13004
DRAWN	DAS
CHECKED BY	CBM
DATE	1/11/16
REVISIONS	DATE
△	
△	
△	
△	
△	
△	

SHEET TITLE  
**HRV1 and MUAU System Diagram SW Detail**

SHEET NUMBER  
**TC 6.15**

D:\Projects\13004\Fire Station 22\13004-TC6.15-16-17-18-19-20-21-22-23-24-25-26-27-28-29-30-31-32-33-34-35-36-37-38-39-40-41-42-43-44-45-46-47-48-49-50-51-52-53-54-55-56-57-58-59-60-61-62-63-64-65-66-67-68-69-70-71-72-73-74-75-76-77-78-79-80-81-82-83-84-85-86-87-88-89-90-91-92-93-94-95-96-97-98-99-100-101-102-103-104-105-106-107-108-109-110-111-112-113-114-115-116-117-118-119-120-121-122-123-124-125-126-127-128-129-130-131-132-133-134-135-136-137-138-139-140-141-142-143-144-145-146-147-148-149-150-151-152-153-154-155-156-157-158-159-160-161-162-163-164-165-166-167-168-169-170-171-172-173-174-175-176-177-178-179-180-181-182-183-184-185-186-187-188-189-190-191-192-193-194-195-196-197-198-199-200-201-202-203-204-205-206-207-208-209-210-211-212-213-214-215-216-217-218-219-220-221-222-223-224-225-226-227-228-229-230-231-232-233-234-235-236-237-238-239-240-241-242-243-244-245-246-247-248-249-250-251-252-253-254-255-256-257-258-259-260-261-262-263-264-265-266-267-268-269-270-271-272-273-274-275-276-277-278-279-280-281-282-283-284-285-286-287-288-289-290-291-292-293-294-295-296-297-298-299-300-301-302-303-304-305-306-307-308-309-310-311-312-313-314-315-316-317-318-319-320-321-322-323-324-325-326-327-328-329-330-331-332-333-334-335-336-337-338-339-340-341-342-343-344-345-346-347-348-349-350-351-352-353-354-355-356-357-358-359-360-361-362-363-364-365-366-367-368-369-370-371-372-373-374-375-376-377-378-379-380-381-382-383-384-385-386-387-388-389-390-391-392-393-394-395-396-397-398-399-400-401-402-403-404-405-406-407-408-409-410-411-412-413-414-415-416-417-418-419-420-421-422-423-424-425-426-427-428-429-430-431-432-433-434-435-436-437-438-439-440-441-442-443-444-445-446-447-448-449-450-451-452-453-454-455-456-457-458-459-460-461-462-463-464-465-466-467-468-469-470-471-472-473-474-475-476-477-478-479-480-481-482-483-484-485-486-487-488-489-490-491-492-493-494-495-496-497-498-499-500-501-502-503-504-505-506-507-508-509-510-511-512-513-514-515-516-517-518-519-520-521-522-523-524-525-526-527-528-529-530-531-532-533-534-535-536-537-538-539-540-541-542-543-544-545-546-547-548-549-550-551-552-553-554-555-556-557-558-559-560-561-562-563-564-565-566-567-568-569-570-571-572-573-574-575-576-577-578-579-580-581-582-583-584-585-586-587-588-589-590-591-592-593-594-595-596-597-598-599-600-601-602-603-604-605-606-607-608-609-610-611-612-613-614-615-616-617-618-619-620-621-622-623-624-625-626-627-628-629-630-631-632-633-634-635-636-637-638-639-640-641-642-643-644-645-646-647-648-649-650-651-652-653-654-655-656-657-658-659-660-661-662-663-664-665-666-667-668-669-670-671-672-673-674-675-676-677-678-679-680-681-682-683-684-685-686-687-688-689-690-691-692-693-694-695-696-697-698-699-700-701-702-703-704-705-706-707-708-709-710-711-712-713-714-715-716-717-718-719-720-721-722-723-724-725-726-727-728-729-730-731-732-733-734-735-736-737-738-739-740-741-742-743-744-745-746-747-748-749-750-751-752-753-754-755-756-757-758-759-760-761-762-763-764-765-766-767-768-769-770-771-772-773-774-775-776-777-778-779-780-781-782-783-784-785-786-787-788-789-790-791-792-793-794-795-796-797-798-799-800-801-802-803-804-805-806-807-808-809-810-811-812-813-814-815-816-817-818-819-820-821-822-823-824-825-826-827-828-829-830-831-832-833-834-835-836-837-838-839-840-841-842-843-844-845-846-847-848-849-850-851-852-853-854-855-856-857-858-859-860-861-862-863-864-865-866-867-868-869-870-871-872-873-874-875-876-877-878-879-880-881-882-883-884-885-886-887-888-889-890-891-892-893-894-895-896-897-898-899-900-901-902-903-904-905-906-907-908-909-910-911-912-913-914-915-916-917-918-919-920-921-922-923-924-925-926-927-928-929-930-931-932-933-934-935-936-937-938-939-940-941-942-943-944-945-946-947-948-949-950-951-952-953-954-955-956-957-958-959-960-961-962-963-964-965-966-967-968-969-970-971-972-973-974-975-976-977-978-979-980-981-982-983-984-985-986-987-988-989-990-991-992-993-994-995-996-997-998-999-1000-1001-1002-1003-1004-1005-1006-1007-1008-1009-1010-1011-1012-1013-1014-1015-1016-1017-1018-1019-1020-1021-1022-1023-1024-1025-1026-1027-1028-1029-1030-1031-1032-1033-1034-1035-1036-1037-1038-1039-1040-1041-1042-1043-1044-1045-1046-1047-1048-1049-1050-1051-1052-1053-1054-1055-1056-1057-1058-1059-1060-1061-1062-1063-1064-1065-1066-1067-1068-1069-1070-1071-1072-1073-1074-1075-1076-1077-1078-1079-1080-1081-1082-1083-1084-1085-1086-1087-1088-1089-1090-1091-1092-1093-1094-1095-1096-1097-1098-1099-1100-1101-1102-1103-1104-1105-1106-1107-1108-1109-1110-1111-1112-1113-1114-1115-1116-1117-1118-1119-1120-1121-1122-1123-1124-1125-1126-1127-1128-1129-1130-1131-1132-1133-1134-1135-1136-1137-1138-1139-1140-1141-1142-1143-1144-1145-1146-1147-1148-1149-1150-1151-1152-1153-1154-1155-1156-1157-1158-1159-1160-1161-1162-1163-1164-1165-1166-1167-1168-1169-1170-1171-1172-1173-1174-1175-1176-1177-1178-1179-1180-1181-1182-1183-1184-1185-1186-1187-1188-1189-1190-1191-1192-1193-1194-1195-1196-1197-1198-1199-1200-1201-1202-1203-1204-1205-1206-1207-1208-1209-1210-1211-1212-1213-1214-1215-1216-1217-1218-1219-1220-1221-1222-1223-1224-1225-1226-1227-1228-1229-1230-1231-1232-1233-1234-1235-1236-1237-1238-1239-1240-1241-1242-1243-1244-1245-1246-1247-1248-1249-1250-1251-1252-1253-1254-1255-1256-1257-1258-1259-1260-1261-1262-1263-1264-1265-1266-1267-1268-1269-1270-1271-1272-1273-1274-1275-1276-1277-1278-1279-1280-1281-1282-1283-1284-1285-1286-1287-1288-1289-1290-1291-1292-1293-1294-1295-1296-1297-1298-1299-1300-1301-1302-1303-1304-1305-1306-1307-1308-1309-1310-1311-1312-1313-1314-1315-1316-1317-1318-1319-1320-1321-1322-1323-1324-1325-1326-1327-1328-1329-1330-1331-1332-1333-1334-1335-1336-1337-1338-1339-1340-1341-1342-1343-1344-1345-1346-1347-1348-1349-1350-1351-1352-1353-1354-1355-1356-1357-1358-1359-1360-1361-1362-1363-1364-1365-1366-1367-1368-1369-1370-1371-1372-1373-1374-1375-1376-1377-1378-1379-1380-1381-1382-1383-1384-1385-1386-1387-1388-1389-1390-1391-1392-1393-1394-1395-1396-1397-1398-1399-1400-1401-1402-1403-1404-1405-1406-1407-1408-1409-1410-1411-1412-1413-1414-1415-1416-1417-1418-1419-1420-1421-1422-1423-1424-1425-1426-1427-1428-1429-1430-1431-1432-1433-1434-1435-1436-1437-1438-1439-1440-1441-1442-1443-1444-1445-1446-1447-1448-1449-1450-1451-1452-1453-1454-1455-1456-1457-1458-1459-1460-1461-1462-1463-1464-1465-1466-1467-1468-1469-1470-1471-1472-1473-1474-1475-1476-1477-1478-1479-1480-1481-1482-1483-1484-1485-1486-1487-1488-1489-1490-1491-1492-1493-1494-1495-1496-1497-1498-1499-1500-1501-1502-1503-1504-1505-1506-1507-1508-1509-1510-1511-1512-1513-1514-1515-1516-1517-1518-1519-1520-1521-1522-1523-1524-1525-1526-1527-1528-1529-1530-1531-1532-1533-1534-1535-1536-1537-1538-1539-1540-1541-1542-1543-1544-1545-1546-1547-1548-1549-1550-1551-1552-1553-1554-1555-1556-1557-1558-1559-1560-1561-1562-1563-1564-1565-1566-1567-1568-1569-1570-1571-1572-1573-1574-1575-1576-1577-1578-1579-1580-1581-1582-1583-1584-1585-1586-1587-1588-1589-1590-1591-1592-1593-1594-1595-1596-1597-1598-1599-1600-1601-1602-1603-1604-1605-1606-1607-1608-1609-1610-1611-1612-1613-1614-1615-1616-1617-1618-1619-1620-1621-1622-1623-1624-1625-1626-1627-1628-1629-1630-1631-1632-1633-1634-1635-1636-1637-1638-1639-1640-1641-1642-1643-1644-1645-1646-1647-1648-1649-1650-1651-1652-1653-1654-1655-1656-1657-1658-1659-1660-1661-1662-1663-1664-1665-1666-1667-1668-1669-1670-1671-1672-1673-1674-1675-1676-1677-1678-1679-1680-1681-1682-1683-1684-1685-1686-1687-1688-1689-1690-1691-1692-1693-1694-1695-1696-1697-1698-1699-1700-1701-1702-1703-1704-1705-1706-1707-1708-1709-1710-1711-1712-1713-1714-1715-1716-1717-1718-1719-1720-1721-1722-1723-1724-1725-1726-1727-1728-1729-1730-1731-1732-1733-1734-1735-1736-1737-1738-1739-1740-1741-1742-1743-1744-1745-1746-1747-1748-1749-1750-1751-1752-1753-1754-1755-1756-1757-1758-1759-1760-1761-1762-1763-1764-1765-1766-1767-1768-1769-1770-1771-1772-1773-1774-1775-1776-1777-1778-1779-1780-1781-1782-1783-1784-1785-1786-1787-1788-1789-1790-1791-1792-1793-1794-1795-1796-1797-1798-1799-1800-1801-1802-1803-1804-1805-1806-1807-1808-1809-1810-1811-1812-1813-1814-1815-1816-1817-1818-1819-1820-1821-1822-1823-1824-1825-1826-1827-1828-1829-1830-1831-1832-1833-1834-1835-1836-1837-1838-1839-1840-1841-1842-1843-1844-1845-1846-1847-1848-1849-1850-1851-1852-1853-1854-1855-1856-1857-1858-1859-1860-1861-1862-1863-1864-1865-1866-1867-1868-1869-1870-1871-1872-1873-1874-1875-1876-1877-1878-1879-1880-1881-1882-1883-1884-1885-1886-1887-1888-1889-1890-1891-1892-1893-1894-1895-1896-1897-1898-1899-1900-1901-1902-1903-1904-1905-1906-1907-1908-1909-1910-1911-1912-1913-1914-1915-1916-1917-1918-1919-1920-1921-1922-1923-1924-1925-1926-1927-1928-1929-1930-1931-1932-1933-1934-1935-1936-1937-1938-1939-1940-1941-1942-1943-1944-1945-1946-1947-1948-1949-1950-1951-1952-1953-1954-1955-1956-1957-1958-1959-1960-1961-1962-1963-1964-1965-1966-1967-1968-1969-1970-1971-1972-1973-1974-1975-1976-1977-1978-1979-1980-1981-1982-1983-1984-1985-1986-1987-1988-1989-1990-1991-1992-1993-1994-1995-1996-1997-1998-1999-2000-2001-2002-2003-2004-2005-2006-2007-2008-2009-2010-2011-2012-2013-2014-2015-2016-2017-2018-2019-2020-2021-2022-2023-2024-2025-2026-2027-2028-2029-2030-2031-2032-2033-2034-2035-2036-2037-2038-2039-2040-2041-2042-2043-2044-2045-2046-2047-2048-2049-2050-2051-2052-2053-2054-2055-2056-2057-2058-2059-2060-2061-2062-2063-2064-2065-2066-2067-2068-2069-2070-2071-2072-2073-2074-2075-2076-2077-2078-2079-2080-2081-2082-2083-2084-2085-2086-2087-2088-2089-2090-2091-2092-2093-2094-2095-2096-2097-2098-2099-2100-2101-2102-2103-2104-2105-2106-2107-2108-2109-2110-2111-2112-2113-2114-2115-2116-2117-2118-2119-2120-2121-2122-2123-2124-2125-2126-2127-2128-2129-2130-2131-2132-2133-2134-2135-2136-2137-2138-2139-2140-2141-2142-2143-2144-2145-2146-2147-2148-2149-2150-2151-2152-2153-2154-2155-2156-2157-2158-2159-2160-2161-2162-2163-2164-2165-2166-2167-2168-2169-2170-2171-2172-2173-2174-2175-2176-2177-2178-2179-2180-2181-2182-2183-2184-2185-2186-2187-2188-2189-2190-2191-2192-2193-2194-2195-2196-2197-2198-2199-2200-2201-2202-2203-2204-2205-2206-2207-2208-2209-2210-2211-2212-2213-2214-2215-2216-2217-2218-2219-2220-2221-2222-2223-2224-2225-2226-2227-2228-2229-2230-2231-2232-2233-2234-2235-2236-2237-2238-2239-2240-2241-2242-2243-2244-2245-2246-2247-2248-2249-2250-2251-2252-2253-2254-2255-2256-2257-2258-2259-2260-2261-2262-2263-2264-2265-2266-2267-2268-2269-2270-2271-2272-2273-2274-2275-2276-2277-2278-2279-2280-2281-2282-2283-2284-2285-2286-2287-2288-2289-2290-2291-2292-2293-2294-2295-2296-2297-2298-2299-2300-2301-2302-2303-2304-2305-2306-2307-2308-2309-2310-2311-2312-2313-2314-2315-2316-2317-2318-2319-2320-2321-2322-2323-2324-2325-2326-2327-2328-2329-2330-2331-2332-2333-2334-2335-2336-2337-2338-2339-2340-2341-2342-2343-2344-2345-2346-2347-2348-2349-2350-2351-2352-2353-2354-2355-2356-2357-2358-2359-2360-2361-2362-2363-2364-2365-2366-2367-2368-2369-2370-2371-2372-

# HRV-1 Sequence of Operation

## Overview

The system includes HRV-1 and the related indoor VRF units (VRF-1 through 13) that it provides make-up air for. The Kitchen Make-up Air Unit MUAU is also very interactive with this system so please refer to that sequence of operation for additional information.

The system includes the following components:

- Motorized power open/spring return closed intake dampers
- MERV13 supply air (outdoor air) filters
- A constant speed enthalpy wheel
- A supplemental electric heating coil with a silicon controlled rectifier to allow modulating capacity control
- A constant speed supply fan
- Variable flow refrigeration indoor units which include:
  1. MERV 8 filters
  2. Direct expansion refrigerant coils capable of heating or cooling
  3. Variable speed supply fans
- MERV 8 exhaust filters
- A constant speed exhaust fan
- Motorized power open/spring return closed exhaust dampers

The majority of the indoor units will run continuously but will have scheduling capabilities provided in the software if schedules are desired at some point in the future. Additional information regarding the indoor units can be found in the Variable Flow Refrigeration System (VRF) sequence of operation.

The following three zones will have their indoor units cycled by an occupancy sensor due to the highly variable occupancy.

- Day Room
- Beanery
- Fitness Center

These zones will also have their CO2 levels monitored for LEED purposes. The CO2 sensors will provide no active control function and are for monitoring only. Outdoor air from the HRV will be delivered to these zones even when the indoor unit is shut down.

## Damper Interlocks

The AHU supply and exhaust dampers shall be commanded open any time the unit is commanded on via factory interlock wiring.

## Start/Stop Control

HRV-1 shall include a scheduling feature to allow scheduled operation to be implemented if so desired. However, the schedule shall be set initially to provide round-the-clock operation.

# HRV-1 Sequence of Operation

(Continued)

## Power Failure Recovery

In the event of a power failure, the HRV-1 logic shall be arranged to provide for an orderly restart of the system in conjunction with the other systems in the facility, including the utility systems serving it. The details of the specific restart sequence shall be coordinated with the design team and facility operations during submittal review and the start-up and commissioning process.

## Start-up Sequencing

An enable command from the Siemens control system to HRV-1, issued for any purpose, shall:

- Immediately start the exhaust fan and open the exhaust damper via the factory interlock wiring.
- Immediately start the enthalpy wheel via an exhaust fan starter auxiliary contact and the factory interlock wiring.
- Immediately start the supply fan and open the supply damper if the frost control cycle is not active via an exhaust fan starter auxiliary contact and the factory interlock wiring. (The frost control cycle is described in the next section.)

On start-up of HRV-1, the operation of the VRF systems associated with the system shall be delayed for 15 minutes (adjustable) to allow the supply system conditions to stabilize.

## Shut Down Sequencing

A shut down command to HRV-1, issued for any purpose, shall immediately disable the electric reheat coil and the VRF systems associated with HRV-1. The command shall also trigger a shutdown timer that will disable the HRV-1 system after 5 minutes (adjustable) to ensure that any residual heat in the electric heating coils is dissipated prior to shut down in an effort to prevent nuisance high temperature safety trips at the electric resistance heater. When the disable command is issued by the Siemens system, the factory interlock wiring in HRV-1 shall shut down the exhaust fan, supply fan and enthalpy wheel and return the dampers to the fully closed position.

## Discharge Temperature Control

## Enthalpy Wheel Control

HRV-1 incorporates an enthalpy wheel to recover energy from the exhaust air stream and move it to the supply air stream. Supplemental cooling is not provided. Supplemental heating is provided and controlled as described below.

The enthalpy wheel is a constant speed wheel with no active control of the leaving air temperature. It is started via the same factory interlock wiring that opens the dampers and starts the fans via the HRV-1 enable command from the Siemens system as described above.

# HRV-1 Sequence of Operation

(Continued)

## Frost Control Cycle

A factory wired frost control cycle is initiated based on the pressure drop across the supply air side of the enthalpy wheel when the outdoor air temperature at the intake to the unit is below 5°F as sensed by a factory furnished and wired thermostat.

When the pressure drop exceeds the setting of the factory furnished and wired pressure switch, a time delay relay cycles the supply fan off for 5 minutes and then on for 30 minutes (factory set, adjustable). During this period of time, the enthalpy wheel continues to rotate, allowing the heat in the exhaust air stream to defrost the wheel.

When the outdoor temperature rises above 5°F plus the fixed differential of the factory outdoor air temperature sensor, the frost control cycle is disable.

An isolated contact factory furnished contact closes when the frost control cycle is occurring. The DDC system monitors this contact to provide annunciation of the frost control cycle.

## Supplemental Heat Control

Supplemental heating is provided by an electric reheat coil which is controlled by a factory furnished and installed Silicon Controlled Rectifier (SCR) with a remote set point adjustment capability from the Siemens system. The Siemens systems independently monitors the leaving air temperature from the electric heating coil (along with other unit parameters, see the point list for details) but the electric resistance coil uses a factory furnished and wired temperature sensor to directly control the electric resistance heater via the factory furnished and installed SCR.

The Siemens system enables the supplemental electric heat when the outdoor temperature drops below the discharge air temperature set point for 30 minutes or more (adjustable). When the outdoor air temperature rises above the enable set point, the supplemental heater is disabled.

Once enabled, the factory furnished SCR modulates the capacity of the electric heater to maintain the desired discharge air temperature ("neutral air" 70°F initial set point, adjustable via the Siemens system). Via the physical configuration of the system, the first stage or heating will be provided by the enthalpy wheel transferring energy from the exhaust stream to the outdoor air stream. This is a passive process with no direct control over the temperature and humidity provided in the supply air stream.

If the supply temperature downstream of the energy recovery wheel deviates below the supply air temperature set point because the recovered energy is insufficient to meet it, then the electric heat is modulated from minimum towards maximum capacity by the SCR. A deviation above set point reverses the sequence.

# HRV-1 Sequence of Operation

(Continued)

Factory furnished, hardwired safety interlocks will shut down the electric resistance heater irrespective of any commands from Siemens or the SCR if:

- The supply fan stops operating as sensed by a differential pressure switch monitoring the pressure drop across the electric heating element.
- An automatic reset thermal limit switch senses a temperature in the duct heater that exceeds its set point.
- A manual reset thermal limit switch senses a temperature in the duct heater that exceeds its set point, which is higher than the automatic reset thermal switch

## Ventilation Operation

HRV-1 operates at a constant volume. Carbon Dioxide (CO2) sensors monitor CO2 levels in the Day Room, Beanery and the Fitness Center and initiate alarms if the levels exceed safe thresholds for 5 minutes or more (1,000 ppm, adjustable).

Nitrous Oxide and Carbon Monoxide sensors monitor the levels of those gases in the corridors with access to the apparatus bay on the first floor and basement levels and initiate alarms if the hard coded threshold levels in the sensors are exceeded (100 ppm for CO and 5 ppm for NO2).

## Indoor Fan Coil Unit Controls

See the narrative sequence of operations for the VRF systems for the details of the sequence of operation associated with the indoor fan coil units. Note that HRV-1 shall continue to supply ventilation air to an indoor fan coil unit even if it is in the unoccupied cycle.

## Safety Interlocks

The HRV1 fire alarm interface and supply duct freezestat shall shut down the system, no matter what the position the any starter Hand-Off-Auto switches are in if an unsafe operating condition is detected. Note that the fire alarm shut down is provided via software logic in the DDC system based on one hard wired input from the fire alarm control panel. This feature is not required by code and is being provided as an added measure of safety in the event of an alarm.

Factory furnished and wired motor overloads shall shut down and lock out either fan no matter what position their starter Hand-Off-Auto selector switches are in.

## Field Wiring Information

The wiring diagram for the basis of design unit has been included for bidding purposes on sheet TC 5.12.

Weinstein A+U  
Architects + Urban Designers LLC  
2200 Western Avenue Suite 301  
Seattle, WA 98121  
T 206 443 8806  
F 206 443 1218  
Weinstein@au.com

© 2013 Weinstein AU - These documents have been prepared specifically for the above named project. They are not suitable for use on other projects or in other locations without the approval and participation of the Architect.



NW Satellite Office  
8560 North Buchanan Avenue  
Portland, Oregon, 97203  
Phone: (503) 286-1494  
DSellers@FacilityDynamics.com

Corporate Office  
6760 Alexander Bell Drive, Suite 200  
Columbia, MD 21046  
Phone: (410) 290-0900  
www.FacilityDynamics.com



CITY OF SEATTLE

Fire Station 22  
901 E. Roanoke St.  
Seattle WA 98102

100% CD SET



100% CONSTRUCTION DOCUMENTS

PROJECT-NO	13004
DRAWN	DAS
CHECKED BY	CBM
DATE	1/11/16
REVISIONS	DATE
△	Revision 1 - Addendum 5 - 2016-02-19
△	
△	
△	
△	
△	
SHEET TITLE	HRV-1 and MUAU Sequence of Operation

SHEET NUMBER  
**TC 6.16**

# MUAU Sequence of Operation

## Overview

The system includes the Makeup Air Unit MUAU, Exhaust Fan EF-6, the Kitchen Hood, and the discharge hood RV-1. This system is interactive with system HRV-1 so please refer to that sequence of operation for additional information.

The MUAU includes the following components:

- Factory motorized and wired power open/spring return closed outdoor air dampers
- MERV 14 filters
- Supply fan
- Eight stage gas furnace

EF-6 is integral with the kitchen hood and is actually two exhaust fans that operate as one fan.

## Damper Interlocks

The MUAU supply damper shall be commanded open any time the unit is enabled via factory interlock wiring.

## Start/Stop Control

The MAUA system operation is manually initiated by the occupants in the Beanery when they want to use the kitchen exhaust hood. A manual switch at the hood is hard wire interlocked to do the following when it is turned on.

1. Open the discharge dampers in RV-1.
2. Enable the operation of exhaust fan EF-6.
3. Enable the operation of the MUAU.

When the switch is turned back off, the system is shut down and the dampers close.

## Power Failure Recovery

In the event of a power failure, the MUAU system will need to be manually restarted if it is still needed by the occupants of the space.

## Discharge Temperature Control

The MUAU is a 100% outdoor air unit that provides no supplemental cooling. The discharge diffusers are located in close proximity to the hood to minimize the impact of untreated outdoor air on the space conditions on hot or humid days. In addition, the ductwork in the Beanery is insulated to prevent condensation problems if the operation of the system is prolonged and it causes the dew point temperature in the space to drift up. However, the design intent is that the kitchen hood only would be in operation when there is stovetop is in use

Supplemental heating is provided by an 8 stage modulating gas furnace. The DDC system enables the gas furnace any time the outdoor temperature is below 70°F (adjustable) and disables it anytime the outdoor temperature is above 72°F (adjustable). Adjust the set point on the factory controller to 80°F (adjustable in the field) to ensure that the Siemens system has control of enabling and disabling the heating system associated with MUAU.

# MUAU Sequence of Operation

(Continued)

When the gas furnace is enabled, as the supply temperature deviates below set point, the gas burner is modulated from minimum towards maximum capacity by a factory furnished and installed controller in 8 steps. A deviation above set point reverses the sequence.

## Safety Interlocks

The MUAU fire alarm interface and supply duct freezestat shall shut down the system, no matter what the position of any Hand-Off-Auto switches are in if an unsafe operating condition is detected. Note that the fire alarm shut down is provided via software logic in the DDC system based on one hard wired input from the fire alarm control panel. This feature is not required by code and is being provided as an added measure of safety in the event of an alarm.

Motor overloads shall shut down and lock out any fan no matter what position their starter Hand-Off-Auto selector switches are in.

1 Add. 05

Weinstein A+U  
Architects + Urban Designers LLC  
2200 Western Avenue Suite 301  
Seattle, WA 98121  
T 206 443 8806  
F 206 443 1218  
Weinsteinau.com

© 2013 Weinstein AU - These documents have been prepared specifically for the above named project. They are not suitable for use on other projects or in other locations without the approval and participation of the Architect.



NW Satellite Office  
8560 North Buchanan Avenue  
Portland, Oregon, 97203  
Phone: (503) 286-1494  
DSellers@FacilityDynamics.com

Corporate Office  
6760 Alexander Bell Drive, Suite 200  
Columbia, MD 21046  
Phone: (410) 290-0900  
www.FacilityDynamics.com



**CITY OF SEATTLE**

**Fire Station 22**  
901 E. Roanoke St.  
Seattle WA 98102

100% CD SET



100% CONSTRUCTION DOCUMENTS

PROJECT-NO	13004
DRAWN	DAS
CHECKED BY	CBM
DATE	2/19/16
REVISIONS	DATE
△	Revision 1 - Addendum 5 - 2016-02-19
△	
△	
△	
△	
△	
SHEET TITLE	HRV-1 and MUAU Sequence of Operation (Continued)

SHEET NUMBER  
**TC 6.17**

D:\Projects\13004\Fire Station 22\13004-Fire Station 22-100% CD-16-02-19.dwg, 1/11/16, 11:58:14 AM, David A. Sellers, P.E.

# HRV-2 Sequence of Operation

## Overview

The HRV-2 system serves the Bunker Gear storage area and includes the following pieces of equipment.

- Rooftop heat recovery unit HRV-2, which includes:
  1. Motorized, power open/spring return closed intake dampers
  2. MERV13 supply air (outdoor air) filters
  3. **A cross-flow plate style air to air heat exchanger**
  4. A two speed, VFD controlled supply fan
  5. A two speed Electrically Commutated Motor (ECM) controlled exhaust fan
  6. Motorized, power open/spring return closed exhaust dampers
- Destratification fan
- Gas fired Unit Heater 1

## Combustion Air Provisions

Combustion air for Unit Heater 1 is provided by a concentric intake/flue system. See Detail 5 on sheet M801 for more information.

## Damper Interlocks

The HRV-2 supply and exhaust dampers shall be commanded open any time the unit is commanded on via factory wiring.

## Start/Stop Control

HRV-2 shall include a scheduling feature to allow scheduled operation to be implemented if so desired. However, the schedule shall be set initially to provide round-the-clock operation on the minimum flow ventilation cycle.

## Power Failure Recovery

In the event of a power failure, the HRV-2 logic shall be arranged to provide for an orderly restart of the system in conjunction with the other systems in the facility, including the utility systems serving it. The details of the specific restart sequence shall be coordinated with the design team and facility operations during submittal review and the start-up and commissioning process.

## Start-up Sequencing

An enable command from the Siemens control system to HRV-2, issued for any purpose, shall:

- Immediately start the exhaust fan and open the exhaust damper via the
- Immediately start the supply fan and open the supply damper if the frost control cycle is not active via an exhaust fan starter auxiliary contact and the factory interlock wiring. (The frost control cycle is described in a subsequent section.)

# HRV-2 Sequence of Operation

(Continued)

## Shut Down Sequencing

When the disable command is issued to HRV-2 by the Siemens system, the factory interlock wiring in HRV-2 shall shut down the exhaust fan, and supply fan and return the dampers to the fully closed position.

## High Flow/Minimum Flow Ventilation Cycle Control

HRV-2 is equipped with a variable speed drive on both the supply fan and a two speed EMC motor on the exhaust fan. The control system shall command the supply fan VSD and the exhaust fan ECM motor as required to achieve either a high flow ventilation cycle or a minimum flow ventilation cycle. The fan sheaves shall be adjusted so that the high flow ventilation rates/design flow rates and pressure relationships associated with it are achieved with the supply fan VFD and exhaust fan ECM at full speed to maximize drive efficiency.

## Minimum Flow Ventilation Cycle

HRV-2 is enabled by the DDC system to run continuously on low speed to provide minimum ventilation for the bunker storage room. The low speed setting for the supply fan variable speed drive shall be operator adjustable via the system graphic with access restricted to a high level operator.

The low speed setting on the ECM motor is made via a set point adjustment on the device. The final setting shall be documented in the system graphic in an editable text object with access restricted to a high level operator.

The VFD and ECM motor low speed settings shall be determined by a coordinated effort between the control contractor, the balancing contractor, and the commissioning provider to identify the required supply and exhaust flows and associated pressure relationships. Note that this determination shall be made after setting up the fans to deliver the design maximum flow with the VFD/ECM at full speed as indicated previously.

A 12 hour, no hold position, spring wound interval timer acting as an input to the DDC system shall trigger a high speed operating cycle. When the interval timer times out, the system shall revert to the normal, low speed ventilation mode.

## Frost Control Cycle

A factory wired control circuit shall provide a frost control cycle to protect the plate and frame heat exchanger from frost building up at low ambient temperatures by cycling the supply fan off for a predetermined time.

# HRV-2 Sequence of Operation

(Continued)

Specifically, when the exhaust air temperature leaving the plate heat exchanger drops below 35°F (adjustable in the field at the unit in the factory furnished and wired exhaust air thermostat), the thermostat triggers a time delay relay. The time delay relay then cycles the supply fan off for 5 minutes and on for 30 minutes (both adjustable in the field at the factory furnished and wired time delay relay). This cycle repeats until the air temperature leaving the plate heat exchanger rises back above the set point of the exhaust air thermostat.

An isolated factory furnished contact closes when the frost control cycle is occurring. The DDC system monitors this contact to provide annunciation of the frost control cycle.

## Space Temperature Control

Bunker unit heater UH-1 shall be controlled based on space temperature. During the low speed operating cycle the space temperature set point shall be 60°F (adjustable via software). During the high speed operating cycle, the space temperature set point shall be 80°F (adjustable via software and via a set point adjustment on the space temperature sensor between 70 and 90°F).

If the space temperature drops below the current set point, UH-1 shall cycle its fan on. If the space temperature continues to drop, UH-1 shall cycle on its gas valve. When the space temperature rises back above the current set point plus 2°F differential (adjustable), UH-1 gas valve shall cycle back off. If the space temperature rises above the current set point plus 4°F differential (adjustable), UH-1 fan shall cycle back off.

## Safety Interlocks

The variable speed drive shall be equipped with Hand-Off-Auto switches. In the "Off" position, the fan shall be shut down no matter what the status of the command from the DDC system is.

In the "Hand" position, the fan shall run continuously at a speed set locally at the drive control panel, no matter what the status of the commands from the DDC system are

In the "Auto" position, the fan shall be controlled by the DDC system contacts and speed commands per the operating sequence described here-in.

The HRV-2 supply duct freezestat shall shut down the system, no matter what the position the VFD Hand-Off-Auto Switches are in. Motor overloads shall shut down and lock out either fan no matter what position their starter Hand-Off-Auto selector switches are in.

# HRV-2 Sequence of Operation

(Continued)

## Ceiling Fan

The ceiling fan shall be wired to a factory furnished, field installed control switch that allows the occupants to turn the fan on or off and select one of three speeds.

A relay piloted by the DDC system shall enable operation of the fan. The relay shall cycle off for 1 minute (adjustable) every day at 2 am (adjustable) if HRV-2 is in the low speed cycle to sweep the fan off and ensure they are not operating when they are not required. If HRV-2 is in the high speed cycle at the sweep time, the fan shall not be commanded off.

A CT monitoring the total current drawn by the fan provides a proof of operation input to the DDC system.

# HRV-3 Sequence of Operation

## Overview

The HRV-3 system serves the Decon/Wash area, the First Floor West Circulation Corridor, the Maintenance area, and the Battery Charging area. It also provides supplemental ventilation to the Bunker Gear Storage room.

## Damper Interlocks

The HRC-3 supply and exhaust dampers shall be commanded open any time the unit is commanded on via factory interlock wiring.

## Start/Stop Control

HRV-3 shall include a scheduling feature to allow scheduled operation to be implemented if so desired. However, the schedule shall be set initially to provide round-the-clock operation.

## Power Failure Recovery

In the event of a power failure, the HRV-3 logic shall be arranged to provide for an orderly restart of the system in conjunction with the other systems in the facility, including the utility systems serving it.

## Start-up Sequencing

An enable command from the Siemens control system to HRV-2, issued for any purpose, shall:

- Immediately start the exhaust fan and open the exhaust damper via the
- Immediately start the supply fan and open the supply damper if the frost control cycle is not active via an exhaust fan starter auxiliary contact and the factory interlock wiring. (The frost control cycle is described in a subsequent section.)

Weinstein A+U  
Architects + Urban Designers LLC  
2200 Western Avenue Suite 301  
Seattle, WA 98121  
T 206 443 8806  
F 206 443 1218  
Weinsteinau.com

© 2013 Weinstein AU - These documents have been prepared specifically for the above named project. They are not suitable for use on other projects or in other locations without the approval and participation of the Architect.



NW Satellite Office  
8560 North Buchanan Avenue  
Portland, Oregon, 97203  
Phone: (503) 286-1494  
DSellers@FacilityDynamics.com

Corporate Office  
6760 Alexander Bell Drive, Suite 200  
Columbia, MD 21046  
Phone: (410) 290-0900  
www.FacilityDynamics.com



**CITY OF SEATTLE**

**Fire Station 22**  
901 E. Roanoke St.  
Seattle WA 98102

100% CD SET



100% CONSTRUCTION DOCUMENTS

PROJECT-NO	13004
DRAWN	DAS
CHECKED BY	CBM
DATE	2/19/16
REVISIONS	DATE
△	Revision 1 - Addendum 5 - 2016-02-19
△	
△	
△	
△	
△	
SHEET TITLE	HRV- 2 and 3 Sequence

SHEET NUMBER  
**TC 6.19**











# Variable Flow Refrigeration (VRF) Systems Sequence of Operation (Continued)

## State Points

The BACnet state points (i.e. On/off State, Operating State, Fan Speed State, Room Temperature, and Air Direction State) will provide Facility Operations with the current operating state selected by the zone occupants in addition to providing proof of operation feedback for any schedules, set back cycles, etc. they implement in the future.

## Occupancy Driven Schedules

The following zones are to be provided with occupancy driven operating hours based on the occupancy sensors that are located in them.

- Fitness Area
- Day Room and Beanery Area
- Bunk Rooms

When an occupancy sensor in these areas detects motion the fan coil unit or unit's serving the area are turned on and allowed to operate to actively control the space temperature at the occupied heating and cooling set points (70°F and 72°F respectively, both adjustable). When a cycle is triggered, the system will remain in the occupied cycle for a minimum of 15 minutes (adjustable) from the last time that motion is detected.

Ventilation air to a zone is provided via HRV-1. Dampers in the ventilation air duct open and close as a function of zone occupancy.

At the end of an occupied cycle, the fan coil unit or units serving the area are turned off and the temperature in the area is allowed to drift between the unoccupied heating and cooling set points (initial settings of 68°F and 78°F respectively). As long as the zone temperature is between the unoccupied set points, no active cooling or heating is provided. But, if the temperature drifts outside the set-back temperature range, the unit is placed in occupied mode and operates until the space temperature is driven back inside the set back/set up range at which time the unit is shut back down again.

Functional testing technique shall be used to determine the appropriate set back and set up temperatures for the zones with occupancy based schedule during the commissioning and warranty period. Test results shall be used to optimize the initial set points provided and tailor them to the thermal mass (stored energy) and HVAC process energy associated with the zone served.

# Variable Flow Refrigeration (VRF) Systems Sequence of Operation (Continued)

## Error Codes and Alarms

The BACnet error code and alarm point shall trigger logic in the Siemens network designed to facilitate remote diagnostics from the Facility Operations office. In general terms the points will trigger alarms and alarm messages with the text of the message providing additional guidance regarding the actions required to resolve the problem. The error messages shall be presented in the system graphics running at the Siemens Operator Work Station (OWS).

Each error code shall have a specific customized message associated with it. The details contained in the message will be coordinated with Facility Operations at the time of the control submittal review.

## Filter Status

The BACnet filter points shall be used to trigger an alarm annunciating the need to change a filter and to allow the operators to reset the filter alarm once the filters have been serviced. The alarm set points shall be coordinated during the start-up and commissioning process to match the capabilities of the HRV fans in terms of ensuring they deliver the required air flows at a minimum with dirty filters.

The BACnet Prohibit Filter Sign Reset point shall be configured to prevent the filter alarm from being reset from the remote controllers located in FS-29.

## Diagnostic Points

The VRF technology employs numerous analog sensors monitoring system temperatures, pressures, currents and other physical properties as required to control and optimize the system. Most, if not all of this data is available via the VRF Maintenance Tool Software. However, few if any of the points are made available as BACnet objects for direct access by the Siemens control system.

To improve operability certain key parameters as outlined in the point lists, will be brought into the Siemens network as physical points to allow preliminary diagnostics to be performed via the Siemens OWS. Some of the diagnostics will simply present key data to the operator for their assessment and judgment. However, in some instances control logic will be used to combine information from multiple sensors to generate an alarm.

# Variable Flow Refrigeration (VRF) Systems Sequence of Operation (Continued)

Control logic will also be used to imply operating pressures based on measure temperatures in the refrigeration system by assuming it is operating as a saturated system and using look-up table functions and/or calculations to infer one parameter from the other. The details of the logic required for diagnostics will be developed during the submittal process once the specific items of equipment to be provided for the project are established, including make and model.

The current project along with FS18, FS29, and several existing facilities with VRF systems will serve as a pilot projects to allow the City to assess the practical issues associated with this approach as well as the cost benefit.

Weinstein A+U  
Architects + Urban Designers LLC  
2200 Western Avenue Suite 301  
Seattle, WA 98121  
T 206 443 8806  
F 206 443 1218  
Weinsteinau.com

© 2013 Weinstein AU - These documents have been prepared specifically for the above named project. They are not suitable for use on other projects or in other locations without the approval and participation of the Architect.



NW Satellite Office  
8560 North Buchanan Avenue  
Portland, Oregon, 97203  
Phone: (503) 286-1494  
DSellers@FacilityDynamics.com

Corporate Office  
6760 Alexander Bell Drive, Suite 200  
Columbia, MD 21046  
Phone: (410) 290-0900  
www.FacilityDynamics.com



**CITY OF SEATTLE**

**Fire Station 22**  
901 E. Roanoke St.  
Seattle WA 98102

**100% CD SET**



**100% CONSTRUCTION DOCUMENTS**

PROJECT-NO	13004
DRAWN	DAS
CHECKED BY	CBM
DATE	1/11/16
REVISIONS	DATE
△	
△	
△	
△	
△	
△	
△	

SHEET TITLE  
**VRF Sequence of Operation Continued**

SHEET NUMBER  
**TC 6.21**

Revised Via Addendum 5

D:\Projects\2013\013004\Fire Station 22\030501-030502-030503-030504-030505-030506-030507-030508-030509-030510-030511-030512-030513-030514-030515-030516-030517-030518-030519-030520-030521-030522-030523-030524-030525-030526-030527-030528-030529-030530-030531-030532-030533-030534-030535-030536-030537-030538-030539-030540-030541-030542-030543-030544-030545-030546-030547-030548-030549-030550-030551-030552-030553-030554-030555-030556-030557-030558-030559-030560-030561-030562-030563-030564-030565-030566-030567-030568-030569-030570-030571-030572-030573-030574-030575-030576-030577-030578-030579-030580-030581-030582-030583-030584-030585-030586-030587-030588-030589-030590-030591-030592-030593-030594-030595-030596-030597-030598-030599-030600-030601-030602-030603-030604-030605-030606-030607-030608-030609-030610-030611-030612-030613-030614-030615-030616-030617-030618-030619-030620-030621-030622-030623-030624-030625-030626-030627-030628-030629-030630-030631-030632-030633-030634-030635-030636-030637-030638-030639-030640-030641-030642-030643-030644-030645-030646-030647-030648-030649-030650-030651-030652-030653-030654-030655-030656-030657-030658-030659-030660-030661-030662-030663-030664-030665-030666-030667-030668-030669-030670-030671-030672-030673-030674-030675-030676-030677-030678-030679-030680-030681-030682-030683-030684-030685-030686-030687-030688-030689-030690-030691-030692-030693-030694-030695-030696-030697-030698-030699-030700-030701-030702-030703-030704-030705-030706-030707-030708-030709-030710-030711-030712-030713-030714-030715-030716-030717-030718-030719-030720-030721-030722-030723-030724-030725-030726-030727-030728-030729-030730-030731-030732-030733-030734-030735-030736-030737-030738-030739-030740-030741-030742-030743-030744-030745-030746-030747-030748-030749-030750-030751-030752-030753-030754-030755-030756-030757-030758-030759-030760-030761-030762-030763-030764-030765-030766-030767-030768-030769-030770-030771-030772-030773-030774-030775-030776-030777-030778-030779-030780-030781-030782-030783-030784-030785-030786-030787-030788-030789-030790-030791-030792-030793-030794-030795-030796-030797-030798-030799-030800-030801-030802-030803-030804-030805-030806-030807-030808-030809-030810-030811-030812-030813-030814-030815-030816-030817-030818-030819-030820-030821-030822-030823-030824-030825-030826-030827-030828-030829-030830-030831-030832-030833-030834-030835-030836-030837-030838-030839-030840-030841-030842-030843-030844-030845-030846-030847-030848-030849-030850-030851-030852-030853-030854-030855-030856-030857-030858-030859-030860-030861-030862-030863-030864-030865-030866-030867-030868-030869-030870-030871-030872-030873-030874-030875-030876-030877-030878-030879-030880-030881-030882-030883-030884-030885-030886-030887-030888-030889-030890-030891-030892-030893-030894-030895-030896-030897-030898-030899-030900-030901-030902-030903-030904-030905-030906-030907-030908-030909-030910-030911-030912-030913-030914-030915-030916-030917-030918-030919-030920-030921-030922-030923-030924-030925-030926-030927-030928-030929-030930-030931-030932-030933-030934-030935-030936-030937-030938-030939-030940-030941-030942-030943-030944-030945-030946-030947-030948-030949-030950-030951-030952-030953-030954-030955-030956-030957-030958-030959-030960-030961-030962-030963-030964-030965-030966-030967-030968-030969-030970-030971-030972-030973-030974-030975-030976-030977-030978-030979-030980-030981-030982-030983-030984-030985-030986-030987-030988-030989-030990-030991-030992-030993-030994-030995-030996-030997-030998-030999-040000