

## Introduction to Commissioning Control Systems



**Presented By:** 

- David Sellers; Facility Dynamics Engineering
- Senior Engineer
- April 11, 2019

## Agenda (and a Bit about Me)

PROPORTIONAL & PNEUMATI CONTROL UN Stabilog

DEC. DUTE®

PROP

### The Path to a Successful Control System





### Complexity, Cx, Reliability, and Persistence

## Control Systems Overview



Automatically adjust a piece of machinery to give us what we want by comparing what is going on to what we want to go on and making appropriate adjustments to the process we want to control

## The Holistic (Green) Goal of the Control System

Automatically adjust a piece of machinery to give us what we want by comparing what is going on to what we want to go on and making appropriate adjustments to the process we want to control as efficiently and sustainably as possible

<u>Commissioning to Meet Space</u> <u>Qualification Criteria vs. Energy</u> <u>Consumption Optimization Focused</u> <u>Commissioning</u> is an example of how quality can be maintained and energy efficiency improved via an EBCx project (downloadable at <u>http://www.av8rdas.com/case-</u>

studies.html)



### The "Three R's"

Repeatable To make, do, or perform an action again (and again, and again, and again ....)

Reliable Giving the same result on successive trials

Robust Sturdy; capable of performing without failure under a wide range of conditions

Automatically adjust a piece of machinery to give us what we want by comparing what is going on to what we want to go on and making appropriate adjustments to the process we want to control

Automatically adjust a piece of machinery to give us what we want by comparing what is going on to what we want to go on and making appropriate adjustments to the process we want to control Inputs Measure the process variable

Automatically adjust a piece of machinery to give us what we<br/>want by comparing what is going on to what we want to go on<br/>and making appropriate adjustments to the process we want to<br/>controlInputsMeasure the process variableOutputsAdjust the controlled variable

Automatically adjust a piece of machinery to give us what we want by comparing what is going on to what we want to go on and making appropriate adjustments to the process we want to control Inputs Measure the process variable Outputs Adjust the controlled variable Our requirements for the process that is Set Point under control, which can be fixed or variable

Automatically adjust a piece of machinery to give us what we want by comparing what is going on to what we want to go on and making appropriate adjustments to the process we want to control Measure the process variable Inputs Adjust the controlled variable Outputs Our requirements for the process that is Set Point under control, which can be fixed or variable **Control Process** Logic and algorithms that tries to bring the controlled variable into agreement with the set point

### A 1914 Central Control System

Image from August 1912 Steam; http://tinyurl.com/August-1912-Steam

## A 1914 Central Control System

- 2.25 miles of interlocking rod
- 1,100 miles of control wire in the form of 5 to 8 conductor cables
- 732 position indicators and transmitters
- 464 control switches
- 382 indicating lamps
- Accurate to 5/8 inch over a 50 foot span



Image courtesy http://ak5.picdn.net/shutterstock/videos/3832016/preview/stock-footage-panama-canal-lock-control-room-close-upmoving-gauge.jpg

## Still Doing Its Thing

## The Other End of the Spectrum

## The Other End of the Spectrum

Main Engine and Controller

- About 50,000 parts
- Rated for multiple flights
- 135 flights with no failures



### The Other End of the Spectrum



Image courtesy

http://large.stanford.edu/courses/2011/ph240/nguyen1/docs/SSME\_PRESENTATION.pdfhttp://large.stanford.edu/courses/2011/ph240/nguyen1/docs/SSME\_PRESENTATION.pdf

## We Are <u>Not</u> Doing Rocket Science

### Seems like:

- We should be able to maintain a 57°F discharge temperature by sequencing preheat with the economizer and the chilled water coil
- We should be able to start around 6:00 am and shut down around 7:00 pm



## We Are *Not* Doing Rocket Science



## Design Phase



### SHEET NOTES: (#)

- External shade motor. Coordinate with external shade vendor to locate a junction box inside the building close enough to the motor location to allow the vendor supplied connector pigtail to reach from the motor to the junction box with sufficient slack to facilitate repairs and maintenance or replacement of the shade.
- Vendor furnished motor connection pigtail. Verify connections with the vendor's installing technician prior to splicing the pigtail to the field wiring. Provide a cord and cable connector for the pigtail where it exits the field wiring junction box.
- Vendor furnished central network controller. Installed in Mechanical Instrumentation Contractor furnished panel DDC-1 by the Mechanical Instrumentation contractor. Coordinate with vendor for proper mounting and final terminations prior to performing the work.
- Vendor furnished network device connector. Installed in Mechanical Instrumentation Contractor furnished panel DDC-1 by the Mechanical Instrumentation contractor. Coordinate with vendor for proper mounting and final terminations prior to performing the work.
- 5. Vendor furnished single zone wall switch. Installed in Mechanical Instrumentation Contractor furnished panel DDC-1 by the Mechanical Instrumentation contractor. Coordinate with vendor for proper mounting and final terminations prior to performing the work. This switch is to be mounted internally in the control panel to limit access to authorized personnel only. It is intended to provide a local means of positioning the blinds if there are problems with the network interface and to support the start-up and commissioning of the system.
- Vendor furnished four motor controller. Installed in Mechanical Instrumentation Contractor furnished panel DDC-1 by the Mechanical Instrumentation contractor. Coordinate with vendor for proper mounting and final terminations prior to performing the work.
- 7. Proof of operation transmitter, furnished and installed in Mechanical Instrumentation Contractor furnished panel DDC-1 by the Mechanical Instrumentation Contractor. Run power wiring for each zone to the motor controller(s) serving it through the transmitter to monitor current on a zone by zone basis for proof of operation purposes.
- Duplex receptacle furnished and installed inside panel DDC-1 by the Mechanical Instrumentation Contractor to power the vendor furnished USB power supply for the central network controller.
- 9. Terminal strip; see specifications for requirements.
- The sizing information here is included for estimating purposes. Each motor requires 4 conductors: Up, Down, Common, and Ground. Coordinate with vendor for final wire and conduit size prior to installation.
- Network drop furnished and installed by SEAIT (City of Seattle IT Department). Coordinate location and final connection in the field with SEAIT.
- Network cable Per Vendor Requirement (Typical for all external shade vendor network connections). Coordinate during the submittal process to match vendor requirements. For estimating purposes, assume CAT 6a cable with RJ45 connectors.
- Control panel DDC-1 with sub-panel. Furnished, fabricated installed by the Mechanical Instrumentation Contractor. Located in Tool Mezzanine 271.
- 14. Mount at roof level. Coordinate final location with the Architect, Control Designer, Owner, Commissioning Provider and Vendor in the field. Allow for a location with-in a 50 foot radius of the location shown on the roof plan.



# Solving the Problem: Own the Control Design and Commissioning Process

- Not as Hard as You Might Think
  - You <u>DON'T</u> need to have:
    - Intimate knowledge of computers
    - Intimate knowledge of networks
    - Intimate knowledge of sensing and actuating technologies
    - Intimate knowledge off differential calculus

# Solving the Problem: Own the Control Design and Commissioning Process

- Not as Hard as You Might Think
  - You <u>DO</u> need to:
    - Understand your mechanical design and the related design targets
    - Apply sound physical principles in the development of your design
    - Communicate clearly
    - Think logically
    - Address the load profile
    - Recognize that all control systems are not created equal out of the box
    - Enforce your requirements

# Solving the Problem: Own the Control Design and Commissioning Process

- Not as Hard as You Might Think
  - You <u>DO</u> need to:
    - Understand your mechanical design and the related design targets
    - Apply sound physical principles in the development of your design
    - Communicate clearly
    - Think logically
    - Address the load profile
    - Recognize that all control systems are not created equal out of the box
    - Enforce your requirements

- Different Network Levels
- Increasing Hardware Capability and Sophistication
- Increasing Network Speed and Protocol Sophistication





Network Architecture is Critical for Determining:

- Network speed
- Data handling capability
- Future flexibility
- Future expansion
- Interoperability











Hardware Capabilities
 are Critical to Success











Specifications Can Define Critical Requirements

- Software
- Memory

clock

• Buffers

programmable

• Downloadable

PC interface

• Fully

- Point capacity Real time
- Global strategies
- A to D resolution
- Speed
- Network protocol











### They're Not All Equal But You Can Get Them Close



### Point List

Bureacratic Affairs	ureacratic Affairs Building 1st Floor Hot Water System													
Point			Sensor			Features						Notes		
Name (Note 6)	Description and Service		Type		Accuracy	Alarms		Trending						
				Paragraph		Limit Warning : Hi Lo Hi Lo	5amples <sup>1</sup>	Comm	ssioning <sup>5</sup> cal <sup>3</sup> Archi	( ve Time <sup>2</sup>	Dperating	1 <sup>5</sup> Archive		
Analog Inputs											1			
STHX-1-LWT	Shell and Tube Heat Exchanger -1 Lvg. W	/tr. Temp. 1,000 Ω P	t RTD with close coupled transmitter and thermometer well	II 25 35 00	0.75% of span for sensor + transmitter	Note 7	60	1 min.	x x	1 min.	X	x	Note 8	
SYSTM-OAT	System OAT	Sing	le point 1,000 $\Omega$ Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitter	None	12	5 min.	x x	5 min.	X	x		
STHX-1-EWT	Shell and Tube Heat Exchanger -1 Ent. W	Vtr. Temp. 1,000 Ω P	t RTD with close coupled transmitter and thermometer well	II 25 35 00	0.75% of span for sensor + transmitter	Note 7	60	1 min.	x x	1 min.	X	x	Note 8	
Analog Outputs (All an	alog outputs to include local override capability and status indication	n at the controller)												
STHX-1-STMVLV-	CMD Shell and Tube Heat Exchanger -1 Steam	n Valve Command	4-20 ma actuator	25 35 13	N/A	N/A N/A N/A N/A	60	1 min.	x x	1 min.	X	x		
Digital Inputs														
HWPMP-1-DPSW	Hot Water Pump -1 Differential Pressure	e Switch	Penn model P74FA-5 differential pressure switch	25 35 16 2.04	N/A	Note 7	10	COV	x x	COV	X	X		
HWPMP-2-DPSW	Hot Water Pump -2 Differential Pressure	e Switch	Penn model P74FA-5 differential pressure switch	25 35 16 2.04	N/A	Note 7	10	COV	x x	COV	X	x		
Virtual Points														
STHX-1-LWT-SP	Shell and Tube Heat Exchanger -1 Lvg. W	/tr. Temp. Set Pnt.	N/A	25 35 00	N/A	Note 7	10	COV	x x	COV	X	X		
STHX-1-LWT-PG	Shell and Tube Heat Exchanger -1 Lvg. W	/tr. Temp. Proportional Gain	N/A	25 35 00	N/A	Note 7	10	COV	x x	COV	X	x		
STHX-1-LWT-IG	Shell and Tube Heat Exchanger -1 Lvg. W	/tr. Temp. Integral Gain	N/A	25 35 00	N/A	Note 7	10	COV	x X	COV	X	x		
STHX-1-LWT-DG	Shell and Tube Heat Exchanger -1 Lvg. W	/tr. Temp. Derivative Gain	N/A	25 35 00	N/A	Note 7	10	COV	x X	COV	X	x		
STHX-1-LWT-OFF	Shell and Tube Heat Exchanger -1 Lvg. W	/tr. Temp. Loop Off Value	N/A	25 35 00	N/A	Note 7	10	COV	x x	COV	X	x	Note 9	
STHX-1-OAT-RST	ILO-SP Shell and Tube Heat Exchanger -1 OAT R	Reset Lo Lmt. Set Pnt.	N/A	25 35 00	N/A	Note 7	10	COV	x X	COV	X	x		
STHX-1-OAT-RST	IHI-SP Shell and Tube Heat Exchanger -1 OAT R	Reset Hi Lmt. Set Pnt.	N/A	25 35 00	N/A	Note 7	10	COV	x x	COV	X	x		
STHX-1-LWT-RST	TLO-SP Shell and Tube Heat Exchanger -1 Lvg. W	/tr. Temp. Reset Lo Lmt. Set	N/A	25 35 00	N/A	Note 7	10	COV	x x	COV	X	x		
STHX-1-LWT-RST	THI-SP Shell and Tube Heat Exchanger -1 Lvg. W	/tr. Temp. Reset Hi Lmt. Set	N/A	25 35 00	N/A	Note 7	10	COV	x x	COV	X	х		
STHX-1-LWT-UNG	DCC-SP Shell and Tube Heat Exchanger -1 Lvg. W	/tr. Temp. Unoccupied Set Pn	N/A	25 35 00	N/A	Note 7	10	COV	x x	COV	X	Х		
STHX-1-CLS-SP	Shell and Tube Heat Exchanger -1 Close	Set Pnt.	N/A	25 35 00	N/A	Note 7	10	COV	x x	cov	×	х		

### Notes:

1. Samples indicates the minimum number of data samples that must be held in the local controller if it is trending the point.

2. Time indicates the required sampling time for the trending function.

3. A check in the local column indicates that the trending only needs to be running in the local controller and the most recent value can write over the last value when the trend buffer fills up.

4. A check in the archive column indicates that the trend data must be archived to the system hard disc when trend buffer fills up so that a continuous trend record is maintained.

5. Commissioning trending requirements only need to be implemented during the start-up and warranty year. After the start-up and warranty process, the control contractor should set the trending parameters to the operating requirements listed if they differ from the commissioning requirements.

6. Point numbers are based on the Owner's point naming convention which is included in the specification. Point names will be verified during the submittal process in the control system integration and coordination meeting.

7. To be determined during the Control System Integration and Coordination Meeting

8. Furnish two wells for installation adjacent to each other by the mechanical contractor. One well is for the sensor and one is for calibration purposes. See the spec and detail.

9. The design intent is that the control loop is a PI loop with derivative added only if tuning in the field indicates that it is necessary to manage the response to a step change or reduce the settling time. Coordinate with the control system designer and Owner proir to adding derviative gain, but provide the point so it is there if needed.

- Point List
- System Diagram



- Point List
- System Diagram
- Narrative
  Sequence

### Bureaucratic Affairs Building Heat Exchanger Leaving Water Temperature Control

### Overview

This sequence applies to the Bureaucratic Affairs Building hot water system steam heat exchanger. The heat exchanger serves finned tube radiation, reheat coils, and a warm-up coil. It is intended to be in operation any time either of the heating hot water pumps are in operation to deliver 170°F water to the loads.

### Steam Valve Control

A temperature sensor located in the discharge piping from the heat exchanger serves as an input to a direct acting Proportional plus Integral (PI) control loop. The output of the control loop is used to modulate a normally open steam valve via a 4-20 ma signal that, in turn generates a 3-15 psi pneumatic signal via an electropneumatic signal convertor for valve actuation.

The set point of the loop is reset based on outdoor air temperature. The reset schedule set points shall be operator adjustable by an operator with administrator credentials. The initial set points are as follows:

- The hot water supply temperature is 170°F when the outdoor air temperature is 7.4°F. These values represent the design conditions.
- The hot water temperature is 102.5°F when the outdoor air temperature is 55°F. These values target matching the finned tube radiation performance to the perimeter heating load at 55°F outdoors with a 72°F indoor temperature.

The set point is are limited to a maximum of  $170^{\circ}$ F and a minimum of  $102.5^{\circ}$ F, no matter what the output of the reset calculation is.

When the building is unoccupied, the hot water set point shall be maintained at 140°F to provide capacity for the night set back cycle when it is initiated.

As the supply temperature deviates above set point, the output of the control loop modulates from 4 ma towards 20 ma (3 psi towards 15 psi to the actuator), causing the normally open valve to modulate closed. As the supply temperature deviates below set point, the output of the control loop modulates from 20 ma towards 4 ma (15 psi towards 3 psi to the actuator), causing the normally open valve to modulate closed.

- Point List
- System Diagram
- Narrative
  Sequence
- Details


## Must Have's

- Point List
- System Diagram
- Narrative
   Sequence
- Details
- Specifications

250800 - Integrated Automation - Commissioning 251116 - Integrated Automation - Network Hardware 251413 - Integrated Automation - Remote Control Panels 251516 - Integrated Automation - Software 253500 - Integrated Automation - Instrumentation and **Terminal Devices** 253513 - Integrated Automation - Actuators and Operators 253516 - Integrated Automation - Sensors and Transmitters 253519 - Integrated Automation - Control Valves 255500 - Integrated Automation - Control of HVAC 255500.13 - Integrated Automation - Control of HVAC-Object Naming Conventions

### **Nice Additions**

• Floor Plans



### **Nice Additions**

- Floor Plans
- Network
   Diagrams



### **Nice Additions**

- Floor Plans
- Network
   Diagrams
- Logic
   Diagrams



### Point Naming Conventions Establish Consistency

Poin	it in the second s
Nar	ne (Note 6)
Ana	log Inputs
	STHX-1-LWT
	SYSTM-OAT
	STHX-1-EWT

#### Analoa Outputs (All analoa outputs to include local

Point		Sensor Peatures Note						Notes				
Name (Note 6)	escription and Service	Туре	Reference Spec	Accuracy	Alarms			Tre	nding			
			Paragraph		Limit Warning	Samples	<sup>1</sup> Con	missioning	<b>)</b> <sup>5</sup>	Opera	iting <sup>5</sup>	
					Hi Lo Hi Lo		Time <sup>2</sup>	Local <sup>3</sup> Ar	chive' Ti	ne² Loc	al <sup>3</sup> Archive	1
Analog Inputs												
STHX-1-LWT	ihell and Tube Heat Exchanger -1 Lvg. Wtr. Temp.	1,000 $\Omega$ Pt RTD with close coupled transmitter and thermometer well	25 35 00	0.75% of span for sensor + transmitter	Note 7	60	1 min.	X	X 1 r	۱in. X	X	Note 8
SYSTM-OAT	ystem OAT	Single point 1,000 $\Omega$ Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitter	None	12	5 min.	X	X 5 r	nin. X	( X	
STHX-1-EWT	shell and Tube Heat Exchanger -1 Ent. Wtr. Temp.	1,000 $arOmega$ Pt RTD with close coupled transmitter and thermometer well	25 35 00	0.75% of span for sensor + transmitter	Note 7	60	1 min.	X	X 1 r	ιin. Χ	( X	Note 8
Analog Outputs (All analog outputs to include local	verride capability and status indication at the controller)											
STHX-1-STMVLV-CMD	Shell and Tube Heat Exchanger -1 Steam Valve Command	4-20 ma actuator	25 35 13	N/A	N/A N/A N/A N/A	60	1 min.	X	X 1 r	nin. X	( X	
Digital Inputs												
HWPMP-1-DPSW	Hot Water Pump -1 Differential Pressure Switch	Penn model P74FA-5 differential pressure switch	25 35 16 2.04	N/A	Note 7	10	COV	X	X CO	x   vc	(   X	
HWPMP-2-DPSW	Hot Water Pump -2 Differential Pressure Switch	Penn model P74FA-5 differential pressure switch	25 35 16 2.04	N/A	Note 7	10	COV	X	X CO	ov x	( X	
Virtual Points												
STHX-1-LWT-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Set Pnt.	N/A	25 35 00	N/A	Note 7	10	cov	X	X CO	ע אנ	:   X	
STHX-1-LWT-PG	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Proportional Gain	N/A	25 35 00	N/A	Note 7	10	COV	X	X CO	ov x	: X	
STHX-1-LWT-IG	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Integral Gain	N/A	25 35 00	N/A	Note 7	10	COV	X	X CO	x   vc	(   X	
STHX-1-LWT-DG	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Derivative Gain	N/A	25 35 00	N/A	Note 7	10	COV	X	X CO	ע אינ אינ	: X	
STHX-1-LWT-OFF	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Loop Off Value	N/A	25 35 00	N/A	Note 7	10	COV	X	X CO	x א vc	:   X	Note 9
STHX-1-OAT-RSTILO-SP	Shell and Tube Heat Exchanger -1 OAT Reset Lo Lmt. Set Pnt.	N/A	25 35 00	N/A	Note 7	10	COV	X	X CO	ע אינ אינ	: X	
STHX-1-OAT-RSTIHI-SP	Shell and Tube Heat Exchanger -1 OAT Reset Hi Lmt. Set Pnt.	N/A	25 35 00	N/A	Note 7	10	COV	X	X CO	x א vc	:   X	
STHX-1-LWT-RSTILO-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Reset Lo Lmt. Set	N/A	25 35 00	N/A	Note 7	10	COV	X	X CO	x vc	x x	
STHX-1-LWT-RSTIHI-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Reset Hi Lmt. Set	N/A	25 35 00	N/A	Note 7	10	COV	X	X CO	x vc	( X	
STHX-1-LWT-UNOCC-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Unoccupied Set Pn	N/A	25 35 00	N/A	Note 7	10	COV	X	X CO	x vc	C X	
STHX-1-CLS-SP	Shell and Tube Heat Exchanger -1 Close Set Pnt.	N/A	25 35 00	N/A	Note 7	10	COV	X	X CO	א vc	( X	

#### Notes

1. Samples indicates the minimum number of data samples that must be held in the local controller if it is trending the point.

2. Time indicates the required sampling time for the trending function.

Bureacratic Affairs Building 1st Floor Hot Water System

3. A check in the local column indicates that the trending only needs to be running in the local controller and the most recent value can write over the last value when the trend buffer fills up.

4. A check in the archive column indicates that the trend data must be archived to the system hard disc when trend buffer fills up so that a continuous trend record is maintained.

5. Commissioning trending requirements only need to be implemented during the start-up and warranty process, the control contractor should set the trending parameters to the operating requirements listed if they differ from the commissioning requirements

6. Point numbers are based on the Owner's point naming convention which is included in the specification. Point names will be verified during the submittal process in the control system integration and coordination meeting.

7. To be determined during the Control System Integration and Coordination Meeting

8. Furnish two wells for installation adjacent to each other by the mechanical contractor. One well is for the sensor and one is for calibration purposes. See the spec and detail.

9. The design intent is that the control loop is a PI loop with derivative added only if tuning in the field indicates that it is necessary to manage the response to a step change or reduce the settling time. Coordinate with the control system designer and Owner proir to adding derivative gain, but provide the point so it is there if needed.

### **Description Conveys Intent**

Description and Service Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. System OAT

Shell and Tube Heat Exchanger -1 Ent. Wtr. Temp.

Bureacratic Affairs Building 1st Floor Hot Water System													
Point		Senson					Featur	es					Notes
Name (Note 6)	Description and Service	Туре	Reference Spec	Accuracy	Alarms			Т	rending	3			
			Paragraph		Limit Warning	Samples	s <sup>1</sup> Con	mission	ing⁵	0	perating	5	
					Hi Lo Hi Lo		Time <sup>2</sup>	Local <sup>3</sup>	Archive	Time <sup>2</sup>	Local <sup>3</sup>	\rchive	
Analog Inputs													
STHX-1-LWT	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp.	1,000 $arOmega$ Pt RTD with close coupled transmitter and thermometer well	25 35 00	0.75% of span for sensor + transmitter	Note 7	60	1 min.	х	Х	1 min.	х	X	Note 8
SYSTM-OAT	System OAT	Single point 1,000 $arOmega$ Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitter	None	12	5 min.	×	Х	5 min.	X	X	
STHX-1-EWT	Shell and Tube Heat Exchanger -1 Ent. Wtr. Temp.	1,000 $arOmega$ Pt RTD with close coupled transmitter and thermometer well	25 35 00	0.75% of span for sensor + transmitter	Note 7	60	1 min.	×	х	1 min.	X	X	Note 8
Analog Outputs (All analog outputs to in	aclude local override canability and status indication at the controller)												
STHX-1-STMVLV-CMD	Shell and Tube Heat Exchanger -1 Steam Valve Command	4-20 ma actuator	25 35 13	N/A	N/A N/A N/A N/A	60	1 min.	х	Х	1 min.	х	X	
Digital Inputs													
HWPMP-1-DPSW	Hot Water Pump -1 Differential Pressure Switch	Penn model P74FA-5 differential pressure switch	25 35 16 2.04	N/A	Note 7	10	COV	х	Х	COV	х	X	
HWPMP-2-DPSW	Hot Water Pump -2 Differential Pressure Switch	Penn model P74FA-5 differential pressure switch	25 35 16 2.04	N/A	Note 7	10	COV	Х	Х	cov	x	x	
Virtual Points													
STHX-1-LWT-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Set Pnt.	N/A	25 35 00	N/A	Note 7	10	COV	Х	Х	COV	x	X	
STHX-1-LWT-PG	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Proportional Gain	N/A	25 35 00	N/A	Note 7	10	COV	х	Х	COV	X	x	
STHX-1-LWT-IG	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Integral Gain	N/A	25 35 00	N/A	Note 7	10	COV	х	х	COV	x	X	
STHX-1-LWT-DG	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Derivative Gain	N/A	25 35 00	N/A	Note 7	10	COV	х	Х	COV	X	x	
STHX-1-LWT-OFF	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Loop Off Value	N/A	25 35 00	N/A	Note 7	10	COV	Х	х	cov	X	X	Note 9
STHX-1-OAT-RSTILO-SP	Shell and Tube Heat Exchanger -1 OAT Reset Lo Lmt. Set Pnt.	N/A	25 35 00	N/A	Note 7	10	COV	х	Х	COV	X	x	
STHX-1-OAT-RSTIHI-SP	Shell and Tube Heat Exchanger -1 OAT Reset Hi Lmt. Set Pnt.	N/A	25 35 00	N/A	Note 7	10	COV	Х	х	cov	X	X	
STHX-1-LWT-RSTILO-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Reset Lo Lmt. Set	N/A	25 35 00	N/A	Note 7	10	COV	х	Х	cov	X	X	
STHX-1-LWT-RSTIHI-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Reset Hi Lmt. Set	N/A	25 35 00	N/A	Note 7	10	COV	х	х	COV	x	х	
STHX-1-LWT-UNOCC-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Unoccupied Set Pn	N/A	25 35 00	N/A	Note 7	10	COV	Х	Х	cov	X	X	
STHX-1-CLS-SP	Shell and Tube Heat Exchanger -1 Close Set Pnt.	N/A	25 35 00	N/A	Note 7	10	cov	х	х	cov	x	х	
	1 - 1		1	1	1	1	1			1			

Notes

1. Samples indicates the minimum number of data samples that must be held in the local controller if it is trending the point.

2. Time indicates the required sampling time for the trending function.

3. A check in the local column indicates that the trending only needs to be running in the local controller and the most recent value can write over the last value when the trend buffer fills up.

4. A check in the archive column indicates that the trend data must be archived to the system hard disc when trend buffer fills up so that a continuous trend record is maintained.

5. Commissioning trending parameters to the operating requirements listed if they differ from the commissioning requirements process, the control contractor should set the trending parameters to the operating requirements listed if they differ from the commissioning requirements

6. Point numbers are based on the Owner's point naming convention which is included in the specification. Point names will be verified during the submittal process in the control system integration and coordination meeting.

7. To be determined during the Control System Integration and Coordination Meeting

8. Furnish two wells for installation adjacent to each other by the mechanical contractor. One well is for the sensor and one is for calibration purposes. See the spec and detail.

9. The design intent is that the control loop is a PI loop with derivative added only if tuning in the field indicates that it is necessary to manage the response to a step change or reduce the settling time. Coordinate with the control system designer and Owner proir to adding derviative gain, but provide the point so it is there if needed.

### Sensor Type Establishes Performance Level Required

Type

1,000  $\Omega$  Pt RTD with close coupled transmitter and thermometer well Single point 1,000  $\Omega$  Pt RTD with close coupled transmitter 1,000  $\Omega$  Pt RTD with close coupled transmitter and thermometer well

| Bureacratic Affairs Building 1st Floor Hot Water System |   |  
   |   
   
   |   
  |  |   |   
   
  |  
   |   |   |   
   |  |   |  
  |  |
|---|---
--
--
--
---
--
--|--|---
--
--
--
--|---|---
---
--|---|---
--|
| t   |   | Sensor   
   |   
   
   |   
  |  |   | Feat  
   
  | ures   
   |   |   |   
   |  | Notes   |  
  |  |
| ne (Note 6)   | Description and Service   | Туре   
   | Reference Spec  
   
   | Accuracy  
  | Alarms   |   |   
   
  |  
   | Trendin   | g   |   
   |  |   |  
  |  |
|   |   |  
   | Paragraph   
   
   |   
  | Limit Warnin   | g Sample  | s <sup>1</sup> Co   
   
  | ommissio   
   | ning <sup>5</sup>   | 0   | perating  
   | 5  |   |  
  |  |
|   |   |  
   |   
   
   |   
  | Hi Lo Hi L   | 0   | Time  
   
  | <sup>2</sup> Local <sup>3</sup>  
   | Archive   | e' Time <sup>2</sup>  | Local <sup>3</sup>  
   | Archive  |   |  
  |  |
| log Inputs  |   |  
   |   
   
   |   
  |  |   |   
   
  |  
   |   |   |   
   |  |   |  
  |  |
| STHX-1-LWT  | Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp.  | 1,000 $arOmega$ Pt RTD with close coupled transmitter and thermometer well   
   | 25 35 00  
   
   | 0.75% of span for sensor + transmitter  
  | Note 7   | 60  | 1 min   
   
  | 1. X   
   | Х   | 1 min.  | х   
   | x  | Note 8  |  
  |  |
| SYSTM-OAT   | System OAT  | Single point 1,000 $\Omega$ Pt RTD with close coupled transmitter  
   | 25 35 00  
   
   | 0.75% of span for sensor + transmitter  
  | None   | 12  | 5 mir   
   
  | 1. X   
   | X   | 5 min.  | X   
   | x  |   |  
  |  |
| STHX-1-EWT  | Shell and Tube Heat Exchanger -1 Ent. Wtr. Temp.  | 1,000 $arOmega$ Pt RTD with close coupled transmitter and thermometer well   
   | 25 35 00  
   
   | 0.75% of span for sensor + transmitter  
  | Note 7   | 60  | 1 min   
   
  | 1. X   
   | X   | 1 min.  | X   
   | x  | Note 8  |  
  |  |
| log Outputs (All analog outputs to include              | local override capability and status indication at the controller)  |  
   |   
   
   |   
  |  |   |   
   
  |  
   |   |   |   
   |  |   |  
  |  |
| STHX-1-STMVLV-CMD                                       | Shell and Tube Heat Exchanger -1 Steam Valve Command  | 4-20 ma actuator   
   | 25 35 13  
   
   | N/A   
  | N/A N/A N/A N/   | /A 60   | 1 min   
   
  | ι. Χ   
   | X   | 1 min.  | х   
   | X  |   |  
  |  |
| tal Inputs  |   |  
   |   
   
   |   
  |  |   |   
   
  |  
   |   |   |   
   |  |   |  
  |  |
| HWPMP-1-DPSW  | Hot Water Pump -1 Differential Pressure Switch  | Penn model P74FA-5 differential pressure switch  
   | 25 35 16 2.04   
   
   | N/A   
  | Note 7   | 10  | COV   
   
  | ' X  
   | X   | COV   | X   
   | x  |   |  
  |  |
| HWPMP-2-DPSW  | Hot Water Pump -2 Differential Pressure Switch  | Penn model P74FA-5 differential pressure switch  
   | 25 35 16 2.04   
   
   | N/A   
  | Note 7   | 10  | COV   
   
  | ' X  
   | X   | COV   | х   
   | X  |   |  
  |  |
| rual Points   |   |  
   |   
   
   |   
  |  |   |   
   
  |  
   |   |   |   
   |  |   |  
  |  |
| STHX-1-LWT-SP   | Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Set Pnt.   | N/A  
   | 25 35 00  
   
   | N/A   
  | Note 7   | 10  | COV   
   
  | ' X  
   | X   | COV   | х   
   | X  |   |  
  |  |
| STHX-1-LWT-PG   | Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Proportional Gain  | N/A  
   | 25 35 00  
   
   | N/A   
  | Note 7   | 10  | COV   
   
  | ' X  
   | X   | COV   | х   
   | X  |   |  
  |  |
| STHX-1-LWT-IG   | Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Integral Gain  | N/A  
   | 25 35 00  
   
   | N/A   
  | Note 7   | 10  | COV   
   
  | ' X  
   | X   | COV   | X   
   | x  |   |  
  |  |
| STHX-1-LWT-DG   | Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Derivative Gain  | N/A  
   | 25 35 00  
   
   | N/A   
  | Note 7   | 10  | COV   
   
  | ' X  
   | X   | COV   | х   
   | X  |   |  
  |  |
| STHX-1-LWT-OFF  | Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Loop Off Value   | N/A  
   | 25 35 00  
   
   | N/A   
  | Note 7   | 10  | COV   
   
  | ' X  
   | X   | COV   | х   
   | x  | Note 9  |  
  |  |
| STHX-1-OAT-RSTILO-SP                                    | Shell and Tube Heat Exchanger -1 OAT Reset Lo Lmt. Set Pnt.   | N/A  
   | 25 35 00  
   
   | N/A   
  | Note 7   | 10  | COV   
   
  | ' X  
   | X   | COV   | X   
   | x  |   |  
  |  |
| STHX-1-OAT-RSTIHI-SP                                    | Shell and Tube Heat Exchanger -1 OAT Reset Hi Lmt. Set Pnt.   | N/A  
   | 25 35 00  
   
   | N/A   
  | Note 7   | 10  | COV   
   
  | ' X  
   | X   | COV   | х   
   | x  |   |  
  |  |
| STHX-1-LWT-RSTILO-SP                                    | Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Reset Lo Lmt. Set  | N/A  
   | 25 35 00  
   
   | N/A   
  | Note 7   | 10  | COV   
   
  | ' X  
   | X   | COV   | х   
   | x  |   |  
  |  |
| STHX-1-LWT-RSTIHI-SP                                    | Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Reset Hi Lmt. Set  | N/A  
   | 25 35 00  
   
   | N/A   
  | Note 7   | 10  | COV   
   
  | ' X  
   | X   | COV   | х   
   | x  |   |  
  |  |
| STHX-1-LWT-UNOCC-SP                                     | Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Unoccupied Set Pn  | N/A  
   | 25 35 00  
   
   | N/A   
  | Note 7   | 10  | COV   
   
  | ' X  
   | X   | COV   | Х   
   | Х  |   |  
  |  |
| STHX-1-CLS-SP   | Shell and Tube Heat Exchanger -1 Close Set Pnt.   | N/A  
   | 25 35 00  
   
   | N/A   
  | Note 7   | 10  | COV   
   
  | ' X  
   | X   | COV   | х   
   | х  |   |  
  |  |
|   | eacratic Affairs Building 1st Floor f<br>t<br>te (Note 6)<br>STHX-1-LWT<br>SYSTM-OAT<br>STHX-1-EWT<br>og Outputs (All analog outputs to include<br>STHX-1-STMVLV-CMD<br>tal Inputs<br>HWPMP-1-DPSW<br>HWPMP-2-DPSW<br>ual Points<br>STHX-1-LWT-SP<br>STHX-1-LWT-F6<br>STHX-1-LWT-F6<br>STHX-1-LWT-F6<br>STHX-1-LWT-F7<br>STHX-1-LWT-F7<br>STHX-1-CAT-RSTLO-SP<br>STHX-1-LWT-STHI-SP<br>STHX-1-LWT-RSTIHI-SP<br>STHX-1-LWT-RSTIHI-SP<br>STHX-1-LWT-RSTIHI-SP<br>STHX-1-LWT-NOCC-SP<br>STHX-1-CS-SP | teacratic Affairs Building 1st Floor Hot Water System         t         te (Note 6)         Description and Service         sTHX-1-WT         Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp.         SySTM-OAT         System OAT         STHX-1-EWT         Shell and Tube Heat Exchanger -1 Ent. Wtr. Temp.         og Outputs (All analog outputs to include local override capability and status indication at the controller)         STHX-1-STMVLV-CMD         Shell and Tube Heat Exchanger -1 Steam Valve Command         tal Inputs         HWPMP-1-DPSW         Hot Water Pump -1 Differential Pressure Switch         ual Points         STHX-1-LWT-SP         Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Set Pnt.         STHX-1-LWT-PG         Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Integral Gain         STHX-1-LWT-D6       Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Derivative Gain         STHX-1-WT-OFF       Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Loop Off Value         STHX-1-WT-OFF       Shell and Tube Heat Exchanger -1 OAT Reset Lo Lmt. Set Pnt.         STHX-1-OAT-RSTILO-SP       Shell and Tube Heat Exchanger -1 OAT Reset Lo Lmt. Set Pnt.         STHX-1-WT-RSTLID-SP       Shell and Tube Heat Exchanger -1 OAT Reset Lo Lmt. Set Pnt.         STHX-1-WT-RSTILO-SP </td <td>Sensor         Sensor         t       Sensor         te (Note 6)       Description and Service       Sensor         ga nputs         STHX-1-L WT       Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp.       Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         <td c<="" td=""><td>Sensor         te (Note 6)       Sensor         Description and Service       Sensor         Type       Reference Spec         Paragraphic         Sensor         Sensor       Sensor         Sensor       Sensor         Sensor       Sensor         Sensor     &lt;</td><td>Sensor         Sensor           r         Sensor           r         Sensor           re (Note 6)         Description and Service         Type         Reference Spec<br/>Paragraph         Accuracy<br/>Paragraph           STHX-1-UWT         Shell and Tube Heat Exchanger -1 Lug. Wtr. Temp.         1,000 Ω Pt RTD with close coupled transmitter and thermometer well         25 35 00         0.75% of span for sensor + transmitter<br/>Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         25 35 00         0.75% of span for sensor + transmitter           go Uuptus (Lil andig outputs to include Locd override capability and status indication at the controller)         The Wtr. Temp.         1,000 Ω Pt RTD with close coupled transmitter and thermometer well         25 35 10         0.75% of span for sensor + transmitter           go Uuptus (Lil andig outputs to include Locd override capability and status indication at the controller)         575/-157 WUV-CMD         Shell and Tube Heat Exchanger - 1 Stem Valve Command         4-20 ma actuator         25 35 10         0.75% of span for sensor + transmitter           at Dapts         HVPMP-1-OFSW         Hot Water Pump -1 Differential Pressure Switch         Penn model P74FA-5 differential pressure switch         25 35 10         0.75% of span for sensor + transmitter           at Pauts         Beil and Tube Heat Exchanger -1 Lug. Wtr. Temp. Proprintial Gein         N/A         25 35 00         N/A           STHX-1-LWT-SP</td><td>Sensor         Sensor         Accuracy         <t< td=""><td>Obschulz Attains Building 1st Hoof Hot Water System         Sensor         Accuracy         Alimit         I         <t< td=""><td>Operation of 1st Hoof Hold Water System         Sensor         Accuracy         Accuracy</td><td>Calculate Attains Building 1st Pioor Not Water System         Second Attains Building 1st Pioor Not Water System         Second Second</td><td>Sensor         Sensor         <th colsp<="" td=""><td>Sensor         Sensor         Sensor         Sensor         Sensor         Sensor           t         Sensor         Sensor</td><td>balance Antaine Building 1st Pador Hox Water System<br/>a (Note 6)<br/>population and Service<br/>b (Note 6)</td><td>Sension and Service         Ference Spectron         Accuracy         Vertex Ve</td></th></td></t<></td></t<></td></td></td> | Sensor         Sensor         t       Sensor         te (Note 6)       Description and Service       Sensor         ga nputs         STHX-1-L WT       Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp.       Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well <td c<="" td=""><td>Sensor         te (Note 6)       Sensor         Description and Service       Sensor         Type       Reference Spec         Paragraphic         Sensor         Sensor       Sensor         Sensor       Sensor         Sensor       Sensor         Sensor     &lt;</td><td>Sensor         Sensor           r         Sensor           r         Sensor           re (Note 6)         Description and Service         Type         Reference Spec<br/>Paragraph         Accuracy<br/>Paragraph           STHX-1-UWT         Shell and Tube Heat Exchanger -1 Lug. Wtr. Temp.         1,000 Ω Pt RTD with close coupled transmitter and thermometer well         25 35 00         0.75% of span for sensor + transmitter<br/>Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         25 35 00         0.75% of span for sensor + transmitter           go Uuptus (Lil andig outputs to include Locd override capability and status indication at the controller)         The Wtr. Temp.         1,000 Ω Pt RTD with close coupled transmitter and thermometer well         25 35 10         0.75% of span for sensor + transmitter           go Uuptus (Lil andig outputs to include Locd override capability and status indication at the controller)         575/-157 WUV-CMD         Shell and Tube Heat Exchanger - 1 Stem Valve Command         4-20 ma actuator         25 35 10         0.75% of span for sensor + transmitter           at Dapts         HVPMP-1-OFSW         Hot Water Pump -1 Differential Pressure Switch         Penn model P74FA-5 differential pressure switch         25 35 10         0.75% of span for sensor + transmitter           at Pauts         Beil and Tube Heat Exchanger -1 Lug. Wtr. Temp. Proprintial Gein         N/A         25 35 00         N/A           STHX-1-LWT-SP</td><td>Sensor         Sensor         Accuracy         <t< td=""><td>Obschulz Attains Building 1st Hoof Hot Water System         Sensor         Accuracy         Alimit         I         <t< td=""><td>Operation of 1st Hoof Hold Water System         Sensor         Accuracy         Accuracy</td><td>Calculate Attains Building 1st Pioor Not Water System         Second Attains Building 1st Pioor Not Water System         Second Second</td><td>Sensor         Sensor         <th colsp<="" td=""><td>Sensor         Sensor         Sensor         Sensor         Sensor         Sensor           t         Sensor         Sensor</td><td>balance Antaine Building 1st Pador Hox Water System<br/>a (Note 6)<br/>population and Service<br/>b (Note 6)</td><td>Sension and Service         Ference Spectron         Accuracy         Vertex Ve</td></th></td></t<></td></t<></td></td> | <td>Sensor         te (Note 6)       Sensor         Description and Service       Sensor         Type       Reference Spec         Paragraphic         Sensor         Sensor       Sensor         Sensor       Sensor         Sensor       Sensor         Sensor     &lt;</td> <td>Sensor         Sensor           r         Sensor           r         Sensor           re (Note 6)         Description and Service         Type         Reference Spec<br/>Paragraph         Accuracy<br/>Paragraph           STHX-1-UWT         Shell and Tube Heat Exchanger -1 Lug. Wtr. Temp.         1,000 Ω Pt RTD with close coupled transmitter and thermometer well         25 35 00         0.75% of span for sensor + transmitter<br/>Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         25 35 00         0.75% of span for sensor + transmitter           go Uuptus (Lil andig outputs to include Locd override capability and status indication at the controller)         The Wtr. Temp.         1,000 Ω Pt RTD with close coupled transmitter and thermometer well         25 35 10         0.75% of span for sensor + transmitter           go Uuptus (Lil andig outputs to include Locd override capability and status indication at the controller)         575/-157 WUV-CMD         Shell and Tube Heat Exchanger - 1 Stem Valve Command         4-20 ma actuator         25 35 10         0.75% of span for sensor + transmitter           at Dapts         HVPMP-1-OFSW         Hot Water Pump -1 Differential Pressure Switch         Penn model P74FA-5 differential pressure switch         25 35 10         0.75% of span for sensor + transmitter           at Pauts         Beil and Tube Heat Exchanger -1 Lug. Wtr. Temp. Proprintial Gein         N/A         25 35 00         N/A           STHX-1-LWT-SP</td> <td>Sensor         Sensor         Accuracy         <t< td=""><td>Obschulz Attains Building 1st Hoof Hot Water System         Sensor         Accuracy         Alimit         I         <t< td=""><td>Operation of 1st Hoof Hold Water System         Sensor         Accuracy         Accuracy</td><td>Calculate Attains Building 1st Pioor Not Water System         Second Attains Building 1st Pioor Not Water System         Second Second</td><td>Sensor         Sensor         <th colsp<="" td=""><td>Sensor         Sensor         Sensor         Sensor         Sensor         Sensor           t         Sensor         Sensor</td><td>balance Antaine Building 1st Pador Hox Water System<br/>a (Note 6)<br/>population and Service<br/>b (Note 6)</td><td>Sension and Service         Ference Spectron         Accuracy         Vertex Ve</td></th></td></t<></td></t<></td> | Sensor         te (Note 6)       Sensor         Description and Service       Sensor         Type       Reference Spec         Paragraphic         Sensor         Sensor       Sensor         Sensor       Sensor         Sensor       Sensor         Sensor     < | Sensor         Sensor           r         Sensor           r         Sensor           re (Note 6)         Description and Service         Type         Reference Spec<br>Paragraph         Accuracy<br>Paragraph           STHX-1-UWT         Shell and Tube Heat Exchanger -1 Lug. Wtr. Temp.         1,000 Ω Pt RTD with close coupled transmitter and thermometer well         25 35 00         0.75% of span for sensor + transmitter<br>Single point 1.000 Ω Pt RTD with close coupled transmitter and thermometer well         25 35 00         0.75% of span for sensor + transmitter           go Uuptus (Lil andig outputs to include Locd override capability and status indication at the controller)         The Wtr. Temp.         1,000 Ω Pt RTD with close coupled transmitter and thermometer well         25 35 10         0.75% of span for sensor + transmitter           go Uuptus (Lil andig outputs to include Locd override capability and status indication at the controller)         575/-157 WUV-CMD         Shell and Tube Heat Exchanger - 1 Stem Valve Command         4-20 ma actuator         25 35 10         0.75% of span for sensor + transmitter           at Dapts         HVPMP-1-OFSW         Hot Water Pump -1 Differential Pressure Switch         Penn model P74FA-5 differential pressure switch         25 35 10         0.75% of span for sensor + transmitter           at Pauts         Beil and Tube Heat Exchanger -1 Lug. Wtr. Temp. Proprintial Gein         N/A         25 35 00         N/A           STHX-1-LWT-SP | Sensor         Sensor         Accuracy         Accuracy <t< td=""><td>Obschulz Attains Building 1st Hoof Hot Water System         Sensor         Accuracy         Alimit         I         <t< td=""><td>Operation of 1st Hoof Hold Water System         Sensor         Accuracy         Accuracy</td><td>Calculate Attains Building 1st Pioor Not Water System         Second Attains Building 1st Pioor Not Water System         Second Second</td><td>Sensor         Sensor         <th colsp<="" td=""><td>Sensor         Sensor         Sensor         Sensor         Sensor         Sensor           t         Sensor         Sensor</td><td>balance Antaine Building 1st Pador Hox Water System<br/>a (Note 6)<br/>population and Service<br/>b (Note 6)</td><td>Sension and Service         Ference Spectron         Accuracy         Vertex Ve</td></th></td></t<></td></t<> | Obschulz Attains Building 1st Hoof Hot Water System         Sensor         Accuracy         Alimit         I <t< td=""><td>Operation of 1st Hoof Hold Water System         Sensor         Accuracy         Accuracy</td><td>Calculate Attains Building 1st Pioor Not Water System         Second Attains Building 1st Pioor Not Water System         Second Second</td><td>Sensor         Sensor         <th colsp<="" td=""><td>Sensor         Sensor         Sensor         Sensor         Sensor         Sensor           t         Sensor         Sensor</td><td>balance Antaine Building 1st Pador Hox Water System<br/>a (Note 6)<br/>population and Service<br/>b (Note 6)</td><td>Sension and Service         Ference Spectron         Accuracy         Vertex Ve</td></th></td></t<> | Operation of 1st Hoof Hold Water System         Sensor         Accuracy         Accuracy | Calculate Attains Building 1st Pioor Not Water System         Second Attains Building 1st Pioor Not Water System         Second | Sensor         Sensor <th colsp<="" td=""><td>Sensor         Sensor         Sensor         Sensor         Sensor         Sensor           t         Sensor         Sensor</td><td>balance Antaine Building 1st Pador Hox Water System<br/>a (Note 6)<br/>population and Service<br/>b (Note 6)</td><td>Sension and Service         Ference Spectron         Accuracy         Vertex Ve</td></th> | <td>Sensor         Sensor         Sensor         Sensor         Sensor         Sensor           t         Sensor         Sensor</td> <td>balance Antaine Building 1st Pador Hox Water System<br/>a (Note 6)<br/>population and Service<br/>b (Note 6)</td> <td>Sension and Service         Ference Spectron         Accuracy         Vertex Ve</td> | Sensor         Sensor         Sensor         Sensor         Sensor         Sensor           t         Sensor         Sensor | balance Antaine Building 1st Pador Hox Water System<br>a (Note 6)<br>population and Service<br>b (Note 6) | Sension and Service         Ference Spectron         Accuracy         Vertex Ve |

#### Notes

1. Samples indicates the minimum number of data samples that must be held in the local controller if it is trending the point.

2. Time indicates the required sampling time for the trending function.

3. A check in the local column indicates that the trending only needs to be running in the local controller and the most recent value can write over the last value when the trend buffer fills up.

4. A check in the archive column indicates that the trend data must be archived to the system hard disc when trend buffer fills up so that a continuous trend record is maintained.

5. Commissioning trending requirements only need to be implemented during the start-up and warranty year. After the start-up and warranty process, the control contractor should set the trending parameters to the operating requirements listed if they differ from the commissioning requirements

6. Point numbers are based on the Owner's point naming convention which is included in the specification. Point names will be verified during the submittal process in the control system integration and coordination meeting.

7. To be determined during the Control System Integration and Coordination Meeting

8. Furnish two wells for installation adjacent to each other by the mechanical contractor. One well is for the sensor and one is for calibration purposes. See the spec and detail.

9. The design intent is that the control loop is a PI loop with derivative added only if tuning in the field indicates that it is necessary to manage the response to a step change or reduce the settling time. Coordinate with the control system designer and Owner proir to adding derivative gain, but provide the point so it is there if needed.

Sensor

### Specification Reference and Accuracy Reinforce Performance Requirements

Reference Spec Paragraph	Accuracy
25 35 00	0.75% of span for sensor + transmitter
25 35 00	0.75% of span for sensor + transmitter
25 35 00	0.75% of span for sensor + transmitter

Bu	reacratic Affairs Building 1st F	loor Hot Water System													
Poir	nt		Sensor	-					Featu	ires					Notes
Na	me (Note 6)	Description and Service	Туре	Reference Spec	Accuracy	Ale	arms			٦	Frending				
				Paragraph		Limit	Warning	3 Sample	s <sup>1</sup> Co	mmission	ing⁵	0	perating	9 <sup>5</sup>	
						-li Lo	Hi L	D	Time	Local <sup>3</sup>	Archive	Time <sup>2</sup>	Local <sup>3</sup>	Archive	
And	alog Inputs														
	STHX-1-LWT	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp.	1,000 $arOmega$ Pt RTD with close coupled transmitter and thermometer well	25 35 00	0.75% of span for sensor + transmitter	No	te 7	60	1 min	×	X	1 min.	X	x	Note 8
	SYSTM-OAT	System OAT	Single point 1,000 $arOmega$ Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitter	N	one	12	5 min	×	X	5 min.	X	x	
	STHX-1-EWT	Shell and Tube Heat Exchanger -1 Ent. Wtr. Temp.	1,000 $\Omega$ Pt RTD with close coupled transmitter and thermometer well	25 35 00	0.75% of span for sensor + transmitter	No	te 7	60	1 min	×	×	1 min.	×	x	Note 8
And	alog Outputs (All analog outputs to in	nclude local override capability and status indication at the controller)		1											
	STHX-1-STMVLV-CMD	Shell and Tube Heat Exchanger -1 Steam Valve Command	4-20 ma actuator	25 35 13	N/A I	N/A N/A	N/A N/	'A 60	1 min	X	X	1 min.	X	X	
Dig	yital Inputs														
	HWPMP-1-DPSW	Hot Water Pump -1 Differential Pressure Switch	Penn model P74FA-5 differential pressure switch	25 35 16 2.04	N/A	No	te 7	10	COV	X	X	cov	X	x	
	HWPMP-2-DPSW	Hot Water Pump -2 Differential Pressure Switch	Penn model P74FA-5 differential pressure switch	25 35 16 2.04	N/A	No	te 7	10	COV	X	X	COV	X	x	
Vir	tual Points														
	STHX-1-LWT-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Set Pnt.	N/A	25 35 00	N/A	No	te 7	10	COV	X	X	cov	X	x	
	STHX-1-LWT-PG	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Proportional Gain	N/A	25 35 00	N/A	No	te 7	10	COV	X	X	COV	X	x	
	STHX-1-LWT-IG	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Integral Gain	N/A	25 35 00	N/A	No	te 7	10	COV	X	X	cov	X	x	
	STHX-1-LWT-DG	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Derivative Gain	N/A	25 35 00	N/A	No	te 7	10	COV	X	X	COV	X	x	
	STHX-1-LWT-OFF	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Loop Off Value	N/A	25 35 00	N/A	No	te 7	10	cov	X	X	COV	x	x	Note 9
	STHX-1-OAT-RSTILO-SP	Shell and Tube Heat Exchanger -1 OAT Reset Lo Lmt. Set Pnt.	N/A	25 35 00	N/A	No	te 7	10	COV	X	X	COV	X	x	
	STHX-1-OAT-RSTIHI-SP	Shell and Tube Heat Exchanger -1 OAT Reset Hi Lmt. Set Pnt.	N/A	25 35 00	N/A	No	te 7	10	cov	X	X	COV	x	x	
	STHX-1-LWT-RSTILO-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Reset Lo Lmt. Set	N/A	25 35 00	N/A	No	te 7	10	COV	X	X	COV	X	x	
	STHX-1-LWT-RSTIHI-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Reset Hi Lmt. Set	N/A	25 35 00	N/A	No	te 7	10	COV	×	Х	COV	х	x	
	STHX-1-LWT-UNOCC-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Unoccupied Set Pn	N/A	25 35 00	N/A	No	te 7	10	COV	X	Х	COV	Х	x	
	STHX-1-CLS-SP	Shell and Tube Heat Exchanger -1 Close Set Pnt.	N/A	25 35 00	N/A	No	te 7	10	COV	×	Х	COV	х	x	

Notes

1. Samples indicates the minimum number of data samples that must be held in the local controller if it is trending the point.

2. Time indicates the required sampling time for the trending function.

3. A check in the local column indicates that the trending only needs to be running in the local controller and the most recent value can write over the last value when the trend buffer fills up.

4. A check in the archive column indicates that the trend data must be archived to the system hard disc when trend buffer fills up so that a continuous trend record is maintained.

5. Commissioning trending requirements only need to be implemented during the start-up and warranty process, the control contractor should set the trending parameters to the operating requirements listed if they differ from the commissioning requirements

6. Point numbers are based on the Owner's point naming convention which is included in the specification. Point names will be verified during the submittal process in the control system integration and coordination meeting.

7. To be determined during the Control System Integration and Coordination Meeting

8. Furnish two wells for installation adjacent to each other by the mechanical contractor. One well is for the sensor and one is for calibration purposes. See the spec and detail.

9. The design intent is that the control loop is a PI loop with derivative added only if tuning in the field indicates that it is necessary to manage the response to a step change or reduce the settling time. Coordinate with the control system designer and Owner proir to adding derivative gain, but provide the point so it is there if needed.

# Alarm Requirements Tailor the System to the Operator's Needs and Your Design Concerns



Du	reactatic Analis Building Ist 1001 not	Water Oystein													
Poi	nt		Sensor						Featur	res					Notes
Na	me (Note 6)	Description and Service	Туре	Reference Spec	Accuracy	A	arms			Т	rending				
				Paragraph		Limit	Warning	amples	<sup>1</sup> Con	nmissioni	ng⁵	Op	perating <sup>5</sup>		
						Hi Lo	Hi Lo		Time <sup>2</sup>	Local <sup>3</sup>	rchive	Time <sup>2</sup>	Local <sup>3</sup> A	•chive'	
And	alog Inputs														
	STHX-1-LWT	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp.	1,000 $\Omega$ Pt RTD with close coupled transmitter and thermometer well	25 35 00	0.75% of span for sensor + transmitte	· N	ote 7	60	1 min.	X	х	1 min.	x	X	Note 8
	SYSTM-OAT	System OAT	Single point 1,000 $arOmega$ Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitte	• •	Jone	12	5 min.	X	Х	5 min.	x	X	
	STHX-1-EWT	Shell and Tube Heat Exchanger -1 Ent. Wtr. Temp.	1,000 $arOmega$ Pt RTD with close coupled transmitter and thermometer well	25 35 00	0.75% of span for sensor + transmitte	· N	ote 7	60	1 min.	X	Х	1 min.	x	x	Note 8
And	alog Outputs (All analog outputs to include loca	al override capability and status indication at the controller)													
	STHX-1-STMVLV-CMD	Shell and Tube Heat Exchanger -1 Steam Valve Command	4-20 ma actuator	25 35 13	N/A	N/A N/A	N/A N/A	60	1 min.	X	х	1 min.	x	x	
Dig	ital Inputs														
	HWPMP-1-DPSW	Hot Water Pump -1 Differential Pressure Switch	Penn model P74FA-5 differential pressure switch	25 35 16 2.04	N/A	N	ote 7	10	cov	X	х	COV	x	x	
	HWPMP-2-DPSW	Hot Water Pump -2 Differential Pressure Switch	Penn model P74FA-5 differential pressure switch	25 35 16 2.04	N/A	N	ote 7	10	COV	X	Х	COV	X	X	
Vir	tual Points														
	STHX-1-LWT-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Set Pnt.	N/A	25 35 00	N/A	N	ote 7	10	cov	X	Х	COV	x	x	
	STHX-1-LWT-PG	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Proportional Gain	N/A	25 35 00	N/A	N	ote 7	10	COV	X	Х	COV	X	x	
	STHX-1-LWT-IG	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Integral Gain	N/A	25 35 00	N/A	N	ote 7	10	COV	×	Х	COV	x	X	
	STHX-1-LWT-DG	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Derivative Gain	N/A	25 35 00	N/A	N	ote 7	10	COV	X	Х	COV	x	x	
	STHX-1-LWT-OFF	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Loop Off Value	N/A	25 35 00	N/A	N	ote 7	10	COV	X	х	COV	x	X	Note 9
	STHX-1-OAT-RSTILO-SP	Shell and Tube Heat Exchanger -1 OAT Reset Lo Lmt. Set Pnt.	N/A	25 35 00	N/A	N	ote 7	10	COV	X	Х	COV	x	x	
	STHX-1-OAT-RSTIHI-SP	Shell and Tube Heat Exchanger -1 OAT Reset Hi Lmt. Set Pnt.	N/A	25 35 00	N/A	N	ote 7	10	cov	X	х	COV	x	x	
	STHX-1-LWT-RSTILO-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Reset Lo Lmt. Set	N/A	25 35 00	N/A	N	ote 7	10	COV	X	х	COV	x	x	
	STHX-1-LWT-RSTIHI-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Reset Hi Lmt. Set	N/A	25 35 00	N/A	N	ote 7	10	cov	×	х	COV	x	X	
	STHX-1-LWT-UNOCC-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Unoccupied Set Pn	N/A	25 35 00	N/A	N	ote 7	10	COV	X	х	COV	X	X	
	STHX-1-CLS-SP	Shell and Tube Heat Exchanger -1 Close Set Pnt.	N/A	25 35 00	N/A	N	ote 7	10	COV	X	х	COV	x	X	

Notes

1. Samples indicates the minimum number of data samples that must be held in the local controller if it is trending the point.

2. Time indicates the required sampling time for the trending function.

3. A check in the local column indicates that the trending only needs to be running in the local controller and the most recent value can write over the last value when the trend buffer fills up.

4. A check in the archive column indicates that the trend data must be archived to the system hard disc when trend buffer fills up so that a continuous trend record is maintained.

5. Commissioning trending requirements only need to be implemented during the start-up and warranty process, the control contractor should set the trending parameters to the operating requirements listed if they differ from the commissioning requirements

6. Point numbers are based on the Owner's point naming convention which is included in the specification. Point names will be verified during the submittal process in the control system integration and coordination meeting.

7. To be determined during the Control System Integration and Coordination Meeting

8. Furnish two wells for installation adjacent to each other by the mechanical contractor. One well is for the sensor and one is for calibration purposes. See the spec and detail.

9. The design intent is that the control loop is a PI loop with derivative added only if tuning in the field indicates that it is necessary to manage the response to a step change or reduce the settling time. Coordinate with the control system designer and Owner proir to adding derviative gain, but provide the point so it is there if needed.

### Trending Requirements Drive System Architecture and Memory and Support LEED

		٦	Frending	1		
Samples	<sup>1</sup> Con	mission	ing <sup>5</sup>	0	peratin	<b>g</b> <sup>5</sup>
	Time <sup>2</sup>	Local <sup>3</sup>	Archive	Time <sup>2</sup>	Local <sup>3</sup>	Archive'
60	1 min.	×	×	1 min.	Х	X
12	5 min.	X	×	5 min.	Х	X
60	1 min.	X	×	1 min.	Х	×

Bure	eacratic Affairs Building 1st Floor Ho	ot Water System												
Point	,		Sensor					E			_	_		Notes
Name	e (Note 6)	Description and Service	Туре	Reference Spec Paragraph	Accuracy	Alarms Limit Warning Hi Lo Hi Lo	Samples	<sup>1</sup> Com Time <sup>2</sup>	T mission Local <sup>3</sup>	'rending ing <sup>5</sup> Archive'	O Time <sup>2</sup>	perating Local <sup>3</sup>	1 <sup>5</sup> Archive'	
Analo	og Inputs													
:	STHX-1-LWT	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp.	1,000 $ m \Omega$ Pt RTD with close coupled transmitter and thermometer well	25 35 00	0.75% of span for sensor + transmitter	Note 7	60	1 min.	Х	Х	1 min.	Х	X	Note 8
	SYSTM-OAT	System OAT	Single point 1,000 $arOmega$ Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitter	None	12	5 min.	x	Х	5 min.	X	x	
:	STHX-1-EWT	Shell and Tube Heat Exchanger -1 Ent. Wtr. Temp.	1,000 $\Omega$ Pt RTD with close coupled transmitter and thermometer well	25 35 00	0.75% of span for sensor + transmitter	Note 7	60	1 min.	х	х	1 min.	Х	×	Note 8
Analo	og Outputs (All analog outputs to include lo	cal override capability and status indication at the controller)												
:	STHX-1-STMVLV-CMD	Shell and Tube Heat Exchanger -1 Steam Valve Command	4-20 ma actuator	25 35 13	N/A	N/A N/A N/A N/A	60	1 min.	Х	Х	1 min.	Х	X	
Digit	al Inputs													
1	HWPMP-1-DPSW	Hot Water Pump -1 Differential Pressure Switch	Penn model P74FA-5 differential pressure switch	25 35 16 2.04	N/A	Note 7	10	COV	х	Х	COV	X	x	
ł	HWPMP-2-DPSW	Hot Water Pump -2 Differential Pressure Switch	Penn model P74FA-5 differential pressure switch	25 35 16 2.04	N/A	Note 7	10	COV	Х	Х	COV	Х	X	
Virtu	ual Points													
	STHX-1-LWT-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Set Pnt.	N/A	25 35 00	N/A	Note 7	10	COV	X	Х	COV	X	x	
	STHX-1-LWT-PG	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Proportional Gain	N/A	25 35 00	N/A	Note 7	10	COV	Х	Х	COV	X	x	
	STHX-1-LWT-IG	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Integral Gain	N/A	25 35 00	N/A	Note 7	10	COV	Х	Х	COV	Х	x	
	STHX-1-LWT-DG	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Derivative Gain	N/A	25 35 00	N/A	Note 7	10	COV	X	Х	COV	X	X	
	STHX-1-LWT-OFF	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Loop Off Value	N/A	25 35 00	N/A	Note 7	10	COV	Х	Х	COV	Х	x	Note 9
	STHX-1-OAT-RSTILO-SP	Shell and Tube Heat Exchanger -1 OAT Reset Lo Lmt. Set Pnt.	N/A	25 35 00	N/A	Note 7	10	COV	X	Х	COV	X	X	
	STHX-1-OAT-RSTIHI-SP	Shell and Tube Heat Exchanger -1 OAT Reset Hi Lmt. Set Pnt.	N/A	25 35 00	N/A	Note 7	10	COV	х	Х	COV	X	x	
	STHX-1-LWT-RSTILO-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Reset Lo Lmt. Set	N/A	25 35 00	N/A	Note 7	10	COV	X	Х	COV	X	x	
	STHX-1-LWT-RSTIHI-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Reset Hi Lmt. Set	N/A	25 35 00	N/A	Note 7	10	COV	х	Х	COV	X	x	
:	STHX-1-LWT-UNOCC-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Unoccupied Set Pn	N/A	25 35 00	N/A	Note 7	10	COV	х	Х	COV	Х	x	
	STHX-1-CLS-SP	Shell and Tube Heat Exchanger -1 Close Set Pnt.	N/A	25 35 00	N/A	Note 7	10	COV	Х	Х	COV	X	x	

#### Notes

1. Samples indicates the minimum number of data samples that must be held in the local controller if it is trending the point.

2. Time indicates the required sampling time for the trending function.

3. A check in the local column indicates that the trending only needs to be running in the local controller and the most recent value can write over the last value when the trend buffer fills up.

4. A check in the archive column indicates that the trend data must be archived to the system hard disc when trend buffer fills up so that a continuous trend record is maintained.

5. Commissioning trending requirements only need to be implemented during the start-up and warranty year. After the start-up and warranty process, the control contractor should set the trending parameters to the operating requirements listed if they differ from the commissioning requirements

6. Point numbers are based on the Owner's point naming convention which is included in the specification. Point names will be verified during the submittal process in the control system integration and coordination meeting.

7. To be determined during the Control System Integration and Coordination Meeting

8. Furnish two wells for installation adjacent to each other by the mechanical contractor. One well is for the sensor and one is for calibration purposes. See the spec and detail.

9. The design intent is that the control loop is a PI loop with derivative added only if tuning in the field indicates that it is necessary to manage the response to a step change or reduce the settling time. Coordinate with the control system designer and Owner proir to adding derivative gain, but provide the point so it is there if needed.

### Point Specific Notes Provide Additional Clarification if Needed

Note 8 Note 8

Notes

Bureacratic Affairs Building 1st F	loor Hot Water System												
Point		Sensor					Featur	res					Notes
Name (Note 6)	Description and Service	Туре	Reference Spec	Accuracy	Alarms			т	rending	1			
			Paragraph		Limit Warning	Samples	s <sup>1</sup> Cor	nmission	ing <sup>5</sup>	0	perating	5	
					Hi Lo Hi Lo		Time <sup>2</sup>	Local <sup>3</sup>	Archive	Time <sup>2</sup>	Local <sup>3</sup> A	rchi <mark>e</mark> ʻ	
Analog Inputs													
STHX-1-LWT	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp.	1,000 $\Omega$ Pt RTD with close coupled transmitter and thermometer well	25 35 00	0.75% of span for sensor + transmitter	Note 7	60	1 min.	X	×	1 min.	~	×	Note 8
SYSTM-OAT	System OAT	Single point 1,000 $\Omega$ Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitter	None	12	5 min.	X	×	F min.	X	×	
STHX-1-EWT	Shell and Tube Heat Exchanger -1 Ent. Wtr. Temp.	1,000 $\Omega$ Pt RTD with close coupled transmitter and thermometer well	25 35 00	0.75% of span for sensor + transmitter	Note 7	60	1 min.	X	~	1 min.	x	×	Note 8
Analog Outputs (All analog outputs to i	nclude local override capability and status indication at the controller)												
STHX-1-STMVLV-CMD	Shell and Tube Heat Exchanger -1 Steam Valve Command	4-20 ma actuator	25 35 13	N/A	N/A N/A N/A N/A	60	min.	X	Х	1 min.	x	x	
Digital Inputs													
HWPMP-1-DPSW	Hot Water Pump -1 Differential Pressure Switch	Penn model P74FA-5 differential pressure switch	25 35 16 2.04	N/A	Note 7	10	COV	X	Х	COV	x	X	
HWPMP-2-DPSW	Hot Water Pump -2 Differential Pressure Switch	Penn model P74FA-5 differential pressure switch	25 35 16 2.04	N/A	Not CT	10	COV	X	Х	COV	x	x	
Virtual Points													
STHX-1-LWT-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Set Pnt.	N/A	25 35 00	N/A	Note 7	10	COV	X	Х	COV	X	X	
STHX-1-LWT-PG	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Proportional Gain	N/A	25 35 00	N/A	Note 7	10	COV	X	×	COV	x	x	
STHX-1-LWT-IG	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Integral Gain	N/A	25 35 00	N/	Note 7	10	COV	X	х	cov	x	x	
STHX-1-LWT-DG	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Derivative Gain	N/A	25 35 00	N/A	Note 7	10	COV	X	Х	COV	X	x	
STHX-1-LWT-OFF	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Loop Off Value	N/A	25 35 00	N/A	Note 7	10	COV	X	×	COV	x	x	Note 9
STHX-1-OAT-RSTILO-SP	Shell and Tube Heat Exchanger -1 OAT Reset Lo Lmt. Set Pnt.	N/A	25 35 00	N/A	Note 7	10	COV	X	×	COV	x	x	
STHX-1-OAT-RSTIHI-SP	Shell and Tube Heat Exchanger -1 OAT Reset Hi Lmt. Set Pnt.	N/A	25 25 00	N/A	Note 7	10	COV	X	×	COV	x	x	
STHX-1-LWT-RSTILO-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Reset Lo Lmt. Set	N/A	25 35 00	N/A	Note 7	10	COV	X	Х	COV	x	x	
STHX-1-LWT-RSTIHI-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Reset Hi Lmt. Set	N/A	25 35 00	N/A	Note 7	10	COV	X	Х	COV	х	X	
STHX-1-LWT-UNOCC-SP	Shell and Tube Heat Exchanger -1 Lvg. Wtr. Temp. Unoccupied Set Pn	N/A	25 35 00	N/A	Note 7	10	COV	X	Х	COV	x	x	
STHX-1-CLS-SP	Shell and Tube Heat Exchanger -1 Close Set Pnt	N/A	25 35 00	N/A	Note 7	10	cov	x	x	COV	x	x	

#### Notes:

1. Samples indicates the minimum number of data samples that must be held in the local controller if it is trending the point.

2. Time indicates the required sampling time for the trending function

3. A check in the local column indicates that the trending only needs to be running in the local controller and the most recent value can write over the last value when the trend buffer fills up.

4. A check in the archive column indicates that the trend data must be archived to the system hard disc when trend buffer fills up so that a continuous trend record is maintained.

5. Commissioning trending requirements only need to be implemented during the start-up and warranty year. After the start-up and warranty process, the control contractor should set the trending parameters to the operating requirements listed if they differ from the commissioning requirements

6. Point numbers are based on the Owner's point naming convention which is included in the specification. Point names will be verified during the submittal process in the control system integration and coordination meeting.

7. To be determined during the Control System Integration and Coordination Meeting

8. [Furnish two wells for installation adjacent to each other by the mechanical contractor. One well is for the sensor and one is for calibration purposes. See the spec and detail.

9. The design intent is that the control loop is a PI loop with derivative added only if tuning in the field indicates that it is necessary to manage the response to a step change or reduce the settling time. Coordinate with the control system designer and Owner proir to adding derviative gain, but provide the point so it is there if needed.

# A Point List Tool

The Control Design Guide

- Design process recommendations
- Sensor selection and application guidelines
- Point list tool



### http://www.ftguide.org/csdg/CSDG.htm

(Note this runs best in a version of Internet Explorer with compatibility mode turned on)

### A Specification Resource

### **Control Spec Builder**

- Generic spec development in Word format
- Point list tool
- System diagram tool
- Sequence of operation tool



### https://www.ctrlspecbuilder.com/

### A System Diagram Tool



#### System Diagram Symbols

System diagrams are important design and diagnostic tools, making them useful "across the boards" for the building or system's life cycle. As a project engineer, I was not allowed to go into production until I had a system diagram developed for my system, which had to include first pass equipment selections.

I soon learned that if I got that right, the project would flow really smoothly and a good designer could take my system diagram and lay it out as a real system with-in the physical constraints imposed by the building arrangement and all I would need to do was check it.

On the field side of things, I learned early on that a field verified system diagram was worth it's weight in gold; in fact my very first assignment when I came to work for McClure Engineering back on April 16, 1976 was to make a system diagram.





#### http://www.av8rdas.com/system-diagram-symbols.html/

# Logic Diagram Tools



http://www.av8rdas.com/eikon-foreducators-and-windlgc.html

### http://www.av8rdas.com/logicdiagram-tool.html

# A Logic Diagram Exercise



#### Blog Post Describing the Exercise

https://av8rdas.wordpress.com/2019/02/18/acontrol-logic-exercise-and-a-way-to-getcomfortable-with-navigating-sketchup-models/

#### **Exercise Set-up and Materials**

http://www.av8rdas.com/bureaucratic-affairsbuilding-hhw-system-logic-exercise.html

### Examples of Standards Applying These Principles <a href="http://www.av8rdas.com/control-and-logic-diagram-standards.html">http://www.av8rdas.com/control-and-logic-diagram-standards.html</a>



# **Submittal** Review



Washington 2602 S 38" St PMB 461 Tacoma, WA 98409 Phone (253) 272-0235 Fax (253) 276-0088 WA #PARTECI972J1

ceptions taken. But since they were isions are required or items which were simply have no problem if Siemens wants to begin s Noted" or "Exceptions Noted" contingent, of

vise and Resubmit", items that were "Rejected", and the items that we would like to see submittals on but

comment I made to make it easier to find them. Note for a particular product so please review all pages e bookmarks to move around.



Exceptions Noted (Do Not Resubmit)

- Revise and Resubmit (See Notes)
- Not Required -Returned Without Action

Corrections or comments made to the shop drawings during this review do not relieve contractor from compliance with requirements of the drawings and specifications. This check is only for review of general conformance with the design concept of the project and general compliance with the information given in the contract documents. The contractor is responsible for: confirming and correlating all quantities and dimensions; selecting fabrication process and techniques of construction; coordinating its work with that of all other trades; and performing its work in a safe and satisfactory



Submittal Sheet Document No. 154-072 April 18, 2011

OpenAir<sup>™</sup> GQD Series, Spring Return, 20 lb-in (2 Nm), Rotary **Electronic Damper Actuators** 



#### Technical Data

Torque Runtime for 90° 20 lb-in (2 Nm) 30 seconds Spring Return 15 seconds typical Nominal angle of rotation 90° typical Power consumption: Running 24 Vac ±20%/ 24 Vdc ±15% GQD12x 6 5 VA (4 5M) GQD13x 4 VA (2.5W) GOD15x 4.5 VA (3W) 120 Vac ±15% GQD22x Damper shaft size Damper shaft size, minimum Agency listings 120 Vac Ambient temperature Operating Storage/transport Ambient humidity (non-condensing) Pre-cabled connection Enclosure Housing materia Plenum rated rugged plastic 4-23/32" × 2-22/32" × 2-15/32" Dimensions: (120 mm × 69 mm × 63 mm) GQD221.1U (only) 5-1/2" × 2-22/32" × 2-15/32"

GQDxx6 w/conduit adapter

Weight

10 VA 7 VA 3/8-inch to 1/2-inch diameter (8 mm to 13 mm) 1/4-inch to 7/16-inch square (6 mm to 11 mm) 3/4-inch (20 mm) minimum length UL listed to UL873 cUL listed: CE certified EMC and Low Voltage Directives -25°F to 130°F (-32°C to 55°C) -40°F to 158°F (-40°C to 70°C) 95% rh (non-condensing) 18 AWG (0.75mm2), 3 ft (0.9m) long NEMA 1

(138.5 mm × 69 mm × 63 mm)

6-3/16" × 2-22/32" × 2-15/32"

(156.7 mm ×69 mm ×63 mm

1.06 lbs (0.48 kg)

4 VA (2.5W)

3 VA (1.5W)

3.5 VA (2W)



requiring fail-safe operation.

- Bi-directional, fail-safe spring return
- Pre-cabled

Description

- Plenum rated models available
- Optional built-in auxiliary switches with fixed switch points at 5° and 85° rotation

The OpenAir GQD Series direct-coupled, spring

return rotary electronic damper actuators are 24

Vac/dc rated and available in 2-position, floating, and

modulating (2 to 10 Vdc) control. The small footprint and torque make this actuator ideal for small HVAC dampers, economizers, or residential zone dampers

- Fast run time
- Signal inversion capability on modulating type (2 to 10 Vdc or 10 to 2 Vdc)
- Small footprint for installation flexibility
- UL and cUL listed; CE certified
- These devices were approved for installation in plenum areas by Underwriters Laboratories, Inc. per UL 1995.
- Low voltage models are 24 Vac/dc compatible
- 120 Vac, 1/2" NPT conduit, model available

 Fixed Dual End Switches 24 Vdc. 24 Vac to 250 Vac 6A resistive 2FLA/12 LRA **Revise and Resubmit** SPST Fixed 5° and 85°

Provide a damper schedule per the requirements of SECTION 25 55 00 INTEGRATED AUTOMATION CONTROL OF HVAC Paragraph 1.11.E.10.

2. For each damper where the actuator is applied, verify the actuator torgue meets damper requirements for operating over the entire stroke and for the force applied at each end of the stroke to meet leakage requirements, including the impact of any linkage system on the force available to the damper drive shaft.

- 3 Verify specified 60,000 full cycle life minimum. The product is rejected if it does not meet this requirement.
- Technically, all of the actuators are specified with manual over-ride capability. But we may be able to waive that for some. Please clarify in the damper schedule where that feature will be provided and where not so we can run it by Fac Ops.

54

### Submittal Review

### Hardware Submittal

- Can be assembled fairly quickly
- Gets long lead items on order
- Supports the installation and software submittal

Functional Devices	a) (RE) (RE)	f: 765.883.7505 • www.functio	naldevices.com • sa	les@functionaldevices.com
RIB24P Enclosed Relay 20 Amp	DPDT with 24 Vac/dc Coil		20 Amp Power Co	ntrol Relay
WiteVie 24 Variot	Bit NC Centern HO Gray KC Centern KC Centern KC Centern KC KC			
# Relays & Contact Type: Expected Relay Life Operating Temperature: Humidity Range: Operate Time: Relay Status Dimensions: Wires: Approvals: Housing Rating: Gold Flash Override Switch:	One (1) DPDT Continuous Duty Coll 10 million cycles minimum mechanical -30 to 140°F 5 to 99% (noncondensing) 18m5 LED On = Activated 2.30° x3.20° x1.80° with 50° NPT Nipple 16°, 6007 Rated UL Listed, UL916, UL864, C-UL California State Fire Marshal, GE, RoHS UL Accepted for Use in Plenum, NEMA 1 Yes No	Contact Ratings 20 Amp Resistive @ 300 Vac 20 Amp Resistive @ 28 VdC 20 Amp Ballast @ 277-480 Vac 15 Amp Resistive @ 500 Vac 770 VA Pilot Duty @ 120 Vac 1139 VA Pilot Duty @ 277 Vac 1640 VA Pilot Duty @ 277 Vac Heavp Milot Duty @ 480 Vac 3 HP @ 480-600 Vac 2 HP @ 240-277 Vac	Coll Current 110 mA ⊕ 20 Vac 138 mA ⊕ 24 Vac 55 mA ⊕ 20 Vdc 55 mA ⊕ 24 Vdc 77 mA ⊕ 30 Vdc	Coll Voltage Input: 24 Vac/dc; 50-60 Hz Drop Out = 3 Yac / 3.8 Ydc Pull In = 20 Vac / 20 Vdc

#### **Exceptions** Noted

1. If any of these relays will be used to switch motor loads or other inductive loads please coordinate with the equipment vendor to make sure the contacts on the relay are rated for the motor load.

2. Clarify any specific requirements for a given piece of equipment via the part number/model number provided on the materials list in your installation drawings.

3. I believe these are the devices you intend to use for the control of the exhaust fans. Please reference the detail on TC5.11 for additional interface requirements. Note that this device needs to fit in the enclosure specified and if a different version of this product would be better in light of that we are fine with you making that change and simply submitting for record. We plan to provide a clarifying detail showing the typical exhaust fan wiring ladder diagram, including the across the line motorized back draft damper wiring once the submittals on the exhaust fans area approved.

## Submittal Review

Installation and Software Submittal

- Long lead time
- Supported by the hardware submittal
- Changes identified during review and approval will likely be low-cost or nocost ...

... <u>but once approved, that will</u> <u>change</u>



# Submittal Review

Installation and Software Submittal

- Consider a controls system installation and coordination meeting
- See The Controls Integration Meeting by Karl Stum and Norm Nelson
- <u>https://av8rdas.wordpress.com/2</u> 008/10/05/the-controlsintegration-and-coordinationmeeting/



# Construction Observation

58

## Sometimes Things Are Just Not Right



## Sometimes Things Are Just Not Right



### Developing a System Diagram

• A good way to learn the system prior to going on site





The Piping Plan

### Developing a System Diagram

• A good way to learn the system prior to going on site





The "System Diagram" from the Drawing Set

### Developing a System Diagram

- A good way to learn the system prior to going on site
- Focusing on one system can be helpful
- "Untangling" can be helpful



My "System Diagram" for the Condenser Water System


















The condenser water system has a huge range of flow variation but no way to isolate a tower cell and maintain uniform flow distribution over the cells (in addition to having no weirs, dams

Roof Level

Level 21











### Developing a System Diagram

- A good way to learn the system prior to going on site
- Focusing on one system can be helpful
- "Untangling" can be helpful
- A good way to spot problems
- Once field verified, it's a valuable commissioning resource



My "System Diagram" for the Condenser Water System

A Resource for Learning to Do System Diagrams https://av8rdas.wordpress.com/category/systemdiagrams/

## Heading Out to Test



### Is the System Ready?

- The control system is the first step in commissioning the <u>controlled</u>system
- Is it the control system remotely accessible?
- Is control vendor ready?
  - Point to point checks complete
  - Software verified



Calibration and Point to Point Checks























# What You See is What You Get;

Maybe ...

- ... or maybe not
  - There are many elements between the sensor and the observer and the observer and the actuator
  - All of them can impact accuracy, precision, and performance



### What You Sense is What You Get;

AC-3, January 6, 2006





#### What You Sense is What You Get; Maybe ...

AC-3, January 6, 2006



#### What You Sense is What You Get; Or Maybe Not!

AC-3, January 6, 2006



#### The Nyquist Theorem a.k.a the Sampling Theorem How Fast is Fast Enough

 $f_s \ge 2 \times f_c$ 

Where:

 $f_s$  = The sampling frequency  $f_c$  = The highest frequency contained in the signal

In words:

The sampling frequency should be at least twice the highest frequency contained in the signal.













More on aliasing and sensor accuracy in the field can be found at:

https://av8rdas.wordpress.com/2016/03/16/aliasing-and-other-factors-affecting-the-accuracy-of-field-data/

# Functional Testing





Forced Response Testing

I force a change and watch how the system responds

Forced Response Testing

I force a change and watch how the system responds

**Natural Response Testing** 

I observe how a system responds to the normal course of events

Tons vs. OAT Per Chiller



Forced Response Testing

I force a change and watch how the system responds

**Natural Response Testing** 

I observe how a system responds to the normal course of events

Tons vs. OAT Per Chiller



Forced Response Testing

I force a change and watch how the system responds

**Natural Response Testing** 

I observe how a system responds to the normal course of events

Tons vs. OAT Per Chiller


# Forced vs. Natural Response Testing

Forced Response Testing *Loop tuning is a forced response test ...* 



**Natural Response Testing** 

I observe how a system responds to the normal course of events



# Forced vs. Natural Response Testing

Forced Response Testing

Loop tuning is a forced response test ...



### ... with some important constraints





















# Getting Rid of Lags;

Sometimes It's Easier than Others

### Easier

- Add positioning relays to valve and damper actuators
- 2. Install faster actuators (particularly applicable to electric actuators)
- 3. Reduce the thermal lag associated with wells by not using them
- 4. Use tighter linkages to minimize hysteresis
- 5. Use ramps instead of acceleration and deceleration times in VFDs

### Harder

- 1. Reducing transportation times
- 2. Reducing the thermal lags associated with the size of the machinery (zmass of coils, fans, duct, pipe, etc.)

# A Bit More About Ramps

# Acceleration and Deceleration times

- Apply all of the time, any time there is a change in the process
  - An acceleration setting of1hz/second slows things down at start up and any time there is a change between control point and set point
  - This introduces a permanent lag into the control process

### Ramps

- Only apply when the set point is outside some window relative to the control point
  - Ramps will only apply if the difference between the set point and control point is large (outside of some predefined window)
  - If the set point and control point are inside the window, then the lag associated with the ramp drops out of the picture
  - As a result, the response to a minor variation in set point is much faster than the response to a step change (start up or set point change

### **Tuning Resources**

HOME BLOG RESOURCES TRAINING CONTACT TEST

#### Proportional Plus Integral Plus Derivative Control (PID) Resources

#### Controller Tuning and Control Loop Performance

David St. Clair, the author of this primer, was a process control engineer who had an important insight, that being that process control engineers needed to stop talking to plant operators using differential equations if they wanted the operators to be able to properly implement and maintain their control system designs. So, he wrote a paper that explained PID control in layman's terms and this is the paper.

I found out about David and this paper after learning the hard way about proportional error and that I needed some sort of process that would eliminate it. It turned out that the current issue of Control Engineering at the time had an article him in it. It is included in the Control Engineering Collection of articles below. So, I ordered the book and then the associated training CD and learned a lot.

David's daughter is running the business now and you can still get both items for under \$50. If you work with control system, it will be the best \$50 you have ever spent. To order, visit StraightlineControl.com and select the Ordering Information



### Mother Nature Writes Great Functional Test

If lightning is the anger of the gods, then the gods are concerned mostly about trees

Attributed to Lao-Tzu, Ancient Chinese philosopher from the 6th Century BC



Image courtesy the Cloud Appreciation Society Image Gallery

https://cloudappreciationsociety.org/gallery



### Mother Nature Writes Great Functional Test

If time and budget are short:

- Verify the "domino's" fall correctly
- Verify trends are up and running
- Randomly spot check
  - Point to point checks
  - Response times
  - Graphics

And use the control system's trending capabilities and trend analysis to review testing by Mother Nature



A Practical Approach to Control System Cx

0

STATE OF THE OWNER WATER OF THE OWNER OWNER

### Performing Random Spot Checks Simply Enforce Your Requirements

Step 1

• Reject equipment and materials that don't meet the specification requirements

Step 2

- Complete the commissioning process
  - All processes running
  - All required trends running
  - Building in a normal cycle

#### 127

### Performing Random Spot Checks Simply Enforce Your Requirements

Step 3

• Test for what you need

Need the fan to be running with-in 15 seconds of a command?

With Step 2 Completed:

- 1. Put one person at the OWS and one person at the fan
- 2. Give them walkie-talkies
- 3. Synchronize their watches
- 4. Send a start command
- 5. Time how long it takes the fan to react

#### 128

### Performing Random Spot Checks Simply Enforce Your Requirements

Step 3

• Test for what you need

Need to know if the supply air temperature changes with-in 10 seconds of a real change? With Step 2 Completed:

- 1. Put one person at the OWS and one person at the sensor
- 2. Give them walkie-talkies
- 3. Synchronize their watches
- 4. Pull the sensor out of the duct
- 5. Time how long it takes the change to show up at the OWS

### Performing Random Spot Checks Simply Enforce Your Requirements

Step 3

• Test for what you need

Need a graphic to populate in 60 seconds or less?

With Step 2 Completed:

- 1. Call up complex graphics
- 2. Time how long it takes for them to populate
- 3. See if the data makes sense
  - Is the mixed air temperature between the OAT and the RAT?
  - Does the fan status match the current command to it?

# Ongoing Operations

PROP

FOXBO

PNEUMATI

CONTROL UN

PROPORTIONAL &

· DEC. OUTPOT

K

## Ongoing Operations

## **Repeat Preceding**

Ongoing Operations

### Repeatereding

- Apply lessons learned
- Require (and financially support) a thorough control system design process for new work and renovations
- Monitor construction and use it as an opportunity to learn about your new systems and equipment
- Perform regular calibration and verification of your control equipment
- Periodically repeat functional tests and address any issues identified
- Leverage Mother Nature's functional testing process by closely monitoring your performance and utility trends
- Become a "silver bullet"

## Have Fun!





### **Questions?** Thank you for attending!



Visit our websites

www.FacilityDynamics.com

https://av8rdas.wordpress.com/ (Blog)

http://www.av8rdas.com/ (Commissioning Resources)