

Pumps and Piping

Design, Performance and Commissioning Issues

Testing Pumps and Piping Systems



Instructor:

David Sellers

Senior Engineer

Facility Dynamics Engineering

April 4, 2017

Commissioning; a Definition

Commissioning is a systematic process of ensuring that all building systems perform interactively according to the contract documents, the design intent and the Owner's operational needs

- Begins in predesign
- Documents the design intent
- Continues through construction, acceptance, the warranty period, and through the building's life cycle
- Includes functional testing
- Includes training
- Documents performance

Commissioning is about performance and integration

Commissioning; a Definition

Commissioning is a systematic process of ensuring that all building systems perform interactively according to the contract documents, the design intent and the Owner's operational needs

- Begins in predesign
- Documents the design intent
- Continues through construction, acceptance, the warranty period, and through the building's life cycle
- Includes functional testing
- Includes training
- Documents performance

Commissioning is about performance and integration

New Construction versus EBCx Testing

New Construction

- Trying to prove design intent
- Demonstrate all elements of the system meet requirements
- Verification and quality assurance process

EBCx

- Trying to understand design intent
- Focused on certain elements of the system
- Diagnostic and troubleshooting process

Forced vs. Natural Response Testing

Forced Response Testing

*I force a change and watch
how the system responds*



Forced vs. Natural Response Testing

Forced Response Testing

Example

1. With it 50°F outside and the AHU near 100% OA, I override the outdoor air sensor and manually enter 100°F as the outdoor temperature
2. I observe that :
 - Outdoor air dampers commanded to MOA
 - Leaving air set point commanded to low end of reset range
 - Chilled water valve opens

Natural Response Testing

Example

1. I pull trend data from the system for a day when the outdoor air temperature swung from 53 – 82°F.
2. I observe
 - Chilled water temperature instability during low outdoor air temperature periods
 - Transition to and from economizer at appropriate temperatures
 - Return fan tracking fails on minimum outdoor air

Forced vs. Natural Response Testing

Forced Response Testing

I force a change and watch how the system responds

View the video on Youtube at
<http://tinyurl.com/MR-1-Launch>

For the details behind what went wrong, visit:

<http://tinyurl.com/MR1Flight>

... which is a chapter from *This New Ocean, a History of Project Mercury*

<http://tinyurl.com/ProjectMercuryHistory>


Natural Response Testing

I observe how a system responds to the normal course of events




Testing Hierarchy

For A Condenser Water System (A Utility System Serving a Chiller)



Generally speaking, successful completion of everything inside the red dotted line is required for system acceptance



COMMISSIONING

Verification Checks/Prestart Checks

- Typically non-dynamic, non-interactive items
- Making sure everything is ready to become dynamic
 - Is all the hardware in place?
 - Is the system ready to run?



Verification Checks/Prestart Checks

- Typically non-dynamic, non-interactive items
- Making sure everything is ready to become dynamic
 - Is all the hardware in place?
 - Is the system ready to run?
- Control system point to point checks are an example

AHU-7

DC-4-1

DX-9100 CONTROLLER - FIELD CHECKOUT					FILE NAME: USC	
JOB NAME:		US Court House Seattle		NCU#:	1	REF DWG:
CONTRACT NO:		1088-0103		N2 TRUNK:	1	M12
LOCATION:		Mechanical Penthouse Level		N2 ADDR:	1	
CHECKOUT INFORMATION:						
HDW POINT	SYS/OBJ NAME	Description	FIELD DEVICE TYPE	CHK	Calib. Sensor	DDC Sensor
					Offset Value	REMARKS
DO-3	SF-C	Supply Fan Command	Control Panel (NO)	YB		
DO-4	RF-C	Return Fan Command	Control Panel (NO)	YB		
DO-6	MOAD-C	Min O/A Damper-Cmd	M-8216-BGx (On-Off)	-		(1) NONE
DO-7						
DO-8						
DI-1	SF-S	Supply Fan Status	Motor Status			
DI-2	SA-HL	Supply Air High Limit	AFS-480 (NC)	YB		(2)
DI-3	RF-S	Return Fan Status	F32 (NO)	YB		Set +5.0" (1.25 KPa) CAN'T SEE UNTIL FAN RUNS
DI-4						
DI-5	LT-A	Low Temp Alarm	A70 (NO) (5 Sensors)	YB		2 sensors - manual trip
DI-6						
DI-7	RA-LP	Return Air Low Limit	AFS-400 (NC)	YB		Set -3.0" (0.75 KPa)
DI-8						
AI-1	CLG-T	C/O Discharge Temp	TE	YB	33.0	33.2
AI-2	SA-T	Supply Air Temp	TE	YB	32.4	33.5
AI-3	HTG-T	H/C Discharge Temp	TE	YB	22.5	31.8
AI-4	RA-T	Return Air Temp	TE	YB	21.6	21.9
AI-5	HWS-T	HW Supply Temp	TE	YB	75.2	74.8
AI-6	MA-T	Mixed Air Temp	TE	YB	31.8	31.9
AI-7	CWS-T	CW Supply Temp	TE	YB	20.0	17.4
AI-8						
AO-1	SF-VSD	SF Speed Control	Output (Voltage)	YB		
AO-2	RF-VSD	RF Speed Control	Output (Voltage)	YB		
AO-9	HTG-O	Heating Valve Output	VA-3100 (Vdc)	YB		
AO-10	CLG-O	Cooling Valve Output	VA-6100 (Vdc)	YB		
AO-11	EAD-O	E/A Damper Output M1x4x5	M-8216 (Vdc) (Int Source)	YB		
AO-12	MAD-O	R/A Damper Output 6x11	M-8216 (Vdc) (Int Source)	YB		
AO-13						
AO-14						
XT1A11						
XT1A12	SA-SP	S/A Static Pressure	DPT200x (mA)	YB		
XT1A13	RA-F	Return Air Flow	Voltage Input	-		
XT1A14	SA-F	Supply Air Flow	Voltage Input	YB		
XT1A15	FILT-S	Filter Diff Pressure	DPT-2015	YB		
XT1A16	FILT-S	Pre-Filter Diff. Press	DPT-2015	YB		
XT1A07						
XT1A08						
() SYSTEM COMPLETELY FUNCTIONING ON:					(DATE)	
() SOFTWARE FILES SAVED ON:					(DATE)	
() POINTS SOFTWARE MAPPED ON:					(DATE)	
NOTES: (1) DO-4 DRIVES 4 24VDC COILS AND 4 RELAYS. DIRECTLY - VOLTAGE DROPS TO 17VDC. NO ALARM. TO OPEN AND DAMPER MOVES.						
(2) VALVES NOT COMPLETE - INFORMATION WORKING						
SIGNATURES:						
DATE:						

11/26/2003

Verification Checks/Prestart Checks

- Typically non-dynamic, non-interactive items
- Making sure everything is ready to become dynamic
 - Is all the hardware in place?
 - Is the system ready to run?
- Control system point to point checks are an example
- Pump alignment checks are a good example
 - Angularity
 - Offset
 - Soft foot


Typical Pump Alignment Specifications

Nominal Speed rpm	Angularity mils	Offset mils
1,200	5.0 - 8.0	2.5 - 4.0
1,800	3.0 - 5.0	2.0 - 3.0
3,600	2.0 - 3.0	1.0 - 1.5



Verification Checks/Prestart Checks

- Typically non-dynamic, non-interactive items
- Making sure everything is ready to become dynamic
 - Is all the hardware in place?
 - Is the system ready to run?
- Control system point to point checks are an example
- Pump alignment checks are a good example
 - Angularity
 - Offset
 - Soft foot



Verifying Pump Alignment

