

## Network Diagram


Work Stations, Servers, Computers



Existing Siemens Operator Work Station  
Located in FS10



Existing Siemens Server  
Furnish and install a new 3TB  
RAID array to be dedicated to  
archival data storage for LEED M&V



Existing City of Seattle  
DOIT Data Center  
Router  
DIOIT to provide routing  
table/path

## Field Panels and Equipment

Siemens  
Modular  
PXM  
Controller

Located in Mech 005  
Serves the following equipment and  
functions:


1. Mitsubishi monitoring, B, and 1st Floor
2. DHW monitoring
3. EH-1 and 2
4. UH-1 and 3



Mitsubishi GB-50 Central Controller with:  
PC Monitoring software option  
PC Scheduling software option  
Error e-mail software option  
Online Maintenance Tool software option  
Personal We Browser software option  
BACnet Interface software option  
Locate the controller in a NEMA 1 enclosure in the Com 003.



Mitsubishi PUY-A12 Outdoor  
Unit ACC-2 with MNet Adapter



Mitsubishi PURY-P192  
Outdoor Unit ACC-1



Mitsubishi PKFY-P06 Fan  
Coil Unit FCU-7



Mitsubishi PAC-SF46EPA  
Transmission Booster  
Located with FCU-7

Operator Work Station (OWS)  
Functions and details as noted

Rack Mounted Server  
Functions and details as noted

Control System Field Panels  
Function and details as noted

Controlled Equipment  
Function and details as noted

## Wiring and Field Devices

Wire and Cable

Contractor to verify conductor and conduit size for each application per the requirements of National Electric Code and other applicable standards and vendor requirements

Service	##
4#14, 1/2"C, 2S	

Line voltage conduit and wire providing interlock and line voltage control functions

Service = Unit or function served by the run

## = Conduit identifier

4#14, 1/2"C = Number of conductors followed by their AWG size followed by the conduit size followed by the number of spares included

Home run to the power source; 20 amp capacity with an independent ground conductor. Panel space and circuit breaker to be provided by Division 26, conduit and wire from the control panel location to the power source provided by the Mechanical Instrumentation contractor.

NEC Article 725 Low voltage Input/Output Cable or Networking Cable. Segregate Class 1 from Class 2 circuits. Provide conduit where runs are exposed and at all locations above 8'0" above finished floor.

## = Conduit identifier

4#14, 1/2"C = Number of conductors followed by their AWG size followed by the conduit size followed by the number of spares included

TSP = Twisted shielded pair

Per Vendor = Per the vendor requirements for the item served

Per SEAIT = Per City of Seattle IT Requirements

## Field Devices

Space temperature sensor with set point adjustment

Remote space temperature controller with multiple functions including On/Off, operating mode, set point adjustment, fan speed adjustment, and air flow direction (where available). Remote = wired connection, Network = wired network connected, Wireless = wireless network connection.

Damper with actuator; see point list and narrative for details

Air differential pressure switch or transmitter; see point list and narrative for details

Duct humidity transmitter

Duct temperature transmitter; rigid averaging sensor

Freezestat; Hardwired safety interlock

Spring wound interval timer switch

Relay interlocking hardwired safeties with a motor starter or VFD and providing a monitoring input to the DDC system

Relay interfacing the DDC system with the control system in a piece of equipment to enable the equipment for operation under the control of its own control and safety interlock system

Motor starter or Variable Speed Drive with indicated control functions and interfaces

Supply fan start/stop  
Supply fan proof of operation  
Supply fan speed command  
Supply fan speed feedback  
Network card

Analog position feedback signal from actuator

Momentary Single Pole Double Throw Center Off Switch

Maintained Double Pole Single Throw Switch

Pilot Light

End switch; Digital input changes state at the end of the actuator stroke

Duct temperature transmitter - high temperature thermocouple sensing element

Emergency stop switch; Mushroom head emergency stop switch hard wired to shut down the indicated equipment

Specialty switch provided by the referenced equipment factory; Hardwired; Function as indicated

Current transformer; analog sensor used for proof and approximate power consumption calculation

Freezestat; Hardwired interlock; Responds to the coldest temperature over 1 foot of the element

Flexible averaging duct temperature sensor; Provide 1 foot of sensing element for every 4 sq.ft. of duct/coil/AHU cross-section

Surface Temperature Sensor; Adhere to clean pipe per manufacturer's instructions; Insulate and vapor seal; See detail

## Field Devices (Continued)

Pipe temperature transmitter with well and a second calibration well

Retransmitted signal from a utility meter

Analog output driving a Silicon Controlled Rectifier (SCR) in an electric heater or similar final control element. Coordinate output type (1-5 vdc, 4-20 ma, etc.) with equipment vendor.

Relay interfacing the DDC system with a piece of equipment that has staged capacity control; one relay per stage, coordinate with equipment vendor for contact requirements.

Carbon Monoxide detector/transmitter

Nitrous Oxide detector/transmitter

Carbon Dioxide detector/transmitter

Combination Nitrous Oxide and Carbon Monoxide alarm and ventilation controller with outputs re-transmitting the gas levels for monitoring by the Siemens system.

Electric meter; See specs, point list and metering detail for requirements

Voltage meter; See specs, point list and metering detail for requirements

Phase angle/power factor meter; See specs, point list and metering detail for requirements

Positive displacement gas meter with pulse output See specs, point list and metering details for requirements

Compound water meter with pulse output; See specs, point list, and metering detail for requirements

Position switch; Analog input, changes value as the actuator strokes to provide position feedback

Occupancy sensor; automatically turns on immediately and off after an adjustable time limit based on motion detection

Vacancy sensor; manually turned on by occupant, automatically turns of if not motion is detected after an adjustable time limit

Modulating damper; NO = Normally Open, NC = Normally Closed, NS = No Spring Return

Two Position damper; NO = Normally Open, NC = Normally Closed, NS = No Spring Return

Outdoor air temperature and relative humidity transmitter

Analog output interface to a modulating controlled device

Dry contact monitor

Outdoor air temperature and relative humidity transmitter

External shades motor

Irradiance sensor

Wind speed sensor

Liquid or gas pressure transmitter; provide service valve and a tee with a test port and service valve on the test port.

## Miscellaneous

Sheet note reference; see the number specified in the list of sheet specific notes.

Point number reference; see the number specified in the list of sheet specific points.


MEP equipment tag number; reference the number in the list of equipment included on the sheet.

Lines cross each other at different elevations


Line broken for presentation purposes to show something that is below it more clearly



6760 Alexander Bell Drive, Suite 200  
Columbia, MD 21046  
Phone: (410) 290-0900



## KEY PLAN



APPROVED BY  
Department of Finance and Administrative Services  
CITY OF SEATTLE

DOVE ALBERG DATE  
Director  
Capital Development & Construction Management

APPROVED FOR ADVERTISING  
LIZ ALZEER  
City Purchasing and Contracting Services  
SEATTLE, WA 20

BY  
City Purchasing and Contracting Services Director

PROJECT-NO FAS 2016-054

DRAWN DAS

CHECKED BY CBM

DATE 10/04/18

REVISIONS DATE

△

△

△

△

△

△

VPI-NO 790-641

SHEET TITLE

Symbols and  
Abbreviations

SHEET NUMBER

MI.0.01



Control System Object Name Structure General Conventions

The table below is used to set up the general structure for object names. Once these conventions are set, they will be the same for each system in the project and are referenced by the next table, which will be specific to each system on the project.

[Jump to the System Specific Object Name Structure \(the working point list\)](#)

Number of segments for a complete point name	4	◀ Note 2			
Maximum number of characters	30	30	◀ Note 3, 11		
Segment functions	Location Segment	System Segment	Subsystem/Component Segment	Device Descriptor Segment	
Target character count for the segment, including the seperator character(s)	11	7	6	6	◀ Note 2, 11, 13, 14
Acceptable characters	LETTER, Number, Seperator	LETTER, Number, Seperator	LETTER, Number, Seperator	LETTER, Number, Seperator	
Segment functions	This segment is intended to designate the location of a control system object. For the SPU projects, this segment has two sub-segments, one to designate the facility and one to designate the location in the facility (roof, first floor, etc.).	This segment is intended to designate the system containing the object associated with the name. For example, a building might have a chilled water system, an air handling system, a hot water system, an electrical system, etc.	This segment specifies the subsystem or component associated with the object. For instance, a hot water system might have pumps, heat exchantgers, control valves, boilers, etc.	This segment designates the specific device associated with the object. For instance, the pump serving a hot water system might have a start/stop point, a proof of operation point, a speed command point, and a speed feedback point, etc.	
Applicable notes	4, 8, 9, 10, 12, 13,14	8, 9, 10, 12, 13,14	5, 6, 8, 9, 10, 12, 13,14	6, 7, 8, 9, 10, 12, 13,14	
Example	SPUSOC_BAR_DOAS1_CMP-1_SUCPR Translation = Seattle Public Utilities South Operations Center Building A Roof Dedicated Outdoor Air System--1 Compressor -1 Suction Pressure				
Location segment	SPUSOC_BAR_				
System Segment	DOAS1_				
Subsystem Segment	CMP-1_				
Device Descriptor Segment	SUCPR				


Notes:

- Not used.
- If you want to have a different number of segments, in the current version of the tool, you would need to edit the spreadsheet to create them. Similarly, if you wanted to be able to use more than two descriptors to build the location segment, more than two descriptors a build the subsystem/component segment, or more than four descriptors and a letter o number to build the descriptor segment, then you would need to edit the spreadsheet to create them.
- The desired maximum character count is manually entered in the white cell with the red boarder and is referenced by the various formulas in the spreadsheet that count characters in a given point name. The number in the adjacent cell reflects the total for target charac entered below. The color will change from green to orange as the total approaches the character limit you enter. It will turn to red if the target counts you have entered exceed the limit.
- This segment can include two location descriptors strung together as needed to fully describe the object with-in the constraints of the maximum character count allowed. Each descriptor needs to be followed by a seperator character.
- This segment can include two location descriptors and a letter or number strung together as needed to fully describe the object with-in the constraints of the maximum character count allowed. Each descriptor needs to be followed by a seperator character.
- The letter/number field provide some flexibility in terms of making a custom descriptor using something that is not included in the standard dropdown selections.
- This segment can include four location descriptors and a letter or number strung together as needed to fully describe the object with-in the constraints of the maximum character count allowed. Each descriptor other than the last one needs to be followed by a seperator
- Avoid using upper case "O" (the letter O) to avoid confusion with "0" (the number zero).
- Avoid using upper case "I" (the letter I) to avoid confusion with 1 (the number one).
- Use leading zeros for numbered items with similar prefixes to ensure they sort in numerical order. No leading zero is required if you only anticipate 10 or fewer objects with a similar prefix. If you antcipate fewer than 100 objects with a similar prefix use one leading zer fewer than 1,000 objects with a similar prefix, use two leading zeros. For example in a facility with 12 air handling units use AHU01, AHU02, ... AHU10, AHU11, AHU12 instead of AHU1, AHU2, ... AHU 10, AHU11, AHU12.
- Names may use less than the maximum number of allowable characters for a given segment. In addition the number of characters in a segment can exceed the target for the segment as long as the total character count is less than the maximum allowable character count.
- Use an appostrophe ahead of any numeric values so they are interpreted as text and allow the other formulas to work; i.e. enter'01 vs. 01
- The formulas that build the point names place a seperator after each descriptor. That means that for segments built from two or more descriptors, there will be two or more seperators included in the character count. Note that the final descriptor in the Device Descrip a seperator after it. This should be reflected in the target character count for that segment.
- This naming convention has been modified from the convention used in the DD and early CD documents based on the structure and abbreviations provided by Siemens from their other SPU work and is included after the seperator tab named "◀ This Job - Siemens Original differences are that Siemens included a building level descriptor in their location string. And they use different system and subsystem abbreviations for controllers on terminal equipment vs. field panels controlling other systems and equipment. The selections available f version of the tool have been edited to reflect the Siemens convention and then augmented for the systems and equipment on this project if there was not an existing Siemens abbreviation for the item. Each drop down list tab has a column labled "Not In Siemens 2013-C abbreviations have a cell with an "X" in it and yellow highlighting.



6760 Alexander Bell Drive, Suite 200  
Columbia, MD 21046  
Phone: (410) 290-0900





APPROVED BY  
Department of Finance and Administrative Services  
CITY OF SEATTLE

DOVE ALBERG DATE  
Director  
Capital Development & Construction Management

APPROVED FOR ADVERTISING  
LIZ ALZEER  
City Purchasing and Contracting Services  
SEATTLE, WA \_\_\_\_\_ 20\_\_\_\_

BY \_\_\_\_\_  
City Purchasing and Contracting Services Director

PROJECT-NO FAS 2016--054

DRAWN DAS

CHECKED BY CBM

DATE 10/04/18

REVISIONS DATE

△

△

△

△

△

VPI-NO 790-641

SHEET TITLE

Point Naming Convention


SHEET NUMBER




South Operations Center Variable Flow Refrigeration System (Location and system point name segments = SPUSOC.VRF.; See note 6)																
Point Name (Note 6)	Description and Service	Sensor				Features				Notes						
		Type	Reference Spec Paragraph	Accuracy	Alarms		Trending									
					Limit Hi Lo	Warning Hi Lo	Samples <sup>1</sup>	Commissioning <sup>5</sup>			Operating <sup>5</sup>					
Analog Inputs																
	ODU-1.CMP.SUCTMP-1	VRF Outdoor Unit -1 Compressor Suction Temperature -1	Surface mounted 1,000 Ω Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitter	Note 8	360	5 sec	X	X	1 min	X	X			Note 7
	ODU-1.CMP.DISTMP-1	VRF Outdoor Unit -1 Compressor Discharge Temperature -1	Surface mounted 1,000 Ω Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitter	Note 8	360	5 sec	X	X	1 min	X	X			Note 7
	ODU-1.CMP.SUCTMP-2	VRF Outdoor Unit -1 Compressor Suction Temperature -2	Surface mounted 1,000 Ω Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitter	Note 8	360	5 sec	X	X	1 min	X	X			Note 7
	ODU-1.CMP.DISTMP-2	VRF Outdoor Unit -1 Compressor Discharge Temperature -2	Surface mounted 1,000 Ω Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitter	Note 8	360	5 sec	X	X	1 min	X	X			Note 7
	ODU-2.CMP.SUCTMP-1	VRF Outdoor Unit -2 Compressor Suction Temperature -1	Surface mounted 1,000 Ω Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitter	Note 8	360	5 sec	X	X	1 min	X	X			Note 7
	ODU-2.CMP.DISTMP-1	VRF Outdoor Unit -2 Compressor Discharge Temperature -1	Surface mounted 1,000 Ω Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitter	Note 8	360	5 sec	X	X	1 min	X	X			Note 7
	ODU-2.CMP.SUCTMP-2	VRF Outdoor Unit -2 Compressor Suction Temperature -2	Surface mounted 1,000 Ω Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitter	Note 8	360	5 sec	X	X	1 min	X	X			Note 7
	ODU-2.CMP.DISTMP-2	VRF Outdoor Unit -2 Compressor Discharge Temperature -2	Surface mounted 1,000 Ω Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitter	Note 8	360	5 sec	X	X	1 min	X	X			Note 7
	IDU-X.CO2	VRF Indoor Unit -X Carbon Dioxide	CO2 sensor, 4-20 ma output	25 35 00	+/- 50 ppm	Note 8	12	5 min	X	X	15 min	X	X			Note 42
	ODU-1.CDF.DISTMP-1	VRF Outdoor Unit -1 Condenser Fan Discharge Temperature -1	Rigid averaging 1,000 Ω Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitter	Note 8	60	1 min	X	X	5 min	X	X			Note 9
	ODU-1.CDF.DISTMP-2	VRF Outdoor Unit -1 Condenser Fan Discharge Temperature -2	Rigid averaging 1,000 Ω Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitter	Note 8	60	1 min	X	X	5 min	X	X			Note 9
	ODU-1.CDF.DISTMP-3	VRF Outdoor Unit -1 Condenser Fan Discharge Temperature -3	Rigid averaging 1,000 Ω Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitter	Note 8	60	1 min	X	X	5 min	X	X			Note 9
	ODU-1.CDF.DISTMP-4	VRF Outdoor Unit -1 Condenser Fan Discharge Temperature -4	Rigid averaging 1,000 Ω Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitter	Note 8	60	1 min	X	X	5 min	X	X			Note 9
	ODU-1.CMP.CUR-1	VRF Outdoor Unit -1 Compressor Current -1	Current Transformer	25 35 00	+/-2% full scale	Note 8	60	1 min	X	X	1 min	X	X			Note 10
	ODU-1.CMP.CUR-2	VRF Outdoor Unit -1 Compressor Current -2	Current Transformer	25 35 00	+/-2% full scale	Note 8	60	1 min	X	X	1 min	X	X			Note 10
	ODU-1.CDF.CUR-1	VRF Outdoor Unit -1 Condenser Fan Current -1	Current Transformer	25 35 00	+/-2% full scale	Note 8	60	1 min	X	X	1 min	X	X			Note 10
	ODU-1.CDF.CUR-2	VRF Outdoor Unit -1 Condenser Fan Current -2	Current Transformer	25 35 00	+/-2% full scale	Note 8	60	1 min	X	X	1 min	X	X			Note 10
	ODU-1.CDF.CUR-3	VRF Outdoor Unit -1 Condenser Fan Current -3	Current Transformer	25 35 00	+/-2% full scale	Note 8	60	1 min	X	X	1 min	X	X			Note 10
	ODU-1.CDF.CUR-4	VRF Outdoor Unit -1 Condenser Fan Current -4	Current Transformer	25 35 00	+/-2% full scale	Note 8	60	1 min	X	X	1 min	X	X			Note 10
	ODU-1.CCHT.CUR	VRF Outdoor Unit -1 Crankcase Heater Current	Current Transformer	25 35 00	+/-2% full scale	Note 11	10	COV	X	X	COV	X	X			
	ODU-2.CDF.DISTMP-1	VRF Outdoor Unit -2 Condenser Fan Discharge Temperature -1	Rigid averaging 1,000 Ω Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitter	Note 8	60	1 min	X	X	5 min	X	X			Note 9
	ODU-2.CDF.DISTMP-2	VRF Outdoor Unit -2 Condenser Fan Discharge Temperature -2	Rigid averaging 1,000 Ω Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitter	Note 8	60	1 min	X	X	5 min	X	X			Note 9
	ODU-2.CDF.DISTMP-3	VRF Outdoor Unit -2 Condenser Fan Discharge Temperature -3	Rigid averaging 1,000 Ω Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitter	Note 8	60	1 min	X	X	5 min	X	X			Note 9
	ODU-2.CDF.DISTMP-4	VRF Outdoor Unit -2 Condenser Fan Discharge Temperature -4	Rigid averaging 1,000 Ω Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitter	Note 8	60	1 min	X	X	5 min	X	X			Note 9
	ODU-2.CMP.CUR-1	VRF Outdoor Unit -2 Compressor Current -1	Current Transformer	25 35 00	+/-2% full scale	Note 8	60	1 min	X	X	1 min	X	X			Note 10
	ODU-2.CMP.CUR-2	VRF Outdoor Unit -2 Compressor Current -2	Current Transformer	25 35 00	+/-2% full scale	Note 8	60	1 min	X	X	1 min	X	X			Note 10
	ODU-2.CDF.CUR-1	VRF Outdoor Unit -2 Condenser Fan Current -1	Current Transformer	25 35 00	+/-2% full scale	Note 8	60	1 min	X	X	1 min	X	X			Note 10
	ODU-2.CDF.CUR-2	VRF Outdoor Unit -2 Condenser Fan Current -2	Current Transformer	25 35 00	+/-2% full scale	Note 8	60	1 min	X	X	1 min	X	X			Note 10
	ODU-2.CDF.CUR-3	VRF Outdoor Unit -2 Condenser Fan Current -3	Current Transformer	25 35 00	+/-2% full scale	Note 8	60	1 min	X	X	1 min	X	X			Note 10
	ODU-2.CDF.CUR-4	VRF Outdoor Unit -2 Condenser Fan Current -4	Current Transformer	25 35 00	+/-2% full scale	Note 8	60	1 min	X	X	1 min	X	X			Note 10
	ODU-2.CCHT.CUR	VRF Outdoor Unit -2 Crankcase Heater Current	Current Transformer	25 35 00	+/-2% full scale	Note 11	10	COV	X	X	COV	X	X			Note 12
	IDU-X.XX.DISTMP	VRF Indoor Unit -X.XX Discharge Temperature	Rigid averaging 1,000 Ω Pt RTD with close coupled transmitter	25 35 00	0.75% of span for sensor + transmitter	Note 8	60	1 min	X	X	1 min	X	X			Note 12
	IDU-X.XX.CUR	VRF Indoor Unit -X.XX Current	Current Transformer	25 35 00	+/-2% full scale	Note 8	60	1 min	X	X	1 min	X	X			Note 10
	IDU-X.XX.FLT.DIFPR	VRF Indoor Unit -X.XX Filter Differential Pressure	0-2 in.w.c. input, 4-20 ma output transmitter, Dwyer MS-121	25 35 00	+/-1% full scale	Note 13	60	1 min	X	X	1 day	X	X			Note 45
Hard wired and Safety Interlocks (Safety interlocks are hardwired to shut down or otherwise manipulate the system. Safeties shall function no matter what position the equipment's Hand-Off-Auto, Inverter-Bypass, or other selector switches are in)																
	IDU-X.XX.HWCNT	VRF Indoor Unit -X.XX Hard Wired Controller	Mitsubishi PAR-U01MEDU remote controller	25 35 00	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Note 41
	IDU-X.XX.CND.HLVSW	VRF Indoor Unit -X.XX Condensate High Level Switch	Mitsubishi DPLS2 Drain Pan Level Sensor	25 35 00	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Note 44
Virtual Points																
	ODU-1.CMP.SUCPR-1	VRF Outdoor Unit -1 Compressor Suction Pressure -1	Calculated Point	25 35 00	N/A			Note 8								Note 14
	ODU-1.CMP.DISPR-1	VRF Outdoor Unit -1 Compressor Discharge Pressure -1	Calculated Point	25 35 00	N/A			Note 8								Note 14
	ODU-1.CMP.SUCPR-2	VRF Outdoor Unit -1 Compressor Suction Pressure -2	Calculated Point	25 35 00	N/A			Note 8								Note 14
	ODU-1.CMP.DISPR-2	VRF Outdoor Unit -1 Compressor Discharge Pressure -2	Calculated Point	25 35 00	N/A			Note 8								Note 14
	ODU-2.CMP.SUCPR-1	VRF Outdoor Unit -2 Compressor Suction Pressure -1	Calculated Point	25 35 00	N/A			Note 8								Note 14
	ODU-2.CMP.DISPR-1	VRF Outdoor Unit -2 Compressor Discharge Pressure -1	Calculated Point	25 35 00	N/A			Note 8								Note 14
	ODU-2.CMP.SUCPR-2	VRF Outdoor Unit -2 Compressor Suction Pressure -2	Calculated Point	25 35 00	N/A			Note 8								Note 14
	ODU-2.CMP.DISPR-2	VRF Outdoor Unit -2 Compressor Discharge Pressure -2	Calculated Point	25 35 00	N/A			Note 8								Note 14
	ODU-1.CMP.PRF-1	VRF Outdoor Unit -1 Compressor Proof of Operation -1	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-1.CMP.KW-1	VRF Outdoor Unit -1 Compressor kW -1	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-1.CMP.RUNTM-1	VRF Outdoor Unit -1 Compressor Run Time -1	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-1.CMP.KWH-1	VRF Outdoor Unit -1 Compressor kWh -1	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-1.CMP.PRF-2	VRF Outdoor Unit -1 Compressor Proof of Operation -2	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-1.CMP.KW-2	VRF Outdoor Unit -1 Compressor kW -2	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-1.CMP.RUNTM-2	VRF Outdoor Unit -1 Compressor Run Time -2	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-1.CMP.KWH-2	VRF Outdoor Unit -1 Compressor kWh -2	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-1.CDF.PRF-1	VRF Outdoor Unit -1 Condenser Fan Proof of Operation -1	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-1.CDF.KW-1	VRF Outdoor Unit -1 Condenser Fan kW -1	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-1.CDF.RUNTM-1	VRF Outdoor Unit -1 Condenser Fan Run Time -1	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-1.CDF.KWH-1	VRF Outdoor Unit -1 Condenser Fan kWh -1	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-1.CDF.PRF-2	VRF Outdoor Unit -1 Condenser Fan Proof of Operation -2	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-1.CDF.KW-2	VRF Outdoor Unit -1 Condenser Fan kW -2	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-1.CDF.RUNTM-2	VRF Outdoor Unit -1 Condenser Fan Run Time -2	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-1.CDF.KWH-2	VRF Outdoor Unit -1 Condenser Fan kWh -2	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-2.CMP.PRF-1	VRF Outdoor Unit -2 Compressor Proof of Operation -1	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-2.CMP.KW-1	VRF Outdoor Unit -2 Compressor kW -1	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-2.CMP.RUNTM-1	VRF Outdoor Unit -2 Compressor Run Time -1	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-2.CMP.KWH-1	VRF Outdoor Unit -2 Compressor kWh -1	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-2.CMP.PRF-2	VRF Outdoor Unit -2 Compressor Proof of Operation -2	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-2.CMP.KW-2	VRF Outdoor Unit -2 Compressor kW -2	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-2.CMP.RUNTM-2	VRF Outdoor Unit -2 Compressor Run Time -2	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-2.CMP.KWH-2	VRF Outdoor Unit -2 Compressor kWh -2	Calculated Point	25 35 00	N/A			Note 8								Note 10
	ODU-2.CDF.PRF-1	VRF Outdoor Unit -2 Condenser Fan Proof of Operation -1	Calculated Point	25 35 00	N/A			Note 8								Note 10



6760 Alexander Bell Drive, Suite 200  
Columbia, MD 21046  
Phone: (410) 290-0900



KEY PLAN



APPROVED BY  
Department of Finance and Administrative Services  
CITY OF SEATTLE

DOVE ALBERG DATE  
Mayor  
Capital Development & Construction Management

APPROVED FOR ADVERTISING  
LIZ ALZEER  
City Purchasing and Contracting Services  
SEATTLE, WA \_\_\_\_\_ 20 \_\_\_\_

By \_\_\_\_\_  
City Purchasing and Contracting Services Director

PROJECT-NO FAS 2016-054  
DRAWN DAs  
CHECKED BY CBM  
DATE 10/04/18  
REVISIONS DATE  
△  
△  
△  
△  
△  
VPI-NO 790-641  
SHEET TITLE  
VRF System Point List -  
Part 1  
SHEET NUMBER

MI.6.03-1




South Operations Center Variable Flow Refrigeration System (Location and system point name segments = SPUSOC.VRF.; See note 6)																	
Point		Sensor				Features						Notes					
Name (Note 6)	Description and Service	Type	Reference Spec Paragraph	Accuracy	Alarms				Trending								
					Limit		Warning		Samples <sup>1</sup>	Commissioning <sup>5</sup>			Operating <sup>5</sup>				
					Hi	Lo	Hi	Lo		Time <sup>2</sup>	Local <sup>3</sup>		Archive <sup>4</sup>	Time <sup>2</sup>	Local <sup>3</sup>	Archive <sup>4</sup>	
	ODU-2.CDF.KW-1	VRF Outdoor Unit -2 Condenser Fan kW -1	Calculated Point	25 35 00	N/A										Note 8	Note 10	
	ODU-2.CDF.RUNTM-1	VRF Outdoor Unit -2 Condenser Fan Run Time -1	Calculated Point	25 35 00	N/A											Note 8	Note 10
	ODU-2.CDF.KWH-1	VRF Outdoor Unit -2 Condenser Fan kWh -1	Calculated Point	25 35 00	N/A											Note 8	Note 10
	ODU-2.CDF.PRF-2	VRF Outdoor Unit -2 Condenser Fan Proof of Operation -2	Calculated Point	25 35 00	N/A											Note 8	Note 10
	ODU-2.CDF.KW-2	VRF Outdoor Unit -2 Condenser Fan kW -2	Calculated Point	25 35 00	N/A											Note 8	Note 10
	ODU-2.CDF.RUNTM-2	VRF Outdoor Unit -2 Condenser Fan Run Time -2	Calculated Point	25 35 00	N/A											Note 8	Note 10
	ODU-2.CDF.KWH-2	VRF Outdoor Unit -2 Condenser Fan kWh -2	Calculated Point	25 35 00	N/A											Note 8	Note 10
	IDU-X.XX.PRF	VRF Indoor Unit -X.XX Proof of Operation	Calculated Point	25 35 00	N/A											Note 8	Note 10
	IDU-X.XX.KW	VRF Indoor Unit -X.XX kW	Calculated Point	25 35 00	N/A											Note 8	Note 10
	IDU-X.XX.RUNTM	VRF Indoor Unit -X.XX Run Time	Calculated Point	25 35 00	N/A											Note 8	Note 10
	IDU-X.XX.KWH	VRF Indoor Unit -X.XX kWh	Calculated Point	25 35 00	N/A											Note 8	Note 10
Network Points																	
	IDU-X.XX.BN.S/SET	VRF Indoor Unit -X.XX BACnet Indoor Unit Start/Stop	VRF Network Integration Panel	25 35 13	N/A											Note 8	Note 15, 16
	IDU-X.XX.BN.S/SFBK	VRF Indoor Unit -X.XX BACnet Indoor Unit Operating State	VRF Network Integration Panel	25 35 13	N/A											Note 8	Note 15, 17
	IDU-X.XX.BN.ALARM	VRF Indoor Unit -X.XX BACnet General Alarm	VRF Network Integration Panel	25 35 13	N/A											Note 8	Note 15, 18
	IDU-X.XX.BN.ERRCD	VRF Indoor Unit -X.XX BACnet General Error	VRF Network Integration Panel	25 35 13	N/A											Note 8	Note 15, 19
	IDU-X.XX.BN.OPMDSET	VRF Indoor Unit -X.XX BACnet Operating Mode Setting	VRF Network Integration Panel	25 35 13	N/A											Note 8	Note 15, 20
	IDU-X.XX.BN.OMDSTA	VRF Indoor Unit -X.XX BACnet Operating Mode Feedback	VRF Network Integration Panel	25 35 13	N/A											Note 8	Note 15, 21
	IDU-X.XX.BN.FNSPSET	VRF Indoor Unit -X.XX BACnet Set Fan Speed	VRF Network Integration Panel	25 35 13	N/A											Note 8	Note 15, 22
	IDU-X.XX.BN.FNSPFBK	VRF Indoor Unit -X.XX BACnet Fan Speed Feedback	VRF Network Integration Panel	25 35 13	N/A											Note 8	Note 15, 23
	IDU-X.XX.BN.RMTMP	VRF Indoor Unit -X.XX BACnet Space Temperature Indication	VRF Network Integration Panel	25 35 13	N/A											Note 8	Note 15, 24
	IDU-X.XX.BN.STRMTMP	VRF Indoor Unit -X.XX BACnet Set Space Temperature Set Point	VRF Network Integration Panel	25 35 13	N/A											Note 8	Note 15, 25
	IDU-X.XX.BN.FTRS6N	VRF Indoor Unit -X.XX BACnet Change Filter Indication	VRF Network Integration Panel	25 35 13	N/A											Note 8	Nt. 15, 26, 46
	IDU-X.XX.BN.FTRRSET	VRF Indoor Unit -X.XX BACnet Change Filter Indication Reset	VRF Network Integration Panel	25 35 13	N/A											Note 8	Nt. 15, 27, 46
	IDU-X.XX.BN.PRONOF	VRF Indoor Unit -X.XX BACnet Prohibit Remote On-Off Override	VRF Network Integration Panel	25 35 13	N/A											Note 8	Note 15, 28
	IDU-X.XX.BN.PRMODE	VRF Indoor Unit -X.XX BACnet Prohibit Rmt. Operating Mode Ovrld.	VRF Network Integration Panel	25 35 13	N/A											Note 8	Note 15, 29
	IDU-X.XX.BN.PRFLTRS	VRF Indoor Unit -X.XX BACnet Prohibit Rmt. Filter Chng. Ind. Reset	VRF Network Integration Panel	25 35 13	N/A											Note 8	Nt. 15, 30, 46
	IDU-X.XX.BN.PRSTTMP	VRF Indoor Unit -X.XX BACnet Prohibit Remote Set Point Adj.	VRF Network Integration Panel	25 35 13	N/A											Note 8	Note 15, 31
	IDU-X.XX.BN.MNETST	VRF Indoor Unit -X.XX BACnet MNet Error Indication	VRF Network Integration Panel	25 35 13	N/A											Note 8	Note 15, 32
	IDU-X.XX.BN.FRCOFF	VRF Indoor Unit -X.XX BACnet Force Indoor Unit Off	VRF Network Integration Panel	25 35 13	N/A											Note 8	Note 15, 33
	IDU-X.XX.BN.AIRDSET	VRF Indoor Unit -X.XX BACnet Set Airflow Direction	VRF Network Integration Panel	25 35 13	N/A											Note 8	Note 15, 34
	IDU-X.XX.BN.AIRDFBK	VRF Indoor Unit -X.XX BACnet Airflow Direction Feedback	VRF Network Integration Panel	25 35 13	N/A											Note 8	Note 15, 35
	IDU-X.XX.BN.STCOOL	VRF Indoor Unit -X.XX BACnet Set Cooling Set Point	VRF Network Integration Panel	25 35 13	N/A											Note 8	Note 15, 36
	IDU-X.XX.BN.STHEAT	VRF Indoor Unit -X.XX BACnet Set Heating Set Point	VRF Network Integration Panel	25 35 13	N/A											Note 8	Note 15, 37
	IDU-X.XX.BN.STAUTO	VRF Indoor Unit -X.XX BACnet Set Auto Mode Set Point	VRF Network Integration Panel	25 35 13	N/A											Note 8	Note 15, 38
	IDU-X.XX.BN.STBKHLM	VRF Indoor Unit -X.XX BACnet Set Unocc. Cycle Hi Lmt Set Point	VRF Network Integration Panel	25 35 13	N/A											Note 8	Note 15, 39
	IDU-X.XX.BN.STBKLLM	VRF Indoor Unit -X.XX BACnet Set Unocc. Cycle Lo Lmt Set Point	VRF Network Integration Panel	25 35 13	N/A											Note 8	Note 15, 40
Notes:																	
1. Samples indicates the minimum number of data samples that must be held in the local controller if it is trending the point.																	
2. Time indicates the required sampling time for the trending function.																	
3. A check in the local column indicates that the trending only needs to be running in the local controller and the most recent value can write over the last value when the trend buffer fills up.																	
4. A check in the archive column indicates that the trend data must be archived to the system hard disc when trend buffer fills up so that a continuous trend record is maintained.																	
5. Commissioning trending requirements only need to be implemented during the start-up and warranty year. After the start-up and warranty process, the control contractor should set the trending parameters to the operating requirements listed if they differ from the commissioning requirements.																	
6. Point names are based on the Owner's point naming convention which is included in the specification. The location and system segments of the point name shown at the top of the point list will be included with the subsystem and descriptor segments in this column to create the complete point name in the point data base. Point names will be verified during the submittal process in the control system integration and coordination meeting.																	
7. Use temperature as a proxy for pressure. Epoxy the sensor to the appropriate pipe near the associated pressure test port (i.e. suction temperature near the suction pressure port on the VRF unit, etc.). Insulate over the sensor and for 1 inch on either side to minimize the influence of ambient temperature. Vapor seal the insulation to the pipe and sensor leads.																	
8. Coordinate alarm values if desired with the Owner and commissioning provider during the submittal process. Document final alarm settings in the mark-ups of the As Built point list.																	
9. Select sensor length to match the fan diameter. Mount the sensor across the outlet of the fan to the fan guard. This sensor is used along with outdoor temperature to determine the operating state of the ODU (heat pump, cooling, balanced, etc.) based on the temperature change across the condenser.																	
10. Monitor amps to provide a proof of operation input and create virtual meters to track run time as well as energy use using voltage and power factor constants determined during commissioning. Accumulate and display current demand level, kWh and hours for the day, and kWh and hours for the previous day, calendar month, and calendar year. Archive data to the data to the dedicated archival data storage drive in the City's Data Center. See Network Diagram.																	
11. Generate an alarm if the compressors are off and there is no current being drawn by the crankcase heater.																	
12. For ducted select the sensor so that it spans the duct and mount it in the discharge duct. For ceiling cassette units, coordinate with the Mitsubishi installing technician for length and mounting location as needed to pick up the temperature on the discharge side of the cooling coil in.																	
13. Coordinate during commissioning to trigger at the pressure drop associated with best life cycle cost operation for the filters that are installed. Document the final settings in the mark-ups of the As Built point list. This point is only provided for the ducted IDUs with filter boxes. Otherwise the standard Mitsubishi filter timer flag is used.																	
14. Use the maintenance tool pressure data to create a look-up table that calibrates the measured proxy temperature with a pressure.																	
15. See Mitsubishi manual WT07919X01 - Centralized Controller BACnet Instruction Book for additional information.																	
16. BACnet Binary Output Object used to set the VRF IDU operating state. Values are Stop or Run.																	
17. BACnet Binary Input Object used to indicate the VRF IDU operating state. Values are Stop or Run.																	
18. BACnet Binary Input Object used to indicate a general error with the VRF system. Values are Normal or Error.																	
19. BACnet Multi-state Input object used to flag a number of different issues in the VRF system. Values are 01 = Normal, 02 = Other Errors, 03 = Refrigeration System Fault, 04 = Water System Error (not applicable for this project), 05 = Air System Error, 06 = Electronic System Error, 07 = Sensor Fault, 08 = Communication Error, and 09 = System Error.																	
20. BACnet Multistate Output object used to set up the VRF IDU operating mode. Values can be 01 = Cool, 02 = Heat, 03 = Fan, 04 = Auto, 05 = Dry, and 06 = Setback.																	
21. BACnet Multistate Input object used to display the VRF IDU operating state setting. Values can be 01 = Cool, 02 = Heat, 03 = Fan, 04 = Auto, 05 = Dry, and 06 = Setback.																	
22. BACnet Multistate Output object used to set up the VRF IDU fan speed. Values can be 01 = Low, 02 = High, 03 = Mid 2, 04 = Mid 1, and 05 = Auto.																	
23. BACnet Multistate Output object used to indicate the VRF IDU fan speed setting. Values can be 01 = Low, 02 = High, 03 = Mid 2, 04 = Mid 1, and 05 = Auto.																	
24. BACnet Analog Input object used to indicate the current room temperature.																	
25. BACnet Analog Value object used to set the room temperature.																	
26. BACnet Binary Input object used to indicate if the filter needs to be changed. Values are On or Off. It is not a pressure drop measurement; rather it is a timer that sets the output on after so many hours in operation. For this project, the is not used for the ducted VRF IDUs because they have higher performance filters in them for LEED purposes and it will be more cost effective to change them based on pressure drop instead of time in service.																	
27. BACnet Binary Value object used to reset the filter change flag once the filters have been changed. See not 26.																	
28. BACnet Binary Value object used to prevent the room occupants from changing the On/Off state of the IDU once it has been set by the Siemens system. See the sequence of operation for additional information on prohibit points as well as Mitsubishi Application Note 3001, 3003, and 3007.																	
29. BACnet Binary Value object used to prevent the room occupants from changing the operating mode of the IDU once it has been set by the Siemens system. See the sequence of operation for additional information on prohibit points as well as Mitsubishi Application Note 3001, 3003, and 3007.																	
30. BACnet Binary Value object used to prevent the room occupants from resetting the filter alarm so that only someone servicing the filters can reset it. See Note 26 for additional information on the filter status points and the sequence of operation for additional information on prohibit points.																	
31. BACnet Binary Value object used to prevent the room occupants from changing the set point of the IDU once it has been set by the Siemens system. See the sequence of operation for additional information on prohibit points as well as Mitsubishi Application Note 3001, 3003, and 3007.																	



**Facility Dynamics**  
ENGINEERING

6760 Alexander Bell Drive, Suite 200  
Columbia, MD 21046  
Phone: (410) 290-0900





APPROVED BY  
Department of Finance and Administrative Services  
CITY OF SEATTLE

\_\_\_\_\_  
DOVE ALBERG      DATE \_\_\_\_\_  
Mayor

Capital Development & Construction Management

APPROVED FOR ADVERTISING  
LIZ ALZEER  
City Purchasing and Contracting Services  
SEATTLE, WA      \_\_\_\_\_ 20 \_\_\_\_

BY \_\_\_\_\_  
City Purchasing and Contracting Services Director

PROJECT-NO      FAS 2016-054

DRAWN      DAS

CHECKED BY      CBM

DATE      10/04/18

REVISIONS      DATE

△

△

△

△

△

VPI-NO      790-641

SHEET TITLE  
VRF System Point List -  
Part 2

SHEET NUMBER

MI.6.03-2




South Operations Center Variable Flow Refrigeration System (Location and system point name segments = SPUSOC.VRF.; See note 6)															
Point		Sensor				Features							Notes		
Name (Note 6)	Description and Service	Type	Reference Spec Paragraph	Accuracy	Alarms				Trending						
					Limit		Warning		Samples <sup>1</sup>	Commissioning <sup>5</sup>				Operating <sup>5</sup>	
					Hi	Lo	Hi	Lo		Time <sup>2</sup>	Local <sup>3</sup>	Archive <sup>4</sup>		Time <sup>2</sup>	Local <sup>3</sup>
32. BACnet Binary Input object used to flag a problem on the Mitsubishi proprietary control network (M-NET).															
33. BACnet Binary Value object used to collectively or individually reset or and deactivate IDUs from the Siemens system.															
34. BACnet Multistate Output object used to set the position the air directing vanes. Not all IDUs have this feature (ducted units for instance). Possible values will vary with the type of unit but will typically include "auto", and number of different fixed positions, and a swing position that causes the vanes to continuously modulate.															
35. BACnet Multistate Input object used to report the position the air directing vanes. Not all IDUs have this feature (ducted units for instance). Possible values will vary with the type of unit but will typically include "auto", and number of different fixed positions, and a swing position that causes the vanes to continuously modulate.															
36. BACnet Analog Value object used in conjunction with the prohibit points to allow the building automation system to perform over-ride local control and/or perform night set-back and set-up functions. This object sets the cooling set point for units that support dual set points; i.e. an independent cooling set point and heating set point with a deadband in-between. When the Auto mode is enabled for these units, they will automatically heat or cool depending on the space temperature relative to these two set points. Not all controllers will support this function.															
37. BACnet Analog Value object used in conjunction with the prohibit points to allow the building automation system to perform over-ride local control and/or perform night set-back and set-up functions. This object sets the heating set point for units that support dual set points; i.e. an independent cooling set point and heating set point with a deadband in-between. When the Auto mode is enabled for these units, they will automatically heat or cool depending on the space temperature relative to these two set points. Not all controllers will support this function.															
38. BACnet Analog Value object used in conjunction with the prohibit points to allow the building automation system to perform over-ride local control and/or perform night set-back and set-up functions. This object sets the set point for units that do not support dual set points; i.e. there is only one set point with no dead band between heating and cooling. When the Auto mode is enabled for these units, they will automatically heat or cool depending on the space temperature relative to this one set point. Not all controllers will support this function.															
39. BACnet Analog Value object used in conjunction with the prohibit points to allow the building automation system to perform over-ride local control and/or perform night set-back and set-up functions by setting a high temperature limit set point. Not all controllers will support this function.															
40. BACnet Analog Value object used in conjunction with the prohibit points to allow the building automation system to perform over-ride local control and/or perform night set-back and set-up functions by setting a low temperature limit set point. Not all controllers will support this function.															
41. Vendor furnished for installation by the Mechanical Control Instrumentation contractor.															
42. Provide one calibration kit specific to the make and model of sensor that is provided and turn it over to the Owner at the completion of construction to support on-giong operation and maintenance of the sensors.															
43. Required for the following rooms, 100, 101, 124, 141, 142, 143, 144, 210, 212, 230, 231, 241, and 244. For monitoring purposes and LEED compliance purposes only.															
44. Hardwire the drain pain overflow sensor to the Mitsubishi VRF IDU using the wiring harness provided and verify operation.															
45. Applies to IDU-1.2, IDU-1.3, IDU-1.4, IDU-1.5, IDU-1.6, IDU-1.14, IDU-2.1, IDU-2.2, IDU-2.3, IDU-2.7, and IDU-2.9.															
46. Not required for IDU-1.2, IDU-1.3, IDU-1.4, IDU-1.5, IDU-1.6, IDU-1.14, IDU-2.1, IDU-2.2, IDU-2.3, IDU-2.7, and IDU-2.9.															



6760 Alexander Bell Drive, Suite 200  
Columbia, MD 21046  
Phone: (410) 290-0900



KEY PLAN



APPROVED BY  
Department of Finance and Administrative Services  
CITY OF SEATTLE

DOVE ALBERG      DATE  
Director  
Capital Development & Construction Management

APPROVED FOR ADVERTISING  
LIZ ALZEER  
City Purchasing and Contracting Services  
SEATTLE, WA      20

BY  
City Purchasing and Contracting Services Director

PROJECT-NO      FAS 2016-054

DRAWN      DAS

CHECKED BY      CBM

DATE      10/04/18

REVISIONS      DATE

△

△

△

△

△

VPI-NO      790-641

SHEET TITLE  
VRF System Point List -  
Part 3

SHEET NUMBER

MI.6.03-3



## Variable Flow Refrigeration (VRF) Systems Sequence of Operation

### Overview

The VRF systems associated with this project operate using a proprietary digital control system that manages the interactions of the indoor units serving the occupied zones with the branch controllers and outdoor units serving the system.

The system is served by:

- Two Outdoor Units (ODU) that can serve as conventional condensers to reject heat to the ambient environment or near-conventional heat pumps to extract heat from the ambient environment, and
- Three Branch Controllers (BC) to manage and direct the flow of refrigerant between
- Twenty-five Indoor Units (IDUs) with contain coils that function as evaporators for a cooling cycle and condensers for a heating cycle.

Note that the ODUs are two different sizes and that each ODU contains two compressors. The ODUs are "twinned" which generally means they are piped in parallel and will operate as a unit with the Mitsubishi controllers using one as the master unit and the other as the slave unit, staging the compressors based on the operating mode and requirements of the system to optimize performance and efficiency.

This system configuration will allow:

1. Refrigerant to be sent to the outdoor units operating as conventional condensing units to reject heat if there is a net cooling requirement on the system, or
2. Refrigerant to be sent to the outdoor units operating as heat pumps to capture heat from the outdoors if there is a net heating requirement on the system, or
3. Refrigerant to be redirected from zone to zone for the purposes of heat recovery.

The system diagrams/operating diagrams used in the following section can be viewed as a narrated animation by downloading the Mitsubishi City Multi Refrigerant Flow Animation Application at [www.mylinkdrive.com](http://www.mylinkdrive.com).

### Full Cooling

This operating mode is virtually identical to a conventional direct expansion/vapor compression refrigeration process and is illustrated in Figure 1.

In this mode, refrigerant is evaporated in the coils in all zones to

cool them. The heat is then rejected in the coils at the ODU which causes the refrigerant to condense.

In this operating mode the air leaving the ODU fan will be warmer than the ambient temperature. This condition is used by the control system as an indication that the ODU is in the cooling mode.

### Full Heating

This operating mode is virtually identical to a conventional direct expansion/vapor compression process applied in a heat pump and is illustrated in Figure 2, although the coils in the condenser can see a liquid vapor mix entering them whereas heat pumps often receive only liquid refrigerant and the outdoor coil.

In this mode, refrigerant is condensed in the coils in all zones to heat them. Then, the refrigerant is evaporated in the coils at the ODU, which causes it to pick up heat from the ambient environment for use in heating the indoor zones.

In this operating mode the air leaving the ODU fan will be cooler than the ambient temperature. This condition is used by the control system as an indication that the ODU is in the heating mode.

### Heat Recovery

There are three general operating states associated with the VRF system performing heat recovery.

#### Balanced System

This operating mode is illustrated in Figure 3.

In this operating mode, energy is transferred from the zones that require cooling to the zones that require heating with no heat being rejected or picked up at the coils in the ODU. This is the lowest energy state for the system because no ODU fan operation is require and because the refrigerant moving through the system does double duty by first passing through the coils where cooling is required and picking up energy and then moving to the coils where heating is required and giving that energy back up.

In this operating mode, the compressor operates but the ODU fan does not operate. The control system uses this as an indication that the system is in a balanced state.

#### More Zones in Heating than Cooling

This operating mode is illustrated in Figure 4.

This operating mode allows the VRF system to concurrently provide heating and cooling with the energy extracted from the zones needing cooling providing energy to the zones that need heat. But because more heat is required than is being recovered from the

zones with a cooling load, the ODU coils are configured to recover heat from the ambient environment and the ODU operates as a heat pump.

As was the case for the full heating mode, the ODU coil receives a mix of liquid and gaseous refrigerant, and the air leaving the ODU fan is cooler than the ambient air. The control system uses the cooler air leaving the ODU fan in combination with a mixed operating state of the VRF InDoor Unit (IDU) zones (some in heating and some in cooling) as an indication that the system is in this operating state.

#### More Zones in Cooling than Heating

This operating mode is illustrated in Figure 5.

This operating mode is similar to the operating mode discussed in the preceding paragraph in that it allows the VRF system to concurrently provide heating and cooling with the energy extracted from the zones needing cooling providing energy to the zones that need heat. But because the heat that needs to be rejected by the zones in cooling exceeds the amount of heat required by the zones in heating, the ODU coils receive hot gas and the ODF fan operates to .

As was the case for the full heating mode, the ODU coil receives a mix of liquid and gaseous refrigerant, and the air leaving the ODU fan is cooler than the ambient air. The control system uses the cooler air leaving the ODU fan in combination with a mixed operating state of the VRF InDoor Unit (IDU) zones (some in heating and some in cooling) as an indication that the system is in this operating state.

### Proprietary Digital Control System

The various elements in the VRF system are managed by a stand-alone proprietary digital control system that is capable of providing all of the functionality necessary to operate the system, perform diagnostics, schedule equipment, and track energy consumption including providing web-based access to these features from a central location. However, since the City of Seattle is a sole source Siemens site, the Mitsubishi control system will be integrated with the Siemens control system using BACnet as well as dedicated physical points that are hardwired into the Siemens control system.

The two primary control elements of the Mitsubishi Control network are the Network Manager and the IDU Remote Controllers.

#### Network Manager

The Mitsubishi AE-200 controller functions as the network manager for the Mitsubishi control system. It shall be furnished

and programmed by the Mitsubishi installing contractor and will be mounted by the Mechanical Instrumentation contractor in an enclosure furnished by the Mechanical Instrumentation contractor.

The Mechanical Instrumentation contractor shall also furnish and install all wiring, raceways and accessories require for a complete wiring system and shall make final terminations to the Mitsubishi equipment in coordination with the Mitsubishi Installing Contractor.

Commissioning shall be performed in conjunction with the Commissioning Provider, the Mitsubishi installing contractor and the Mechanical Instrumentation contractor with support from the design and construction team as required by the contract documents.

The AE-200 provides the following functions for this project.

- Master control functions for the network
- Operation and monitoring of the VRF equipment in the facility
- BACnet functions as required to integrate with the Siemens system
- Web browser access to allow a user with proper credentials to access the system via a web browser for monitoring, operation, energy management, and maintenance functions.

(Continued on sheet MI.8.03-2)




Figure 1 - A VRF System Operating in the Full Cooling Mode




Figure 2 - A VRF System Operating in Full Heating Mode




Figure 3 - A VRF System Operating in a Balanced State






Figure 5 - A VRF System with a Net Cooling Requirement on the System



APPROVED BY  
Department of Finance and Administrative Services  
CITY OF SEATTLE

DOVE ALBERG DATE  
Specialist  
Capital Development & Construction Management

APPROVED FOR ADVERTISING  
LIZ ALZEER  
City Purchasing and Contracting Services  
SEATTLE, WA 20

BY  
City Purchasing and Contracting Services Director

PROJECT-NO FAS 2016-054

DRAWN DAS

CHECKED BY CBM

DATE 10/04/18

REVISIONS DATE

△

△

△

△

VPI-NO 790-641

SHEET TITLE

VRF System Sequence  
of Operation Part 1

SHEET NUMBER

MI.8.03-1



<b>APPROVED BY</b> <b>Department of Finance and Administrative Services</b> <b>CITY OF SEATTLE</b>											
<b>DOVE ALBERG</b> <i>Director</i>	<b>DATE</b>  Capital Development & Construction Management										
<b>APPROVED FOR ADVERTISING</b> <b>LIZ ALZEER</b> <i>City Purchasing and Contracting Services</i>											
SEATTLE, WA _____	20____										
BY _____ <i>City Purchasing and Contracting Services Director</i>											
<table style="width: 100%; border: none;"> <tr> <td style="width: 40%; border-bottom: 1px solid black;">PROJECT-NO</td> <td style="border-bottom: 1px solid black;">FAS 2016-054</td> </tr> <tr> <td style="border-bottom: 1px solid black;">DRAWN</td> <td style="border-bottom: 1px solid black;"><b>DAS</b></td> </tr> <tr> <td style="border-bottom: 1px solid black;">CHECKED BY</td> <td style="border-bottom: 1px solid black;"><b>CBM</b></td> </tr> <tr> <td style="border-bottom: 1px solid black;">DATE</td> <td style="border-bottom: 1px solid black;">10/04/18</td> </tr> <tr> <td style="border-bottom: 1px solid black;">REVISIONS</td> <td style="border-bottom: 1px solid black;">DATE</td> </tr> </table> <div style="display: flex; justify-content: space-between; margin-top: 10px;"> <div> <div style="margin-bottom: 5px;">△</div> <div style="margin-bottom: 5px;">△</div> <div style="margin-bottom: 5px;">△</div> <div style="margin-bottom: 5px;">△</div> <div style="margin-bottom: 5px;">△</div> </div> <div> <div style="margin-bottom: 5px;">/PI-NO</div> <div style="margin-bottom: 5px;">790-641</div> </div> </div>		PROJECT-NO	FAS 2016-054	DRAWN	<b>DAS</b>	CHECKED BY	<b>CBM</b>	DATE	10/04/18	REVISIONS	DATE
PROJECT-NO	FAS 2016-054										
DRAWN	<b>DAS</b>										
CHECKED BY	<b>CBM</b>										
DATE	10/04/18										
REVISIONS	DATE										
SHEET TITLE <b>VRF System Sequence</b> <b>of Operation Part 2</b>											
SHEET NUMBER											
<b>MI.8.03-2</b>											







VRF System Sequence of Operation (Continued from MI.8.03-3)

Diagnostic Points

The VRF technology employs numerous analog sensors monitoring system temperatures, pressures, currents and other physical properties as required to control and optimize the system. Most, if not all of this data is available via the VRF Maintenance Tool Software. However, few if any of the points are made available as BACnet objects for direct access by the Siemens control system.

To improve operability certain key parameters as outlined in the point lists, will be brought into the Siemens network as physical points to allow preliminary diagnostics to be performed via the Siemens OWS. Some of the diagnostics will simply present key data to the operator for their assessment and judgment. However, in some instances control logic will be used to combine information from multiple sensors to generate an alarm.

The details of the logic required for diagnostics will be developed during the submittal process once the specific items of equipment to be provided for the project are established, including make and model.

LEED Measurement and Verification Requirements

The IDUs and ODUs are provided with current transmitters that provide proof of operation, allow the operating state of the system to be determined, and support metering functions needed for measurement and verification purposes. See the metering sequence of operation and point list for additional information.

Run Time Accumulation

The proof of operation points also supports run time accumulation for each motor in the system. Run time shall be accumulated and archived. The graphic for each individual unit shall display the run time for that unit for the current day, the previous day, the month to date, and the year to date.

Typical IDU Zone Sequences of Operation

DOAS Units Associated with IDUs

The IDU's associated with each of the four DOAS systems are as follows:

<u>DOAS-1</u>	<u>DOAS-2</u>	<u>DOAS-3</u>	<u>DOAS-4</u>
IDU-1.2	IDU-1.14	IDU-1.4	IDU-1.8
IDU-1.3	IDU-1.15	IDU-1.5	IDU-1.9
	IDU-2.1	IDU-1.6	IDU-1.10
	IDU-2.2	IDU-1.7	IDU-1.11
	IDU-2.3	IDU-2.6	
	IDU-2.4A	IDU-2.7	
	IDU-2.4B	IDU-2.9	
	IDU-2.5		

IDU-2.6 In addition, there are three IDUs that are associated with Heat Recovery Ventilators (HRV) as follows:

- IDU-1.1 - Room 105 - Source Control Work Room is associated with HRV-3
- IDU-1.12 - Room 161 - Warehouse Office is associated with HRV-1
- IDU-1.13 - Room 164 - Tool Office is associated with HRV-2

Note that there is no IDU-2.8.

The association between an IDU and a DOAS unit or HRV unit is created by the physical arrangement of the ductwork. In other words, the IDUs associated with a given DOAS or HRV unit have outdoor air delivered to the zone(s) they serve by a connection from the supply duct of their associated DOAS or HRV unit.

Similarly, exhaust air is returned from the IDU zone to the DOAS or HRV unit to allow energy to be recovered when appropriate, based on the current climate conditions, building operating state, and utility rate structure.

The DOAS/HRV unit's function is to deliver the ventilation air required by the zone when it is occupied. Thus, the DOAS and HRV systems will not run during a warm-up or cool down cycle. They will also not run during set back or set up cycles if the IDU(s) are only running to maintain the space temperature with-in the set back or set up limits and there are no occupants in the zone served by the IDU.

See the DOAS and HRV sequence of operation for additional information regarding the DOAS and HRV system control.

IDU Zone Types

There are several different zone configurations associated with the IDUs as follows:

- Zone type 1 - Single zone ducted fan coil unit
- Zone type 2 - Multiple zone ducted fan coil unit
- Zone type 3 - Multiple zone VAV ducted fan coil unit
- Zone type 4 - Single zone ceiling cassette fan coil unit
- Zone type 5 - Single zone multiple ceiling cassette fan coil units
- Zone type 6 - Single zone wall mounted fan coil unit
- Zone Type 7 - Single space, single zone wall mounted IDU with a heat recovery ventilator
- Zone Type 8 - Single space, single zone ducted IDU with destratification fans
- Zone Type 9 - Single space, single zone, ceiling cassette IDU with a dedicated exhaust fan and hood and a dedicated make-up air system
- Zone Type 10 - Single space, single zone ducted IDU with dedicated exhaust

Many of the zones have common sequence requirements as described in the following section.

Operating Requirements Common to All Zone Types

Indoor Unit Function Switch Setting Coordination

Coordinate with the Mitsubishi start-up technician for the following indoor unit function settings.

- Set the IDU to not restart automatically after a power failure to allow the Siemens power failure recovery sequence to manage the restart.
- For ducted units, set the external static switch for the appropriate external duct static pressure requirement. An initial setting can be made based on the design documents but the final setting should be coordinated with the testing and balancing results during the commissioning process.
- Unless otherwise noted, set the IDUs up to use the remote controller sensor for space temperature control.
  - External static pressure setting matches the requirements for the unit

Occupied Setpoints

The following setpoints shall be used for occupied hours:

- Cooling - nominal setpoint of 75°F with an occupant adjustment range of +/-2°F around the nominal setpoint.
- Heating - nominal set point of 70°F with an occupant adjustment range of +/-2°F around the nominal setpoint.

The occupant range of adjustment shall be restricted to the bands indicated above via the programmable settings of the Mitsubishi PAR-U01MEDU remote controller. See the IDU Remote Controller Features and Settings table for additional information.

Unoccupied Setpoints

The following initial setpoints shall be used for unoccupied hours:

- Cooling - nominal setpoint of 85°F with no occupant adjustment capability.
- Heating - nominal setpoint of 60°F with no occupant adjustment capability.

Once a space has achieved steady state operating conditions at the desired operating temperature, an investment has been made in storing energy in the thermal mass represented by the space and its contents at the steady-state condition. Setback and setup cycles are a balancing act between the cost of replacing the stored energy that will be lost if the space temperature is allowed to drift and the parasitic energy and time it takes to replace that lost energy and recover the space from the setback/setup condition to the desired condition.

The unoccupied set points shall be fine-tuned via the commissioning process during the first year of operation to balance the recovery time required to return the space to the nominal occupied set point against the amount of operating time required to unoccupied hours to maintain the set-back temperature.

Recovery from Power Failure

The VRF equipment shall be included in the power failure recovery sequence provided for the facility. Each VRF IDU shall have a start order set point and a time delay set point. See the Power Failure Recovery Sequence of Operation for additional details.

Note that starting the first VRF IDU will also enable the operation of the ODUs, which are significant loads.

Fire alarm shut down

A hardwired point from the fire alarm system provides an input to the DDC systems. The DDC system shall use this input to perform a courtesy shutdown of all of the HVAC equipment if there is a fire alarm. This is not a code requirement but is being provided as an added measure of protection against the spread of smoke in the event of a fire.

Specifically, when a fire alarm is detected, all of the VRF IDUs shall be commanded to the off state and restart from the local controller shall be prohibited. After the fire alarm is cleared, the VRF IDUs shall be allowed to resume normal operation based on the current operating condition. The unit starts shall be staggered and shall use the logic associated with the Power Failure Recovery sequence for order of start and timing.

Drain Pan Alarm

Furnish and install the optional Mitsubishi DPLS2 drain pan level sensor and connect the wiring harnesses to shut down the VRF unit if the drain pan is about to overflow per the manufacturer's instructions. The level switch is powered by an internal 20-year life cycle battery.

For each IDU graphic, provide an indicator showing the remaining years of service available using a countdown timer that is started and begins counting down based on the date of installation. Include the installation date below the countdown timer.

Operating Requirements Common to Multiple Zone Types but Not All Zone Types

These features apply to multiple zone types as indicated, but not to all zone types.

Time Driven Schedules

Unless otherwise indicated, the IDUs shall be controlled via an optimized start-stop schedule with warm-up and cool-down cycles.

Each IDU shall be capable of having its own schedule with the hours of operation fully adjustable by the operators. The initial schedule settings for each zone shall be as indicated below and shall be fine-tuned to the Owner's specific requirements during the control system submittal review process.

Occupancy Driven Schedules

The following zones are to be provided with occupancy driven schedules based on the occupancy sensors that are incorporated in the Mitsubishi PAR-U01MEDU controller.

- Breakout 210
- Conference 230
- Conference 231

Occupied Cycle Temperature Control

When the occupancy sensor serving these zones detects motion the IDU(s) serving the area shall be enabled and allowed to operate to actively control the space temperature at the occupied heating and cooling set points (70°F and 75°F respectively, both adjustable +/-2°F). When a cycle is triggered, the system will remain in the occupied cycle for a minimum of 15 minutes (adjustable) from the last time that motion is detected.

Unoccupied Cycle Temperature Control During Normal Hours

These zones shall have two different unoccupied cycle set back/set up temperature set. If the zone is unoccupied and all of the other zones associated with the DOAS unit serving it are occupied, then the set back/set up temperature set points shall be set to allow the unit to shut down but also to minimize the drift from the normal occupied set points so that the zone can recover quickly if a zone level occupancy cycle is triggered.

At the end of an occupied cycle, the IDU(s) serving the area are turned off and the temperature in the area is allowed to drift between the unoccupied heating and cooling set points. Each zone shall have:

- A zone-specific unoccupied set-up set point that will be set to 1°F (adjustable) above the current occupied cooling set point, and
- A zone-specific unoccupied set-back set point that will be set to 1°F (adjustable) below the current occupied heating set point.


If the zone temperature is between the unoccupied set points, no active cooling or heating shall be provided. But, if the temperature drifts outside the set-back temperature range, the unit associated with the space shall be placed in occupied mode and operated until the space temperature is driven back inside the set back/set up range at which time the unit shall return to the unoccupied mode.

Ventilation air will be provided to the zones by the DOAS units serving them any time the DOAS runs and will continue to be provided even if the zone is unoccupied. Continuing to supply ventilation air, along with a fairly narrow set-back/set-up range (1°F above the maximum set point and 1°F below the minimum set point) is intended to minimize the pull-down time required when a zone goes occupied based on an occupancy sensor driven trigger.


Functional testing technique shall be used to fine tune the set back and set up temperatures for the zones with occupancy-based schedule during the commissioning and warranty period. Test results shall be used to optimize the initial set points provided and tailor them to the thermal mass (stored energy) and HVAC process energy associated with the zone served.

Figure 6 (see sheet sheet MI.8.03-4) illustrates how the zones associated with DOAS-2 would operate over the course of a typical day, including the interaction of the zones and DOAS-2 and reflects the design intent for the integration of zones with time driven schedules, occupancy driven schedules and the DOAS system supporting them.


(Continued on sheet MI.8.03-4)



6760 Alexander Bell Drive, Suite 200  
Columbia, MD 21046  
Phone: (410) 290-0900



KEY PLAN



APPROVED BY  
Department of Finance and Administrative Services  
CITY OF SEATTLE

DOVE ALBERG      DATE \_\_\_\_\_  
Director  
Capital Development & Construction Management


APPROVED FOR ADVERTISING  
LIZ ALZEER  
City Purchasing and Contracting Services  
SEATTLE, WA      00 \_\_\_\_\_

By \_\_\_\_\_  
City Purchasing and Contracting Services Director

PROJECT-NO	FAS 2016-054
DRAWN	DAS
CHECKED BY	CBM
DATE	10/04/18
REVISIONS	DATE
△	
△	
△	
△	
△	
VPI-NO	730-641
SHEET TITLE VRF System Sequence of Operation Part 4	
SHEET NUMBER MI.8.03-4	



DOAS-2 Scheduled Operation Example



VRF System Sequence of Operation (Continued from MI.8.03-4)

Filter Status Points- Ducted Fan Coil IDUs

The following ducted fan coil type IDUs are being provided with separate filter boxes designed to accommodate MERV 13 filters in support of LEED Indoor Air Quality (IAQ) requirements.

- IDU 1.2
- IDU 1.3
- IDU 1.4
- IDU 1.5
- IDU 1.6

Page 1 of 1 of Sheet Schedule Example of File IDU-DOAS Schedule v4.xlsx  
Printed on 10/16/2018 at 3:53 PM  
IDU 2.1

- IDU 2.2
- IDU 2.3
- IDU 2.7
- IDU 2.9

Under the Mechanical Instrumentation work, as indicated in the point list, these filter boxes will be shall be provided with stand-alone filter differential pressure sensors that are wired directly to the Siemens system. For these units, the BACnet filter points shall be disabled and shall not be mapped across the BACnet interface.

The design intent behind this decision is for the filters to be changed based on pressure drop, which approaches changing them

based on best life cycle cost. The higher performance filters have a higher first cost and thus, maximizing their service life by not changing them until the pressure drop warrants it was deemed desirable. Monitoring pressure drop also provides more positive proof that the filters are in place and functional and that the intended IAQ benefit is being realized.

The filter change set points shall be coordinated during the start-up and commissioning process to match the capabilities of the IDU fans in terms of ensuring they deliver the required air flows at a minimum with dirty filters.


Carbon Dioxide Monitoring

The following zones are provided with CO2 monitors for the purposes of compliance with LEED Indoor Air Quality credits.


- Dispatch A (Room 100),
  - Dispatch B (Room 101),
  - Break Out (Room 124),
  - Break Out (Room 141),
  - Break Out (Room 142),
  - Conference (Room 143),
  - Lunch Room (Room 144),
  - Break Out (Room 210),
  - Break Out (Room 212),
  - Conference (Room 230),
- (Continued on MI.0.03-6)



6760 Alexander Bell Drive, Suite 200  
Columbia, MD 21046  
Phone: (410) 290-0900



KEY PLAN



APPROVED BY  
Department of Finance and Administrative Services  
CITY OF SEATTLE

DOVE ALBERG DATE  
Capital Development & Construction Management

APPROVED FOR ADVERTISING  
LIZ ALZEER  
City Purchasing and Contracting Services  
SEATTLE, WA 20

BY  
City Purchasing and Contracting Services Director

PROJECT-NO FAS 2016-054

DRAWN DAS

CHECKED BY CBM

DATE 10/04/18

REVISIONS DATE

△

△

△

△

△

△

VPI-NO 790-641

SHEET TITLE

VRF System Sequence

of Operation Part 5

SHEET NUMBER

MI.8.03-5



VRF System Sequence of Operation (Continued from MI.8.03-5)

- Conference (Room 231),
- Break Out (Room 241), and
- Break Out (Room 244).

The manufacturer's recommended calibration kit for the make(s) and model(s) of CO2 sensors furnished for the project shall be provided as part of the turn-over package and the Facility Operations staff who will be servicing the facility shall be trained regarding its use as part of the training package.

Zone Specific Features and Operating Requirements

The following paragraphs describe the different zone types and zone type specific sequence requirements.

Zone Type 1 - Single Space, Single Zone or Open Space, Ducted IDU

This zone configuration applies to the following IUDs.

1. IDU-1.4 - Room 111 - Lobby
2. IDU-1.7 - Room 145 - Shared Support
3. IDU-1.8 - Room 150 - Women's Locker
4. IDU-1.10 - Room 151 - Men's Locker Room
5. IDU-2.1 - Room 211 - Open Office
6. IDU-2.3 - Room 200 - Hallway, Room 212 - Breakout
7. IDU-2.9 - Room 213 - Open Office

The Mitsubishi controller for these zones provides direct contr

For these zones, the zone temperature shall be be controlled by a wired, multifunction controller mounted as shown on the floor plans. When an occupancy sensor in these areas detects motion the IDU(s) serving the area are turned on and allowed to operate to actively control the space temperature at the occupied heating and cooling set points (70°F and 75°F respectively, both adjustable +/-2°F). When a cycle is triggered, the system will remain in the occupied cycle for a minimum of 15 minutes (adjustable) from the last time that motion is detected.

At the end of an occupied cycle, the IDU(s) serving the area are turned off and the temperature in the area is allowed to drift between the unoccupied heating and cooling set points. Each zone shall have:

- A zone-specific unoccupied set-up set point that will be set to 1°F (adjustable) above the current occupied cooling set point, and
- A zone-specific unoccupied set-back set point that will be set to 1°F (adjustable) below the current occupied heating set point.

If the zone temperature is between the unoccupied set points, no active cooling or heating shall be provided. But, if the temperature drifts outside the set-back temperature range, the unit associated with the space shall be placed in occupied mode and operated until the space temperature is driven back inside the set back/set up range at which time the unit shall return to the unoccupied mode.

Ventilation air will be provided to the zones by the DOAS units serving them any time the DOAS runs and will continue to be provided even if the zone is unoccupied. Continuing to supply ventilation air, along with a fairly narrow set-back/set-up range (1°F above the maximum set point and 1°F below the minimum set point) is intended to minimize the pull-down time required when a zone goes occupied based on an occupancy sensor driven trigger.

Functional testing technique shall be used to fine tune the set back and set up temperatures for the zones with occupancy-based schedule during the commissioning and warranty period. Test results shall be used to optimize the initial set points provided and tailor them to the thermal mass (stored energy) and HVAC process energy associated with the zone served.

Zone Type 2 - Multiple Space, Single Zone Ducted IDU

This zone configuration applies to the following IUDs.

1. IDU-1.14 - Room 120 - Hallway, Room 124 - Break-out, Room 127 - Recovery Room, Room 128 - Restroom, Room 129 - Janitor's Closet, and Room 131 - Waste/Recycle

Zone Type 3 - Multiple Space, Multiple Zone Variable Air Volume (VAV) Ducted IDU

This zone configuration applies to the following IUDs.

1. IDU-1.5 - Room 140 - ERC, Room 141 - Break-out, Room 142 - Breakout and Room 143 - Conference
2. IDU-2.2 - Room 221 - Office, Room 222 - Office, Room 223 - Office, and Room 221 - Office
3. IDU-2.7 - Room 241 - Breakout, Room 242 - Office, Room 243 - Office, and Room 244 - Breakout

Zone Type 4 - Single Space, Single Zone Ceiling Cassette IDU

This zone configuration applies to the following IUDs.

1. IDU-1.6 - Room 144 - Lunch Room
2. IDU-2.5 - Room 231 - Conference
3. IDU-2.6 - Room 210 - Breakout

Zone Type 5 - Single Space, Single Zone, Multiple Ceiling Cassette IDUs

This zone configuration applies to the following IUDs.

1. IDU-2.4A - Room 230 - Conference
2. IDU-2.4B - Room 230 - Conference

Zone Type 6 - Single Space, Single Zone Wall Mounted IDU with Dedicated Exhaust

This zone configuration applies to the following IUDs.

1. IDU-1.15 - Room 130 - CCTV Workroom

Zone Type 7 - Single Space, Single Zone Wall Mounted IDU with a Heat Recovery Ventilator

This zone configuration applies to the following IUDs.

1. IDU-1.12 - Room 161 - Warehouse Office
2. IDU-1.13 - Room 164 - Tool Office

Zone Type 8 - Single Space, Single Zone Ducted IDU with Destratification Fans

This zone configuration applies to the following IUDs.

1. IDU-1.2 - Room 101 - Dispatch B
2. IDU-1.3 - Room 100 - Dispatch A

This

Zone Type 9 - Single Space, Single Zone, Ceiling Cassette IDU with a Dedicated Exhaust Fan and Hood and a Dedicated Make-up Air System, with Ventilation Air from a Heat Recovery Ventilator

This zone configuration applies to the following IUDs.

1. IDU-1.1 - Room 108 - Source Control Work Room

Zone Type 10 - Single Space, Single Zone Ducted IDU with Dedicated Exhaust

This zone configuration applies to the following IUDs.


1. IDU-1.9 - Room 152 - Women's Drying Room
2. IDU-1.11 - Room 153 - Men's Drying Room



Facility Dynamics  
ENGINEERING

6760 Alexander Bell Drive, Suite 200  
Columbia, MD 21046  
Phone: (410) 290-0900





<b>APPROVED BY</b> Department of Finance and Administrative Services CITY OF SEATTLE	
DOVE ALBERG	DATE
Director Capital Development & Construction Management	
<b>APPROVED FOR ADVERTISING</b> LIZ ALZEER	
City Purchasing and Contracting Services	
SEATTLE, WA	20
BY City Purchasing and Contracting Services Director	
PROJECT-NO	FAS 2016-054
DRAWN	DAS
CHECKED BY	CBM
DATE	10/04/18
REVISIONS	DATE
△	
△	
△	
△	
△	
VPI-NO	790-641
SHEET TITLE VRF System Sequence of Operation Part 6	
SHEET NUMBER  MI.8.03-6	